#### **Hudson River PCBs Site**

### **Engineering Performance Standards For Dredging**

Presentation to Peer Review Panel





Malcolm Pirnie, Inc.
TAMS, an EarthTech Company
October 15-16, 2003

# Synergistic Characteristics Performance Standard Interactions Promote Protection and Productivity

Donald Hayes, PhD, PE University of Utah



#### **Performance Standards**

### Purpose: establish boundaries for project implementation

- Consistent with project objectives
- Protect resource & human health
- Require sufficient data collection to evaluate Phase 1

#### **Development Philosophy**

- Provide design flexibility
- Allow field decisions where possible
- Avoid over-specification to allow innovative project design & implementation as appropriate

#### **Alternative Philosophy**

#### Prescriptive Standards

- Reduce flexibility
- Discourage innovation
- Force premature decisions

#### **Development Approach**

- Establish solid technical basis for each standard
- Subject to a test case to ensure project objectives met Practicable application for each standard

#### **Technical Team**

- Large, highly-qualified development team assembled
  - Diverse backgrounds & perspectives
  - Extensive knowledge of upper Hudson River System

#### Quality Review Team

- Leading experts in field
- Functioned independently from development team
- Fully integrated into process
- Role was to "challenge" the standards

#### Current Focus - Phase 1

- Data collection is important component of Phase 1
  - Recognize limitations of available data
  - Obtain site-specific data required for refining project design
  - Address concerns of local citizens
- Satisfactory performance during Phase 1 will likely lead to streamlined standards for Phase 2


#### **Natural Tension**

- Expeditious project completion leads to more rapid resource recovery (Productivity Standard)
- Remedial project design must not further damage the resource, thereby jeopardizing project benefits (Resuspension Standard)
- Post-project conditions must meet or exceed project objectives (Residuals Standard)

#### **False Notions**

- Increased production yields increased residual and resuspension losses
- Corrollary
  - Restricting a dredging operation minimizes residuals and decreases resuspension losses

#### **Resuspension Trends**



**DREDGE PRODUCTION** 

#### Residuals

- Processes regarding how and why residuals occur are poorly understood
- Normal dredging operations should result in least residual sediment
- Excessively aggressive dredging may increase residuals
- Sediment conditions and equipment type are important

### Performance Standard Interactions

#### **Productivity Standard**

- Establishes a progress schedule to meet project objectives
- Productivity schedule based upon
  - Conventional equipment
  - Conservative production estimates
- Proper design & equipment selection should lead to higher production rates

#### Residuals Standard

- Recognizes
  - Inability of dredges to precisely remove contaminated sediment shown during previous projects
  - Limited effectiveness of repeated dredging attempt with same equipment

#### Residuals Standard (cont'd)

- Repeated dredging attempts detrimental to productivity
  - 2 additional attempts maximum during Phase 1 (after inventory removed)
  - Definitive process allows field decisions

#### Resuspension Standard

- Routine monitoring
  - Baseline data collection
- Evaluation Level
  - Properly designed operation should remain at or below this level
- Concern Level
  - Increases monitoring to identify source of resuspension

#### Resuspension Standard (cont'd)

- Control Level
  - Implements actions to avoid temporary cessation of operations
- Threshold exceeded
  - Temporary cessation of operations

#### **Data Collection**

- Essential component of Phase 1, particularly at Evaluation & Concern Levels
  - Comparison to action levels
  - Identify mechanism of release
  - Identify TSS turbidity relationship
- Automated monitoring and data evaluation encouraged

## Intricacies Within The Standards

#### **Drinking Water Protection**

- 500 ng/l standard maintained in river
- Additional treatment will further reduce concentration
- Lag time allows adequate notification details will be in CHASP
- Early notification by using TSS as a surrogate

#### Redredging requirements streamlined

- When a CU is non-compliant because of one or a few nodes, the CU can be brought into compliance by:
  - Redredging areas of concern
    - Guidance for area definition provided
  - Capping areas of concern
    - Remaining area must be compliant

#### **Aggregating Small Dredging Areas**

- Proximate non-contiguous dredging areas < 5 ac can be tested as a single contiguous area (i.e. only 40 samples required)
- If non-targeted areas are contained within a barrier, a plan to either protect or sample non-targeted areas must be submitted.

#### Resuspension Monitoring

- Balanced between sampling requirements and data needs
- Automated sampling methods encouraged whenever they can meet the DQOs
- Split-phase sampling
  - Required to address concern over dissolved releases at the point of dredging
  - Since sampling is more difficult and expensive, not required in routine monitoring

#### **Flexibility**

- Redredge, Backfill, or Cap decisions for individual areas left to design and field operation based upon technical feasibility
- Capping within navigation channel
  - Discouraged, but allowed if
  - Overdredged to accommodate cap thickness
  - Indicator layer installed to protect the cap
- Non-contiguous areas can be backfilled/closed as long as they are compliant within themselves

#### Recharacterization

- Post-dredging samples (0-6") for a CU are the basis to determine if an investigation of additional inventory is needed
- Mean > 6 ppm AND Median > 6 ppm
  - Must recharacterize entire CU (deeper samples), then redredge to remove additional inventory located
- Mean > 6 ppm AND Median < 6 ppm</p>
  - Must recharacterize only areas that seem to have inventory, then redredge to remove additional inventory located

#### Conclusions

- Standards have been developed through a thorough & reasoned process
  - Considered input from QRT, trustees, GE, and public
- Aim is for a constructible project that accomplishes stated objectives
- Standards provide a framework that allows for innovation and a unique approach to the problem
- We look forward to your independent review

# Important Questions for the Peer Review Team to Consider

#### **Are The Standards**

- Technically sound?
- Reasonable and appropriate?
- Balanced?
- Implementable?

#### **Are The Standards**

- Technically adequate?
- Properly documented?
- Developed so as to satisfy established quality requirements?
- Developed so as to yield scientifically valid and credible conclusions?