#### Appendix P Other Screened Dredging Technologies



FIGURE P-1. BELLC BONACAVOR. BAYOU BONFOUCA, SLIDELL, LOUISIANA

#### PROFILING GRAB



#### Efficient dredging of polluted bed material

The profiling grab, which has a horizontal closing action, is an efficient dredging tool developed by Boskatis for the removal of polluted bed material in ports and waterways. Great accuracy is required for this type of selective dredging. If dumping or processing costs are to be contained, only polluted spoil must be removed and not the uncontaminat material which should be left in space.

The profiling grab is designed to dredge in layers (the thinnest layers if necessary) and without spillage or muddying of the water. The volume to be recovered or processed is consequently kept to a minimum.

Polluted bed material often contains substantial quantities of large items of rubbish. Fitted an hydrautic crane, the profiling grab has no difficulty in handling this kind of waste.


Boskalis has successfully used the profiling grab on numerous clean-up projects in the Netherlands, at Elburg, Werneldinge, Terneuzen and Tiel, and on the Zuid-Willemsvaart canal.



#### Boskalis Dolman by

's-Gravenweg 399-405
P.O. Box 4466, 3006 AL. Rotterdam
The Netherlands
Telephone +31 (0)10 288 28 00
Telefax +31 (0)10 288 28 10

# THE UNIQUE BONACAVOR



What once was a beau southeastern Louisiana, turned into an environmental disaster. A creosote plant operating on the banks of Bayou Bonfouca since 1892, burned down in 1970 - spilling large amounts of toxic creosote into the bayou. By the 1980's, the spill had contaminated over 55 acres of bottom material. The site was subsequently placed on the EPA's Superfund priorities list, and has since become the largest Superfund Project ever awarded.


The specifications for the "Bayou Bonfouca Superfund Remediation Project" required an extremely narrow excavation tolerance. Such extreme tolerances were necessary in order to reduce or eliminate overdredging, and hold the quantity and cost of sediment treatment to the project estimates. Another challenge presented was protecting personnel and property from exposure to the contaminated sediments during excavation and transportation to the treatment facility. In addition, the sediment treatment process required the removal of contaminated sediments in as close to in situ state as possible.


Bean responded to these challenges by designing and building the Bonacavor. With innovations in cutter location, dredge positioning, sediment processing and transportation, the Bonacavor and Bean successfully conquered the challenges presented at Bayou Bonfouca.





FIGURE P-2. NORMROCK INDUSTRIES AMPHIBEX





From time immemorial, humankind has used its ingenuity to exploit the planet's resources. But in these enlightened times, we also know that we must treat those resources with respect. The **Amphibex** from Normrock Industries is an amphibious excavator designed to meet both needs, wedding state-of-the-art performance with environmentally sound operation.

The culmination of many years of research and innovation, the **Amphibex** is an amphibious excavator specially designed to operate in an aquatic environment. What makes it different? Its versatility, power, ruggedness, mobility, sophisticated positioning equipment, and very low capital and operational costs.


The Quebec-designed and built Amphibex is suitable for a wide range of uses in all types of water:


- cleaning and restoring contaminated waterways
- · installing water pipes, pipelines and submarine cables
- · cleaning wastewater treatment ponds
- preventing and breaking up ice jams
- · controlling vegetation
- developing peat lands
- · creating wildlife habitats



The Amphibex's cab meets the highest standards of comfort and visibility. It is equipped with two deluxe seats, easy-to-reach controls, side windows that can be opened, and a range of standard and optional accessories. The Amphibex's supportional sophisticated positioning system, developed by Normrock Industries, is particularly useful for clean-up

operations. It can pinpoint the exact location where the machine is to set to work, by night or day. A graphical display system enables the operator to position the bucket with a high degree of precision.








The Amphibex's powerful hydraulic pumping system can proper highly concentrated solid residues over distances of more than one kilometre.

The Amphithex can be equipped with an array of accessories bucket, cutterhead equipped pump bucket, rake etc.) to enable it to perform the job at hand.



General Description

Maximum length 35 7" (10.85 m) Working weight appr. 24.25 tons) (22 metric tens Transport length 47 2" (12.85 m) Transport width 4F 6" (3.5 m) Transport beight 10° 6" (3.2 m) Sailing speed appr. 8 knots Stabilizers (rear) Draught 2' (60 cm)

Engine

Detroit diesel, Series 40 see options

Model Cylinders

Maximum HP

Maximum torque

170: #2/16/61/NM) at 1700 non 30E 1050/16 (1324 NM) at 1300 (pt

fullesoff it e.t.m.

12 vote are Deli

Alternator Batteries (2)

Delco/Rimy 12 vots Delco/Remy 100 amp Delco/Remy 225 amps/hr.

Fuel Tank Capacity To Transparence u

#### Hydraulics

2 Gear pump Maximum working pressure

90 gai (340 L)/min.

Variable displacement pump

Maximum working pressure Hydraulic system capacity

Hydraulic oil vegetable base or mineral

132.09 gal (500 L)

#### Standard Equipment

- Corrosion resistant one-piece body divided into nine wateruight compartments.
- Two rear stabilizers; equipped with hydraulic at tilling. cylinders. Depth control by means of hydraulic cylinder/ mechanical control
- Two front stabilizers with detachable floats and 1 recopyable spads
- Propulsion by stem hydrautically height controlled
- . Output connection SALZOC's ax discharge (X 1) gal/s (2 X 125 L/s) - bucket with horizontal cutter
- Quick coupling for working attachment
- Life saving equipment

#### Excavator

Maximum bucket reach

21'6" (6.5 m) to 25' 9" (7. through 180°

Maximum depth with telescopic arm 21'5" (6.528 Breakout force (from bucket cyl.) depends on selec option

Digging force (from bucket cyt.) depends on selec option

#### Optional Equipment

- Backoe buckets, 0.5 yd\*(400 L) and 1 yd\* (800 L)
- Discharge spout for side casting
- Rake -width 9' 11" (3 m)
- Discharge pipe 8" (200 mm) X 20' (6 m) with aluminum mounting flanges (SAE200) connected
- Air compressor, hydraulically driven for accessor
- Navigation and dredging lights, telescopic and fu
- · Winch
- → Crane
- \* Tools
- Heating system
- . Air conditioning

For customized equipment for your special needs, please consult manufacturer.

3360, boul. des Entreprises, Terrebonne (Quebec), Canada J6X 4J8 Tel.: ( 477-5132 • 1-800-830-9080 • Fax: ( 477-2020 http://www.normrock.ca

Printed in Casedle



FIGURE P-3. ELLICOTT INTERNATIONAL SERIES 370 HP

THE NEW ELLICOTT

# Series 7/JP Drift



### TUNNLIN UL:



## STANDARD SPECIFICATIONS SERIES STANDARD

GENERAL	- Salvarenessa	
Overall Length (with ladder)	17.5 m	57.5 feet
Overall Width	3.7 m	12.0 feet
Hull Depth	1.2 m	4.0 feet
Mean Draft (with fuel)	0.81 m	2.67 feet
Spud Length	8.9 m	29.1 feet
Spud Weight (each)	816 kg	1800 lb.
Total Dredge Dry Weight	25400 kg	56000 Rb.
Suction Pipe Diameter	305 mm	12 in.
Discharge Pipe Diameter	254 mm	10 in.
OPERATING CONDITIONS		
Digging Depth		
Minimum	0.9 m	3.0 foot
Maximum	6.1 m	20.0 feet
Maximum Channel Cut of Dredg	je	
@Minimum Digging Depth	22.2 m	73.0 feet
@Maximum Digging Depth	18.3 m	60.0 feet
PRIME MOVER		
Diesel Engine (radiator cooled)	Caterpillar	Caterpitar
Model	3406 B	3406 B
Maximum Operating RPM	1800	1800
Continuous Power (flywheel)	306 kW	410 SHP
SWING WINCHES		
Line Pull (1st layer)	3629 kg	8000 fb.
Line Speed (1st layer)	22.9 m/min.	75 FPM
Wire Size	12.7 mm	1/2 in.
Drum Capacity (maximum)	91 m	300 feet
Drum Capacity (standard)	61 m	200 feet

CUTTER MODULE		
Cutter Force	1787 kg	3940 lb.
Cutting Force (per unit length of blade)	34.3 kg/cm	192 lb./m.
Cutter Diameter	800 mm	31.5 in.
Cutter Rating	30 kW	40.0 SHP
Cutter Speed	0-39 RPM	0-39 RPM
Number of Blades	6	6
SLURRY PUMP		
Impeller Diameter	686 mm	27 in.
Particle Clearance	152 mm	6 in dia
Maximum RPM	845	845
LADDER HOIST CYLINDER		
Extending Force	4452 kg	9815 lb.
Retracting Force	18700 kg	41225 lb.
Lowering Speed at Cutter	24.7 m/min	81 FPM
Hoisting Speed at Cutter	29.6 m/min	97 FPM
SPUD HOIST	CYLINDER	CYLINDER
Lifting Force (at spud)	3266 kg	7200 lb.
Lowering Speed	Free Fall	Free Fall
ELECTRICAL SYSTEM		
Battery	24 V	24 V
CAPACITIES		1000
Fuel	3028 Liters	800 gal.
Hydrautic Oil	871 Liters	230 gal.


Complete dredge outlitting equipment available including polyethylene pipeline and booster pumps.

CONVERSION FOR VARIOUS IN-SITU S.G.		
DENSITY	MULTIPLIER	
2.10	1.000	
2.00	1.100	
1.95	1.156	
1.90	1.222	
1.85	1.294	
1.80	1.375	

#### SERIES 370HP CALCULATED DUTPUT CURVES

Material In-situ Density = 2.1
For material In-situ values other than 2.1, see conversion chart at left.
CALCULATED OUTPUT CURVES BASED ON 12-INCH (365 mm) PIPELINE:

- # 12" (305mm) Diameter Suction
- # 12" (305mm) Diameter Discharge
- 20" (6.09m) Digging Depth
- 10' (3.05m) Terminal Elevation
- 27" (685.8mm) Diameter Impeller ■ Maximum RPM = 845 SHP = 329



Output curves for all applications are computer generated on a program specifically designed for this purpose. The calculated output curves represent our best engineering knowledge and reflect the output pumping capability of the dredge under the conditions stated. In actual practice, the material varies from free-flowing, easily excavated material, to compacted and/or difficult excavations. nature of the material and job conditions must be considered when estimating actual outputs. The outputs are indicated for your reference and are not guaranteed.

#### WARRANTY

Ellicott warrants its equipment only in accordance with its printed warranty conditions, the latest copy of which will be forwarded to you promptly upon written request. No other warranties are provided.

The specifications shown in this brochure are subject to change due to improvements or design modifications required during construction, or the addition of equipment not described in the specifications.