

---

*Draft*

# **Sediment Removal Work Plan**

Prepared for  
**Tyco Fire Products LP**

December 2010

**CH2MHILL®**

# Sediment Removal Work Plan

Document Control No. 405439-061

Revision 0

Prepared by:



December 2010

Approved By:

A handwritten signature in black ink, appearing to read "Jeffrey H. Blank".

Project Manager

12/01/2010

Date

# Contents

---

<b>Acronyms and Abbreviations .....</b>	<b>vii</b>
<b>1. Introduction.....</b>	<b>1-1</b>
1.1 Site Description and History .....	1-2
1.2 Previous Facility Investigations and Corrective Actions .....	1-3
1.2.1 Investigation Activities .....	1-3
1.2.2 Corrective Measures in the Resource Conservation and Recovery Act Program.....	1-4
1.3 Menominee River Great Lakes Area of Concern.....	1-5
<b>2. Conceptual Site Model.....</b>	<b>2-1</b>
2.1 Generalized Stratigraphy and Groundwater Flow Direction.....	2-1
2.2 Historical Arsenic Transport Mechanisms .....	2-2
2.3 Sediment Characterization .....	2-2
2.3.1 Main Channel .....	2-3
2.3.2 Turning Basin .....	2-3
2.3.3 Transition Areas.....	2-3
2.3.4 6th Street Slip.....	2-3
2.3.5 South Channel .....	2-4
2.4 Arsenic Data .....	2-4
2.4.1 Soft Sediment.....	2-5
2.4.2 Semi-Consolidated Material.....	2-5
2.4.3 Glacial Till .....	2-6
2.4.4 Comparisons Across Layers .....	2-6
<b>3. Menominee River Sediment Removal Plan .....</b>	<b>3-1</b>
3.1 Project Objectives .....	3-1
3.2 Proposed SRWP Corrective Action Plan .....	3-1
3.2.1 Pre-Dredging Activities .....	3-2
3.2.2 Phase I Activities.....	3-2
3.2.3 Phase II Activities .....	3-3
3.2.4 Phase III Activities .....	3-4
3.2.5 Post-Dredging Activities.....	3-5
3.2.6 Phase IV Activities, Monitoring Natural Recovery.....	3-5
3.3 Design Components .....	3-5
3.3.1 Bathymetric and Sediment Thickness Surveys.....	3-5
3.3.2 Bulkhead/Shoreline Stability .....	3-5
3.3.3 Utilities .....	3-6
3.3.4 Arsenic Contamination Evaluation .....	3-6
<b>4. Corrective Action Design – Project Delivery Strategy .....</b>	<b>4-1</b>
4.1 Preliminary Design.....	4-1
4.2 Final Design .....	4-1
<b>5. Preliminary Design Approach, Assumptions, and Parameters .....</b>	<b>5-1</b>
5.1 Minimizing Environmental and Public Impacts .....	5-1

5.1.1	Planning and Permitting .....	5-1
5.1.2	Execution of Dredging Activities .....	5-2
5.2	Site Preparation and Mobilization .....	5-2
5.2.1	Site Preparation and Mobilization Activities .....	5-2
5.2.2	Asphalt Pad and Site Access Roadways .....	5-3
5.3	Mechanical Dredging.....	5-4
5.3.1	Dredging Equipment .....	5-5
5.3.2	Dredging Sequence .....	5-5
5.3.3	Dredging Process.....	5-5
5.3.4	Debris .....	5-6
5.3.5	Stabilization Reagents.....	5-6
5.3.6	Dredging Production Rate and Duration.....	5-7
5.3.7	Debris Handling .....	5-7
5.3.8	Dredging Positioning System .....	5-7
5.4	Dry Excavation - South Channel .....	5-7
5.4.1	Site Preparation and Dewatering .....	5-8
5.4.2	Excavation Activities.....	5-8
5.5	Dredged Material Disposal .....	5-8
5.6	Water Quality.....	5-9
5.6.1	River Water Quality .....	5-9
5.6.2	Wastewater from Stabilization and Decontamination Activities .....	5-10
5.7	Working Season and Hours of Operation.....	5-12
5.8	Decontamination and Site Restoration.....	5-12
<b>6.</b>	<b>Compliance with Applicable Requirements .....</b>	<b>6-1</b>
6.1	Rivers and Harbors Act .....	6-1
6.2	Clean Air Act.....	6-1
6.3	Clean Water Act.....	6-1
6.4	Soil Erosion and Sediment Control Permit .....	6-2
6.5	Endangered Species Act .....	6-2
6.6	National Historic Preservation Act.....	6-2
6.7	RCRA Regulations and Administrative Order on Consent .....	6-3
6.8	Coastal Zone Management Act .....	6-4
6.9	Wisconsin Chapter 30 permit .....	6-5
6.10	NPDES Stormwater Permit .....	6-5
6.11	City of Marinette Building Permit .....	6-5
6.12	OSHA Requirements.....	6-5
6.13	Waterway Markers Permit .....	6-5
6.14	Notice to Mariners.....	6-6
<b>7.</b>	<b>Performance Monitoring and Operations and Maintenance Requirements.....</b>	<b>7-1</b>
7.1	Water Quality Monitoring.....	7-1
7.1.1	River Water Quality Monitoring .....	7-1
7.1.2	Water Treatment System Monitoring.....	7-2
7.2	Post-Dredging Sediment Confirmation Sampling and Surveys.....	7-2
7.2.1	Surveys.....	7-2
7.2.2	Confirmation Sampling .....	7-2
7.3	Air Monitoring.....	7-3
<b>8.</b>	<b>Preliminary Construction Schedule .....</b>	<b>8-1</b>

9. Preliminary Cost Estimate .....9-1  
 10. Biddability, Constructability, and Operability Review .....10-1  
 11. References.....11-1

**Tables**

1 Summary Statistics – Nature and Extent of Arsenic Contamination  
 2 Sampled Locations with Clean Material Overlying Contaminated

**Figures**

1 Site Map  
 2 2010 Menominee River Investigation Sampling Locations  
 3 Conceptual Site model – Existing Conditions  
 4 Thickness of Soft Sediment  
 5 Thickness of Semi-consolidated Sands and Silts  
 6 Thickness of Glacial Till  
 7 Top of Bedrock Elevation Contours  
 8 Conceptual Site Model – Transport Mechanisms.  
 9 Top of Soft Sediment Elevation Contours  
 10 Top of Semi-consolidated Sands and Silts Elevation Contours  
 11 Top of Glacial Till Elevation Contours  
 12 Maximum Arsenic Concentration in Soft Sediment  
 13 Maximum Arsenic Concentration in Semi-consolidated Sands and Silts  
 14 Maximum Arsenic Concentration in Glacial Till  
 15 Sheet Piling Assessment - Cross Section Locations  
 16 Sheet Piling Assessment – Cross Section A-A’  
 17 Sheet Piling Assessment – Cross Section B-B’  
 18 Total Thickness of Arsenic Contaminated Material to be Removed

**Appendixes**

A Sediment Remediation Work Plans Evaluation Letter  
 B Analytical Data  
 C Sediment Removal Preliminary Design Drawings  
 D Project Schedule  
 E Compensation Schedule  
 F Cost Estimate

# Acronyms and Abbreviations

---

3D	three-dimensional
AMRSRP	<i>Alternative Menominee River Sediment Removal Plan</i>
AOC	Administrative Order on Consent
BMP	best management practice
CAA	Clean Air Act
CERCLA	Comprehensive Environmental Response, Compensation, and Liability Act
CFR	Code of Federal Regulations
CSM	conceptual site model
CWA	Clean Water Act
CZMA	Coastal Zone Management Act
EVS	Environmental Visualization System
GLAOC	Great Lakes Area of Concern
GLWQA	Great Lakes Water Quality Agreement
gpd	gallons per day
gpm	gallons per minute
GPS	global positioning system
GWCT	groundwater collection and treatment
IMI	interim measures investigation
MF	microfiltration
mg/kg	milligrams per kilogram
mg/L	milligrams per liter
MNR	monitored natural recovery
NHI	Natural Heritage Inventory
NOI	Notice of Intent
NPDES	National Pollutant Discharge Elimination System
O&M	operations and maintenance
OSHA	Occupational Safety and Health Administration

PCB	polychlorinated biphenyl
PM <sub>10</sub>	particulate matter finer than 10 micrometers in diameter and smaller
ppm	parts per million
RAP	remedial action plan
RCRA	Resource Conservation and Recovery Act
RFI	remedial facilities investigation
RO	reverse osmosis
SESC	soil erosion and sediment control
SRWP	sediment removal work plan
TCLP	toxicity characteristic leaching procedure
TSS	total suspended solids
Tyco	Tyco Fire Products LP
URS	URS Corporation
USACE	United States Army Corps of Engineers
USC	United States Code
USEPA	United States Environmental Protection Agency
USFWS	United States Fish and Wildlife Service
VBW	vertical barrier wall
WCMP	Wisconsin Coastal Management Program
WDNR	Wisconsin Department of Natural Resources
WPDES	Wisconsin Pollutant Discharge Elimination System
yd <sup>3</sup>	cubic yards

## SECTION 1

# Introduction

---

This Sediment Removal Work Plan (SRWP) is provided as required by the Administrative Order on Consent (AOC) between Tyco Fire Products LP (Tyco) and the U.S. Environmental Protection Agency (USEPA), dated February 26, 2009, and has been prepared in accordance with Section VI, 11, paragraph d (Page 6) of the AOC. The AOC addresses contamination present at the Tyco Fire Products LP manufacturing facility in Marinette, Wisconsin (hereafter referred to as the “site” or “facility”) and states that Tyco “will remove from the river all soft sediments and semi-consolidated sands and silts (semi-consolidated “material”) which contain arsenic concentrations greater than or equal to 50 ppm [parts per million]<sup>1</sup> of arsenic. Soft sediments are those sediments that overlay more consolidated materials (i.e., semi-consolidated [sands and] silts, lacustrine clays, glacial till, and bedrock). The depth of removal will not exceed the top of the glacial till layer.”

In Section VI, 11, paragraph e of the AOC, it is stipulated that Tyco “...will use MNR [monitored natural recovery] to remediate sediments remaining after sediment removal activities to a concentration of 20 ppm of arsenic.” If the 20 ppm arsenic concentration is not met within 10 years of completing sediment removal, an MNR alternative plan will be submitted for USEPA’s review (at the latest by November 1, 2023) indicating how the 20 ppm threshold will be achieved or how an equivalent level of protection (compared to 20 ppm) will be achieved. For purposes of discussion, this “baseline” set of activities described in Section VI, 11, paragraphs d and e of the AOC is referred to as the SRWP approach throughout this document.

Section VI, 11, paragraph f of the AOC makes allowance for an alternative sediment remediation approach. This alternative approach is detailed in the *Alternative Menominee River Sediment Removal Plan (AMRSRP)* that Tyco is submitting simultaneously with this SRWP. The alternative approach outlined in the AMRSRP is more environmentally protective and cost-effective than the SRWP approach as fully detailed in the *Sediment Remediation Work Plans Evaluation letter* dated December 1, 2010 – submitted to USEPA under separate cover and included as Appendix A to this document. The AMRSRP approach also addresses the technological impracticability of the SRWP approach.

For reasons that Tyco does not understand, USEPA insists that the AOC requires that Tyco submit a plan to address the Section VI, 11, paragraph d “dredge only” approach even if Tyco submits an alternative plan under Section VI, 11, paragraph f. Tyco does not agree with USEPA’s interpretation, but to avoid unnecessary disagreements, Tyco submits this SRWP that addresses the Section VI, 11, paragraph d approach. To be clear, however, Tyco is submitting this plan only because it facilitates the analysis and comparison of the SRWP to the AMRSWP. Tyco’s proposal is to conduct the AMRSWP approach.

---

<sup>1</sup> The abbreviation “ppm” refers to “parts per million.” This is the terminology used in the AOC. Milligrams per kilogram (mg/kg) is the concentration unit used in the rest of this SRWP, which is equivalent to ppm.

The major points of the *Sediment Remediation Work Plans Evaluation letter* (Appendix A to this SRWP) are summarized below:

- Approximately 5,000 cubic yards (yd<sup>3</sup>) of contaminated semi-consolidated sand and silt material with arsenic concentrations significantly greater than 50 milligrams per kilogram (mg/kg) provides necessary structural support for the existing sheet pile barrier wall that was installed to contain contamination beneath the onshore Tyco facility. Thus, the approach required by the AOC Section VI, 11, paragraph d is technically impracticable. This SRWP includes removal of the semi-consolidated material per the AOC – thereby affecting the structural integrity of the sheet pile barrier wall. The AMRSRP approach leaves this semi-consolidated material in place to eliminate risks to the structural integrity and proposes instead to cap this material.
- The AMRSRP approach eliminates an environmental risk from dredging the semi-consolidated material, which will release particle-associated and dissolved arsenic at levels that are likely to endanger ecological receptors in the Menominee River near to and downstream of the dredging areas during the period of dredging.
- Implementation of the SRWP is estimated to cost between \$23.7 million and \$50.8 million. Implementation of the AMRSRP approach is estimated to cost between \$11.7 million and \$25.1 million. Thus, the more environmentally protective alternative approach can be implemented for half the cost of the AOC-specified (SRWP) remedy.
- The AMRSRP approach protects human health and the environment by removing soft sediment with arsenic concentrations greater than or equal to 50 mg/kg and by capping semi-consolidated material with concentrations greater than or equal to 50 mg/kg. Capping and in-place containment of the semi-consolidated material is more environmentally protective in the short term as compared to dredging these materials included in the SRWP approach because the AMRSRP reduces the mass of arsenic that will be released during SRWP dredging. The AMRSRP approach also is more environmentally protective in the long term because the SRWP requires removal of contaminated semi-consolidated material that must remain in place to support the existing sheet pile barrier wall, while the AMRSRP caps this material, retains the structural integrity of the barrier wall, and provides ongoing and immediate protection to the Menominee River fisheries and other ecological receptors.

## 1.1 Site Description and History

The Tyco site is an active manufacturing facility in the city of Marinette in northeastern Wisconsin, adjacent to the south shore of the Menominee River (herein referred to as the facility or site; Figure 1). The property is bordered by the Menominee River to the north; the 6th Street Slip and City of Marinette property to the east; Water Street, City of Marinette property, Marinette School District property, and residential properties to the south; and Stanton Street and Marinette Marine Corporation to the west.

The facility consists of approximately 63 acres, including a manufacturing area on the western part of the property and an undeveloped area to the east, referred to as the “wetlands area.” A fence surrounds both parts of the facility, and access is restricted. The facility began operations in 1915, and manufacturing entities acquired by Tyco in the 1990s

produced cattle feed, refrigerants, and specialty chemicals. Arsenic-based agricultural herbicides were manufactured at the facility between 1957 and 1977. A byproduct of the manufacturing of this herbicide was a salt that contained approximately 2 percent arsenic by weight and was stockpiled at several locations on the property. Some of this arsenic subsequently entered site soil and groundwater. By 1978, the facility ceased production of arsenic-based herbicides, and since 1983 has produced only fire extinguishers and fire suppression systems.

## 1.2 Previous Facility Investigations and Corrective Actions

### 1.2.1 Investigation Activities

The facility and the associated contamination have been studied since 1974. Five major investigations have been performed to assess arsenic contamination in the Menominee River soft sediment, soil, and groundwater. The first was a sediment site assessment conducted in October 1996 (Dames & Moore 1996). The purpose of the assessment was to evaluate sediment contamination in the 8th Street Slip, the 6th Street Slip, the Turning Basin, and limited portions of the Menominee River. Elevated arsenic levels were detected in most of the sampled areas, with sediment containing arsenic concentrations up to 22,300 mg/kg in the 8th Street Slip and up to 18,200 mg/kg in the Turning Basin. Based on the results of this investigation, USEPA required that Tyco remove sediment within the 8th Street Slip.

The second sediment investigation was performed in 2000 as part of an interim measures investigation (IMI) and is summarized in the final IMI report appended to the *Summary of Findings Report* (URS Corporation [URS] 2001). The IMI included the following:

- Performing a hydrographic survey and sub-bottom profile survey to select soft sediment sampling locations within the Menominee River.
- Advancing 20 borings to bedrock within the Menominee River to assess total arsenic concentrations in soft sediment, semi-consolidated material, and glacial till. The borings were continuously sampled, with samples for laboratory analysis of arsenic collected from each 2-foot interval.
- Collecting soft sediment samples at 24 locations within the Menominee River, the Turning Basin, and the South Channel to assess total arsenic concentrations. These samples were collected at 0- to 0.5-foot intervals, with additional samples collected to the bottom of the soft sediment over 2-foot intervals. Soft sediment was defined operationally as sediment that could be sampled using vibracoring equipment.
- Collecting surface water samples at the 24 soft sediment sampling locations to assess arsenic concentrations in the water column, with samples collected at the surface, mid-depth, and bottom of the water column.
- Collecting sediment pore water samples to assess total arsenic concentrations at the 24 soft sediment sampling locations.
- Performing arsenic speciation analyses on the soft sediment and pore water samples from the semi-consolidated material.

- Collecting geotechnical and geochemical data to evaluate how site conditions affect the migration of arsenic throughout the Menominee River.
- Preparing visual descriptions of the sediment cores.
- Screening sediment samples to determine the presence of arsine gas.

A third investigation was performed in late 2001 to fill data gaps for the remedial facilities investigation (RFI) (URS 2002). RFI activities related to the Menominee River included the following:

- Collecting and analyzing eight soft sediment samples from two locations adjacent to the 6th Street Slip to determine whether a former channel was present adjacent to the slip. Samples were collected from the 0- to 0.5-foot depth interval and then over 2-foot intervals to the base of the soft sediment.
- Collecting and analyzing 13 soft sediment samples from five locations within the Menominee River Turning Basin to further characterize sediment for a Wisconsin Department of Natural Resources (WDNR) dredging permit. Samples were collected from the 0- to 0.5-foot depth interval and then over 2-foot intervals to the base of the soft sediment.
- Collecting groundwater samples from 16 locations in the river. Groundwater samples were collected at 5-foot intervals, beginning at a depth of 5 feet below the sediment/water interface and continuing to the top of bedrock at each location.

A fourth investigation was performed in June 2004 to further evaluate groundwater impacts below the Menominee River (URS 2004). Sixty groundwater samples were collected from 10 locations within the river, with sampling depth intervals ranging from 5 to 40 feet below the sediment surface. Groundwater samples were analyzed for total and dissolved arsenic.

The fifth investigation was conducted in May and June 2010 – the results of which are reported herein. Sample locations were selected, in part, using concentrations of arsenic in the soft sediment, semi-consolidated material, and groundwater beneath the river from the June 2004 investigation. A total of 722 samples for total arsenic were collected and submitted for laboratory analysis. Sample locations are shown on Figure 2. Subsets of these samples also were submitted for arsenic speciation, the State of Wisconsin NR374 parameters (to support a dredge permit application), geotechnical analyses, and moisture content. Appendix B includes results for all samples collected and analyzed. The details of the conceptual site model (CSM) provided in Section 2 of this SRWP are based on data collected from the 2010 investigation.

## 1.2.2 Corrective Measures in the Resource Conservation and Recovery Act Program

Tyco has implemented a number of corrective measures through the Resource Conservation and Recovery Act (RCRA) program. Between 1999 and 2000, interim site corrective actions were completed including constructing a slurry wall and sheet pile sections around the Salt Vault and 8th Street Slip (Figure 1), respectively, to contain groundwater. (These site features are now enclosed/contained and no longer used for their original purposes; therefore, they are referred to as the former Salt Vault and the former 8th Street Slip.) An

interim corrective action was conducted in the former 8th Street Slip, the slip was filled and covered with asphalt, and a groundwater monitoring program was established. Based on the results of the monitoring program, USEPA agreed to cease monitoring within these contained areas because the effectiveness of the barriers had been established.

Investigations conducted since 2006 have provided the information necessary to design corrective actions for the rest of the manufacturing area and the wetlands area at the site. The culmination of these investigations has been the identification of additional corrective and remedial measures that have been implemented at the facility property as required by the AOC, including installing a vertical barrier wall (VBW) system to surround the facility (Figure 1), a groundwater collection and treatment (GWCT) system to prevent flooding within the VBW, and a network of phyto-pumping tree plantings to remove additional water.

### 1.3 Menominee River Great Lakes Area of Concern

In 1987, the federal governments of the United States and Canada adopted amendments to the Great Lakes Water Quality Agreement (GLWQA). One of these amendments, called “Annex 2 of the 1987 Protocol,” directed the two countries to identify areas of concern that did not meet the objectives of the GLWQA. Great Lakes Areas of Concern (GLAOCs) are severely degraded geographic areas within the Great Lakes Basin. GLAOCs are defined by the GLWQA as “geographic areas that fail to meet the general or specific objectives of the agreement where such failure has caused or is likely to cause impairment of beneficial use of the area’s ability to support aquatic life.” Remedial action plans (RAPs) were to be prepared for all 43 GLAOCs identified to address “beneficial use impairments.” The 1990 Lower Menominee River RAP identified six of the GLWQA’s 14 potential beneficial uses as being impaired in the Menominee River (USEPA 2010) as follows:

- Restrictions on fish and wildlife consumption
- Degradation of fish and wildlife populations
- Beach closings
- Degradation of benthos
- Restriction on dredging activities
- Loss of fish and wildlife habitat

These impairments primarily have been caused by historical discharges to the river from industrial facilities in the area. Although arsenic contamination was identified in the RAP as one of the pollutants of concern, degradation of the benthos is the only beneficial use identified by the GLWQA that can be attributed to arsenic contamination in the sediment and semi-consolidated material in the Turning Basin and downstream of the facility. Other pollutants of concern identified in this GLAOC include paint sludge and coal tar. Remediation of the paint sludge site was completed in 1995 on the Michigan side. The Wisconsin Public Service Corporation Marinette Manufactured Gas Plant “Coal Tar Site” is another significant source of contamination. It is currently under remedial investigation by the USEPA Superfund Division. Other pollutants (such as mercury, polychlorinated biphenyls [PCBs], and oil and grease) also have contributed to use impairments. A fish advisory exists for mercury and PCBs.

Long-term goals of the Menominee River GLAOC include (USEPA 2010):

- Protect the aquatic ecosystem of the Menominee River and harbor from the effects of toxic and conventional pollutants
- Maintain a balanced aquatic and terrestrial community to ensure long-term health of the ecosystem
- Maintain and enhance recreational and commercial uses of the Menominee River and Harbor, consistent with the long-term maintenance of the natural resource base and a healthy economy

## SECTION 2

# Conceptual Site Model

---

This section briefly describes key components of the CSM, including the transport mechanisms responsible for the arsenic distribution observed in the soft sediment, semi-consolidated material, and glacial till beneath the Menominee River and the current understanding of the extent of contamination. For organizational purposes, the river adjacent to the facility is divided into seven subareas as indicated on Figure 1. The designated subareas include:

- Main Channel
- Turning Basin
- South Channel
- Transition Area 1
- Transition Area 2
- Transition Area 3
- 6th Street Slip

## 2.1 Generalized Stratigraphy and Groundwater Flow Direction

In general, four material types (or layers) are present in the upland portion of the site (Figure 3). The upper soil layer is generally composed of fill (sand and gravel with cinders, wood chips, brick, and glass). Beneath the fill is a layer of loose to medium dense alluvial deposits of fine- to coarse-grained sand and gravel with varying amounts of silt (alluvium). Underlying the sand is a layer of dense to extremely dense silty sand to sandy silt (compacted glacial “till” deposit). Below the dense silty sand/sandy silt is dolomitic bedrock.

In the Menominee River, water depth ranges between a few feet in the South Channel and 26 feet in the Main Channel. Soft sediment thickness ranges between less than 1 foot in the Main Channel and 8 feet in the Turning Basin, Transition Area 1, and the 6th Street Slip (Figure 4). Semi-consolidated material underlies the soft sediment, and the thickness of this layer ranges from 2 feet in the Turning Basin up to 27 feet thick in Transition Area 3 (Figure 5). The glacial till layer beneath the semi-consolidated material ranges between 0.5 and 7 feet thick (Figure 6). The northern portion of the Main Channel of the river (along the shoreline) was dredged in approximately 2002 down to bedrock, so semi-consolidated material and glacial till are not present in this area. The elevations of the top of bedrock ranged from a low of 539.1 feet (North American Vertical Datum of 1988) at SD556 within the Main Channel northeast of the Turning Basin, to a high of 562.6 feet at SD501 in the western portion of the Turning Basin, directly adjacent to the south shoreline of the river (Figure 7). The bedrock surface slopes east-northeast toward the Main Channel.

Portions of the Main Channel and Turning Basin fall within the federally authorized navigation channel. Authorized dredging depth in the federal navigation channel is 21 feet below the Lake Michigan low water datum of 577.5 feet above mean sea level referenced to

the International Great Lakes Datum of 1985. While the entire federal navigation channel has not been dredged to the full authorized depth, historical dredging by the U.S. Army Corps of Engineers (USACE) in the Turning Basin and Main Channel appears to have removed some of the semi-consolidated material layer, and soft sediment subsequently has deposited through natural accretion directly on the surface of the till and, in areas where it remains, on top of the semi-consolidated material. The outline of the approximate limits of the federally authorized navigation channel is shown on Figure 1.

Regional groundwater flow beneath the facility is generally northeast toward the Menominee River. The direction of groundwater flow will be affected in the vicinity of the facility because of the presence of the VBW, which was completed in fall 2010. Regional groundwater flow outside of the facility likely will remain generally toward the river but will be diverted around the VBW directly south of the facility.

## 2.2 Historical Arsenic Transport Mechanisms

Arsenic concentrations in groundwater at the facility are highest in the vicinity of the former 8th Street Slip and former Salt Vault areas because of historical storage of the salts in these areas. Three primary transport mechanisms have been identified for the movement of arsenic from the salt piles that were situated near the river. These transport mechanisms include:

- Overland transport via surface water and stormwater runoff into the Menominee River.
- Windblown transport of salt into the river and surrounding environment.
- Dissolution and infiltration into subsurface groundwater beneath the site with subsequent transport beneath the river. The arsenic contamination present in the semi-consolidated material primarily occurred through this transport mechanism.

Figure 8 shows a conceptual depiction of these transport mechanisms.

## 2.3 Sediment Characterization

Several figures were prepared to depict features within the individual sediment investigation study areas. The top of soft sediment elevation contour map is shown on Figure 9 and is based on bathymetry data collected in April and May 2010. The thickness of this soft sediment is shown on Figure 4. The soft sediment in the lower velocity areas of the river consisted of highly organic silt and detritus. Soft sediment in the portions of the river with higher flow velocity also included loosely consolidated sand and gravel.

The semi-consolidated material observed contain fine- to medium-grained sand. The elevation contour map for the top of semi-consolidated material beneath the soft sediment (Figure 10) shows the semi-consolidated material is highest in elevation near the south shoreline of the Turning Basin and the Transition Areas, and gradually decreases in elevation toward the northern portion of the Main Channel of the Menominee River. The thickness of the semi-consolidated material is shown on Figure 5.

The glacial till situated beneath the semi-consolidated material was described as dry to moist, hard silt with small to medium pebbles; firm to hard sandy silt with some gravel; and

fine-grained, hard silty sand with trace gravel. The elevation of the top of the glacial till is shown on Figure 11 – with a shallower elevation near the southern shoreline of the Turning Basin and becoming deeper toward the northern shore of the Menominee River, sloping in a north-northeast direction. The glacial till thickness is shown on Figure 6.

The elevation of the top of the bedrock surface beneath glacial till is shown on Figure 7. Sediment characteristics specific to individual study areas are included in the subsections that follow.

### 2.3.1 Main Channel

The soft sediment in the northern portion of the Main Channel of the Menominee River is composed of loosely consolidated sands and gravel. The soft sediment in the southern portion of the Main Channel was described as soft, moist clay/silt with a trace to minor fine-grained sand component and a medium-grained, dark brown to dark gray sand with a minor fines component. Soft sediment deposits within the Main Channel are relatively thin, ranging from 0.3 to 5 feet thick.

The semi-consolidated material thickness (Figure 5) ranges from 2.5 to 16 feet in borings advanced in the Main Channel, with glacial till thickness ranging from 0.5 to 7 feet.

### 2.3.2 Turning Basin

Since this area has a relatively slow river water velocity, the soft sediment within is comprised of clay/silt with a trace to minor fine-grained sand component and a medium-grained, dark brown to dark gray sand with a minor fines component. Soft sediment thickness in the Turning Basin ranges from 0.5 foot to approximately 8 feet, with most locations in the central area of the Turning Basin approximately 4 to 5 feet thick (Figure 4).

Figure 5 shows semi-consolidated material from 2 to 25.3 feet in borings within the Turning Basin. The thickest portion of the semi-consolidated material within the Turning Basin is located in the eastern portion. The glacial till thickness (Figure 6) within the Turning Basin ranged from 1 to 6.2 feet.

### 2.3.3 Transition Areas

The Transition Areas also are a slower-velocity environment, with soft sediment being described as a soft, moist clay/silt with a trace to minor fine-grained sand component and a medium-grained, dark brown to dark gray sand with a minor fines component. Sediment thickness in the Transition Areas appears to be relatively uniform, with most locations exhibiting approximately 5 feet of soft sediment.

The thickness of semi-consolidated material ranges from 8 to 26.8 feet in borings within the Transition Areas, with the majority of the borings indicating a thickness of 25 to 26.8 feet. The observed glacial till thickness in the Transition Areas ranges from 0.5 to 2.5 feet (Figure 6).

### 2.3.4 6th Street Slip

The soft sediment in the 6th Street Slip was described as soft, moist clay/silt with a trace to minor fine-grained sand component and a medium-grained, dark brown to dark gray sand

with a minor fines component. Sediment thicknesses in the 6th Street Slip range from 4 to 8 feet.

### 2.3.5 South Channel

Another slow-velocity environment, soft sediment in the South Channel exhibited similar characteristics as soft sediment in the 6th Street Slip and Transition Areas. The river bottom in the South Channel is largely covered with wood, wood chips, bark, and other debris from the former lumber operations in the area. The sediment thickness within the South Channel ranges from 0.3 to 5 feet, with the thickest deposits occurring at the western end of the channel.

## 2.4 Arsenic Data

The 2010 sediment investigation analytical data were used to define the lateral and vertical extent of the arsenic-contaminated sediment requiring removal. Three figures were compiled to depict arsenic concentrations in each zone – soft sediment, semi-consolidated material, and glacial till (Figures 12, 13, and 14, respectively). The maximum concentration was determined for each sampling location on each figure and within each zone, and then these assigned maximum concentrations were contoured, extrapolating values between points. Figures 12 and 13 use the following concentration range categories: less than 20 mg/kg, 20 to 50 mg/kg, 50.01 mg/kg to 500 mg/kg, and greater than 500 mg/kg. Figure 14 for the glacial till only has the first two categories, with the third being everything greater than 50 mg/kg because the maximum concentrations in the till are not as high as those in the soft sediment or semi-consolidated zones.

Appendix B, Table B1 contains the data for samples collected by CH2M HILL in April 2010. The summary statistics of the arsenic concentration by area and layer type (soft sediment, semi-consolidated materials, glacial till, weathered bedrock) are provided in Table 1, including the number of samples collected in each area and within each soil type. Discussions for each layer and observations for concentrations between layers follow.

TABLE 1  
Summary Statistics – Nature and Extent of Arsenic Contamination (mg/kg)

Area/Matrix	Minimum	Maximum	Average (Arithmetic Mean)
<b>Turning Basin</b>			
Soft sediment	2.3	20,000	2,900
Semi-consolidated material	1.5	2,900	270
Glacial Till	1.6	310	66
Weathered bedrock	3.3	3.3	3.3
<b>Main Channel</b>			
Soft sediment	1.8	850	62
Semi-consolidated material	1.4	97	6.3
Glacial Till	1.6	140	11
Weathered bedrock	6.8	6.8	6.8

TABLE 1  
Summary Statistics – Nature and Extent of Arsenic Contamination (mg/kg)

Area/Matrix	Minimum	Maximum	Average (Arithmetic Mean)
<b>Transition Areas</b>			
Soft sediment	0.71	5000	170
Semi-consolidated material	1.1	1300	54
Glacial Till	1.6	3.3	2.6
<b>South Channel</b>			
Soft sediment	1.7	110	36
<b>6th Street Slip</b>			
Soft sediment	3.5	230	75

### 2.4.1 Soft Sediment

Arsenic concentrations in the soft sediment within the Turning Basin ranged from 2.3 to 19,600 mg/kg. All locations in the central and western part of the Turning Basin had maximum arsenic concentrations greater than 20 mg/kg. Locations in the eastern portion of the Turning Basin, adjacent to Transition Areas 1 and 2, did not exhibit arsenic concentrations above 20 mg/kg. The highest concentrations in this area were detected within the center of the Turning Basin and adjacent to the shoreline. Soft sediment collected from the Main Channel had concentrations exceeding 500 mg/kg adjacent to the Turning Basin.

Maximum concentrations of arsenic in soft sediment exceeded 50 mg/kg near the southern shoreline, within the 6th Street Slip, and South Channel. The 50 mg/kg concentration also was exceeded at sample locations SD533 and SD534 in Transition Area 2, and SD554 in the Main Channel. Arsenic concentrations exceeded 500 mg/kg in the southern portion adjacent to Transition Area 3 and the former 8th Street Slip.

All soft sediment sampled in the 6th Street Slip contained maximum arsenic concentrations above 50 mg/kg.

### 2.4.2 Semi-Consolidated Material

The data collected during the 2010 investigation from the semi-consolidated material were used to develop Figure 13, which assigns colors to interpolated zones of maximum arsenic concentrations at each sampling location in this layer.

Maximum arsenic concentrations in the semi-consolidated material within the Turning Basin follow a similar pattern as those found in the soft sediment. The highest concentrations (greater than 500 mg/kg) in this layer are adjacent to the southern shoreline and extend outward into the Turning Basin and the western portions of Transition Areas 2 and 3 (Figure 13). Along the southern shoreline of the Turning Basin, the highest arsenic concentrations are in the top intervals of the semi-consolidated material and concentrations generally appear to decrease with depth (Appendix B).

The zone where maximum arsenic concentrations exceed 50 mg/kg extends beyond the greater than 500 mg/kg zone, just a bit farther into the river (Figure 13). Semi-consolidated material samples were not collected from the 6th Street Slip, South Channel, and Transition Area 1 during the 2010 investigation because of the combination of very shallow water and debris that prevented the sampling barge with the drill rig from reaching these areas. Several attempts were made to reach these areas, each ending with the sampling barge either running aground or becoming entangled on submerged debris.

### 2.4.3 Glacial Till

Figure 14 shows interpolated areas of maximum arsenic concentrations for all of the sample locations where one or more glacial till samples were collected. Similar to the access issues encountered when attempting to sample the semi-consolidated material, glacial till samples either were not collected or were not encountered in the 6th Street Slip and the South Channel during the 2010 investigation. Additionally, only one location in Transition Area 1 was accessible to the drilling rig.

All of the maximum arsenic concentrations exceeding 50 mg/kg within the glacial till layer are within the Turning Basin or in the Main Channel directly adjacent to the Turning Basin (Figure 14). From this figure, it is concluded that the concentrations within the glacial till are significantly less than from those detected in both the soft sediment and semi-consolidated material.

### 2.4.4 Comparisons Across Layers

When viewing concentration results for arsenic in the various layers, it is noted that several areas exist where the arsenic concentrations are relatively clean in the shallower elevations, decrease with depth, but then increase again a bit deeper. This information is summarized in Table 2 that contains a subset of the information provided in Appendix B. The region includes sample locations SD515, SD519, SD562, and SD574. Each of these locations is situated at least 100 feet from the southern shoreline of the river (see Figure 13 for the semi-consolidated material). This situation suggests that arsenic in this area of the semi-consolidated zone has been transported by groundwater from the site rather than originating from soft sediment at the surface.

TABLE 2  
 Sampled Locations with Clean Materials Overlying Contaminated  
*Tyco Fire Products LP*

Sample Location Name	Area Assignment	Top of Sediment Surface Elevation (ft amsl)	Depth to Top of Sampled Interval (ft)	Depth to Bottom of Sampled Interval (ft)	Arsenic Concentration (mg/kg)	Midpoint elevation of Sampled Interval (ft amsl)	Layer Assignment
		569.9	0.0	-1.0	6.9	569.4	soft sediment
		569.9	-1.0	-2.0	4.6	568.4	soft sediment
		569.9	-2.0	-2.4	4.8	567.7	soft sediment
		569.9	-4.0	-5.0	3	565.4	semiconsolidated
		569.9	-6.0	-7.0	2.5	563.4	semiconsolidated
		569.9	-8.0	-9.0	2.5	561.4	semiconsolidated
		569.9	-9.0	-10.0	3.2	560.4	semiconsolidated
		569.9	-10.0	-11.0	3.8	559.4	semiconsolidated
SD515	Turning Basin	569.9	-12.0	-13.0	48.8	557.4	semiconsolidated
		569.9	-13.0	-14.0	152	556.4	semiconsolidated
		569.9	-14.0	-15.0	262	555.4	semiconsolidated
		569.9	-15.0	-16.0	522	554.4	semiconsolidated
		569.9	-16.0	-17.0	631	553.4	semiconsolidated
		569.9	-17.0	-18.0	692	552.4	semiconsolidated
		569.9	-18.0	-19.0	332	551.4	semiconsolidated
		569.9	-19.0	-20.0	94.6	550.4	till
		569.9	-20.0	-21.0	246	549.4	till
		569.9	-21.0	-22.0	22.1	548.4	till

TABLE 2  
 Sampled Locations with Clean Materials Overlying Contaminated  
*Tyco Fire Products LP*

Sample Location Name	Area Assignment	Top of Sediment Surface Elevation (ft amsl)	Depth to Top of Sampled Interval (ft)	Depth to Bottom of Sampled Interval (ft)	Arsenic Concentration (mg/kg)	Midpoint elevation of Sampled Interval (ft amsl)	Layer Assignment
		569.9	-22.0	-23.0	4.3	547.4	till
		569.9	-23.0	-24.0	3.3	546.4	till
		569.9	-24.0	-25.0	2.7	545.4	till
		569.9	-25.0	-26.0	3.3	544.4	weathered bedrock
		576.6	0.0	-0.5	8.7	576.4	soft sediment
		576.6	-0.5	-1.0	8.5	575.9	soft sediment
		576.6	-1.0	-1.5	3.1	575.4	soft sediment
		576.6	-1.5	-2.0	2.5	574.9	soft sediment
		576.6	-2.0	-2.5	2.3	574.4	soft sediment
		576.6	-2.5	-3.0	2.6	573.9	soft sediment
SD519	Turning_Basin	576.6	-5.0	-6.0	4.3	571.1	semiconsolidated
		576.6	-7.0	-8.0	4.8	569.1	semiconsolidated
		576.6	-9.0	-10.0	61.7	567.1	semiconsolidated
		576.6	-10.0	-11.0	133	566.1	semiconsolidated
		576.6	-11.0	-12.0	44	565.1	semiconsolidated
		576.6	-12.0	-13.0	6.9	564.1	semiconsolidated
		576.6	-13.0	-14.0	30.9	563.1	semiconsolidated
		576.6	-14.0	-15.0	42.5	562.1	semiconsolidated

TABLE 2  
 Sampled Locations with Clean Materials Overlying Contaminated  
*Tyco Fire Products LP*

Sample Location Name	Area Assignment	Top of Sediment Surface Elevation (ft amsl)	Depth to Top of Sampled Interval (ft)	Depth to Bottom of Sampled Interval (ft)	Arsenic Concentration (mg/kg)	Midpoint elevation of Sampled Interval (ft amsl)	Layer Assignment
		576.6	-15.0	-16.0	2.3	561.1	semiconsolidated
		576.6	-16.0	-17.0	1.7	560.1	semiconsolidated
		576.6	-17.0	-18.0	2.3	559.1	semiconsolidated
		576.6	-18.0	-19.0	1.5	558.1	semiconsolidated
		576.6	-19.0	-20.0	2.3	557.1	semiconsolidated
		576.6	-20.0	-21.0	1.6	556.1	semiconsolidated
		576.6	-21.0	-22.0	6	555.1	semiconsolidated
		576.6	-22.0	-23.0	1.9	554.1	semiconsolidated
		576.6	-23.0	-24.0	6.3	553.1	semiconsolidated
		576.6	-24.0	-25.0	1.8	552.1	semiconsolidated
		576.6	-25.0	-26.0	2.5	551.1	semiconsolidated
		576.6	-26.0	-27.0	2.4	550.1	semiconsolidated
		576.6	-27.0	-28.0	2.6	549.1	semiconsolidated
		576.6	-28.0	-29.0	3	548.1	semiconsolidated
		576.6	-29.0	-30.0	1.8	547.1	till
		576.6	-30.0	-31.0	1.6	546.1	till
		576.6	-31.0	-32.0	2	545.1	till
		576.6	-32.0	-33.0	2.4	544.1	till

TABLE 2  
 Sampled Locations with Clean Materials Overlying Contaminated  
*Tyco Fire Products LP*

Sample Location Name	Area Assignment	Top of Sediment Surface Elevation (ft amsl)	Depth to Top of Sampled Interval (ft)	Depth to Bottom of Sampled Interval (ft)	Arsenic Concentration (mg/kg)	Midpoint elevation of Sampled Interval (ft amsl)	Layer Assignment
		576.6	-33.0	-33.8	3.6	543.2	till
		575.1	0.0	-0.5	101	574.9	soft sediment
		575.1	-0.5	-1.0	97.8	574.4	soft sediment
		575.1	-1.0	-1.5	111	573.9	soft sediment
		575.1	-1.5	-2.0	71.9	573.4	soft sediment
		575.1	-2.0	-2.5	9.7	572.9	soft sediment
		575.1	-2.5	-3.0	5.9	572.4	soft sediment
		575.1	-3.0	-3.5	29.8	571.9	soft sediment
		575.1	-5.0	-6.0	37	569.6	semiconsolidated
SD562	Transition Area 3	575.1	-7.0	-8.0	23.3	567.6	semiconsolidated
		575.1	-8.0	-9.0	24.1	566.6	semiconsolidated
		575.1	-9.0	-10.0	28.8	565.6	semiconsolidated
		575.1	-11.0	-12.0	65.6	563.6	semiconsolidated
		575.1	-12.0	-13.0	34.6	562.6	semiconsolidated
		575.1	-13.0	-14.0	19.5	561.6	semiconsolidated
		575.1	-14.0	-15.0	24.7	560.6	semiconsolidated
		575.1	-15.0	-16.0	12.5	559.6	semiconsolidated
		575.1	-16.0	-17.0	5.3	558.6	semiconsolidated

TABLE 2  
 Sampled Locations with Clean Materials Overlying Contaminated  
*Tyco Fire Products LP*

Sample Location Name	Area Assignment	Top of Sediment Surface Elevation (ft amsl)	Depth to Top of Sampled Interval (ft)	Depth to Bottom of Sampled Interval (ft)	Arsenic Concentration (mg/kg)	Midpoint elevation of Sampled Interval (ft amsl)	Layer Assignment
		575.1	-17.0	-18.0	4.1	557.6	semiconsolidated
		575.1	-18.0	-19.0	2.2	556.6	semiconsolidated
		575.1	-19.0	-20.0	5.8	555.6	semiconsolidated
		575.1	-20.0	-21.0	2.5	554.6	semiconsolidated
		575.1	-21.0	-22.0	3.4	553.6	semiconsolidated
		575.1	-22.0	-23.0	2.3	552.6	semiconsolidated
		575.1	-25.0	-26.0	2	549.6	semiconsolidated
		575.1	-26.0	-27.0	1.7	548.6	semiconsolidated
		575.1	-27.0	-28.0	1.9	547.6	semiconsolidated
		575.1	-28.0	-29.0	2.1	546.6	semiconsolidated
		575.1	-29.0	-30.0	2.4	545.6	semiconsolidated
		575.1	-30.0	-31.0	1.9	544.6	semiconsolidated
		575.1	-31.0	-32.0	1.6	543.6	till
		576.7	-5.0	-6.0	13.2	571.2	semiconsolidated
		576.7	-7.0	-8.0	62.4	569.2	semiconsolidated
SD574	Transition Area 2	576.7	-9.0	-10.0	61.3	567.2	semiconsolidated
		576.7	-10.0	-11.0	108	566.2	semiconsolidated
		576.7	-11.0	-12.0	55.7	565.2	semiconsolidated

TABLE 2  
 Sampled Locations with Clean Materials Overlying Contaminated  
*Tyco Fire Products LP*

Sample Location Name	Area Assignment	Top of Sediment Surface Elevation (ft amsl)	Depth to Top of Sampled Interval (ft)	Depth to Bottom of Sampled Interval (ft)	Arsenic Concentration (mg/kg)	Midpoint elevation of Sampled Interval (ft amsl)	Layer Assignment
		576.7	-12.0	-13.0	145	564.2	semiconsolidated
		576.7	-13.0	-14.0	79.1	563.2	semiconsolidated
		576.7	-14.0	-15.0	78.4	562.2	semiconsolidated
		576.7	-15.0	-16.0	31.3	561.2	semiconsolidated
		576.7	-16.0	-17.0	5.5	560.2	semiconsolidated
		576.7	-17.0	-18.0	10.5	559.2	semiconsolidated
		576.7	-18.0	-19.0	5.1	558.2	semiconsolidated
		576.7	-19.0	-20.0	66.3	557.2	semiconsolidated
		576.7	-20.0	-21.0	87.2	556.2	semiconsolidated
		576.7	-21.0	-22.0	53.8	555.2	semiconsolidated
		576.7	-22.0	-23.0	53.2	554.2	semiconsolidated
		576.7	-23.0	-24.0	4.5	553.2	semiconsolidated
		576.7	-24.0	-25.0	2.8	552.2	semiconsolidated
		576.7	-25.0	-26.0	2.4	551.2	semiconsolidated
		576.7	-26.0	-27.0	2.1	550.2	semiconsolidated
		576.7	-27.0	-28.0	2	549.2	semiconsolidated
		576.7	-28.0	-29.0	2.3	548.2	semiconsolidated
		576.7	-29.0	-30.0	3.1	547.2	semiconsolidated

TABLE 2  
 Sampled Locations with Clean Materials Overlying Contaminated  
*Tyco Fire Products LP*

Sample Location Name	Area Assignment	Top of Sediment Surface Elevation (ft amsl)	Depth to Top of Sampled Interval (ft)	Depth to Bottom of Sampled Interval (ft)	Arsenic Concentration (mg/kg)	Midpoint elevation of Sampled Interval (ft amsl)	Layer Assignment
		576.7	-30.0	-31.0	3.1	546.2	till
		576.7	-31.0	-32.0	2	545.2	till
		576.7	-32.0	-33.0	2.1	544.2	till

## Notes:

	Arsenic Concentration above 20 mg/kg
	Arsenic Concentration above 50 mg/kg

# Menominee River Sediment Removal Plan

---

## 3.1 Project Objectives

The requirement of the sediment removal activities per the AOC is to remove contaminated soft sediment and semi-consolidated material from the Menominee River adjacent to the facility that exhibit arsenic concentrations greater than or equal to 50 mg/kg total arsenic, with MNR for the material present between 20 and 50 mg/kg. These requirements have been used to develop the SRWP approach.

## 3.2 Proposed SRWP Corrective Action Plan

Data from the 2010 investigation, as well as previous investigations, have been used to develop this SRWP. This document presents the plan for the removal, stabilization, and disposal of the targeted contaminated materials from the Menominee River. Although implementation of the SRWP approach is technically impracticable as it will likely result in failure of the sheet pile wall and it is not as protective of the environment as the alternative approach described in the AMRSRP, implementation of the SRWP is described in this plan per AOC requirements. The corrective measures design will be further refined once an alternative is selected and final design plans and specifications will be developed and submitted to USEPA for review. After the review of the final design documents by USEPA, corrective activities will be implemented.

Tyco will implement a dredging, stabilization, and disposal corrective action. The SRWP activities are divided into four phases, which are described below. During the corrective action activities, some phases likely will be performed simultaneously with others. The sediment remediation preliminary design drawings in Appendix C provide additional details regarding the SRWP corrective activities.

1. **Phase I (Mechanical Dredging of Contaminated Soft Sediment)**: The soft sediment that contains total arsenic contamination in excess of 50 mg/kg will be mechanically dredged using an environmental clamshell bucket and stabilized onsite. The stabilization process will reduce the concentration of leachable arsenic in the sediment such that it passes the toxicity characteristic leaching procedure (TCLP) test with less than 5 milligrams per liter (mg/L) of total arsenic. The stabilized soft sediment will then be disposed offsite at a RCRA Subtitle D (nonhazardous) landfill.
2. **Phase II (Mechanical Dredging of Contaminated Semi-consolidated Material)**: The semi-consolidated material beneath the soft sediment that contains total arsenic contamination in excess of 50 mg/kg will be mechanically dredged using a standard clamshell bucket and stabilized onsite. It is important to note that this phase includes removal of the semi-consolidated materials adjacent to the sheet pile wall, and removal of these materials will likely result in wall failure. The stabilized semi-consolidated material will then be disposed offsite at a RCRA Subtitle D landfill.

3. **Phase III (Dry Excavation of Soft Sediment from the South Channel):** Sheet piling will be installed at the west end of the South Channel, and water inside the temporary enclosure will be pumped out. Depending upon water levels in the river, a culvert on the east end of the channel may need to be blocked temporarily as well. Conventional excavation equipment (backhoes and articulated haulers) will be used to stabilize the soft sediment in situ, excavate it, and transport it back to the facility for stabilization and disposal offsite at a RCRA Subtitle D landfill.
4. **Phase IV (Monitoring Natural Recovery):** Sediment containing arsenic at concentrations between 20 and 50 mg/kg will be left in place. The site will be monitored, and within 10 years a decision will be made as to what actions are necessary to complete the remediation. Monitoring activities will be described under a separate plan.

The corrective activities consist of the following key components:

### 3.2.1 Pre-Dredging Activities

- Mobilizing equipment and personnel
- Completing minor improvements to the existing asphalt surface in the former Salt Vault area for use as a staging pad
- Demarcating roads on the existing asphalt surface for trucks to travel
- Constructing a temporary mooring structure and drip containment along the shoreline of the facility
- Installing a temporary water treatment system, and other temporary infrastructure on the facility
- Installing turbidity monitoring equipment in the river
- Clearing and grubbing of trees and vegetation on the City of Marinette-owned property east of the facility and constructing a temporary access road to the South Channel
- Installing sheet piling at the west end of the South Channel to facilitate dry excavation
- Performing a bathymetric survey to document the pre-dredge sediment elevations
- Installing turbidity control devices in the river

### 3.2.2 Phase I Activities

- Mechanical dredging of approximately 58,000 yd<sup>3</sup> of soft sediment contaminated with arsenic equal to or greater than 50 mg/kg using an environmental bucket<sup>2</sup>, following best management practices (BMPs), and loading the sediment into watertight scows
- Transporting loaded scows to the mooring area adjacent to the facility
- Pumping free water off the dredged material to the temporary water treatment system
- Offloading dredged material from the scows

---

<sup>2</sup> “Environmental bucket and best management practices (BMP) are defined in Section 5.6.1.

- Treating and stabilizing the contaminated dredged material with suitable reagents to reduce leachable arsenic, eliminate free water, and provide moderate strength gain
- Allowing sufficient time for reagents added to sediment to react to meet landfill acceptance criteria
- Conducting sampling and analysis to verify compliance with disposal criteria
- Placing the stabilized sediment into trucks
- Covering the truck bed and decontaminating the exterior of the trucks
- Transporting the sediment to a RCRA Subtitle D landfill
- Collecting and treating wastewater through the temporary water treatment system
- Performing ongoing monitoring activities, including turbidity monitoring in the river, and monitoring of arsenic and suspended solids concentrations in the influent to and effluent from the water treatment system
- Performing a bathymetric survey to document the post-Phase I subsurface elevations

### 3.2.3 Phase II Activities

- Mechanical dredging of approximately 149,000 yd<sup>3</sup> of semi-consolidated material contaminated with arsenic greater than 50 mg/kg using a standard clamshell bucket, and loading the material into watertight scows
- Transporting loaded scows to the mooring area adjacent to the facility
- Pumping free water off the dredged material to the temporary water treatment system
- Offloading dredged material from the scows
- Treating and stabilizing the contaminated dredged material with suitable reagents to reduce leachable arsenic, eliminate free water, and provide moderate strength gain
- Allowing sufficient time for reagents added to the material to react to meet landfill acceptance criteria
- Conducting sampling and analysis to verify compliance with disposal criteria
- Placing the stabilized material into trucks
- Covering the truck bed and decontaminating the exterior of the trucks
- Transporting the stabilized material to a RCRA Subtitle D landfill
- Collecting and treating wastewater through the temporary water treatment system
- Performing ongoing monitoring activities, including turbidity monitoring in the river and monitoring of arsenic and suspended solids concentrations in the influent to and effluent from the water treatment system

- Performing confirmation sampling to document that semi-consolidated material with arsenic contamination exceeding 50 mg/kg has been removed, or that glacial till has been reached
- If necessary, removing additional contaminated semi-consolidated material based on the initial confirmation sampling, followed by additional confirmation sampling
- Performing a bathymetric survey to document the post-Phase II subsurface conditions

### 3.2.4 Phase III Activities

- Mobilizing equipment necessary specifically for Phase III activities
- Pumping free water on top of the sediment to the river until total suspended solids (TSS) exceeds 80 mg/L
- Pumping remaining free water within the sediment to the onsite temporary water treatment system
- Installing well points to facilitate additional dewatering below the top of sediment and pumping this water to the onsite temporary water treatment system
- Stabilizing approximately 12,000 yd<sup>3</sup> of soft sediment contaminated with arsenic greater than 50 mg/kg in situ using an excavator, excavating the stabilized sediment, and loading the sediment into articulated trucks to transport the material back to the stabilization area on the facility (some stabilization reagents might be added to the soft sediment before it is transported to the facility in order to dry it out)
- Treating and stabilizing the contaminated dredged material with suitable reagents to reduce leachable arsenic, eliminate free water, and provide moderate strength gain
- Allowing sufficient time for reagents added to sediment to react to meet landfill acceptance criteria
- Conducting sampling and analysis to verify compliance with disposal criteria
- Placing the stabilized sediment into trucks
- Covering the truck bed and decontaminating the exterior of the trucks
- Transporting the sediment to a RCRA Subtitle D landfill
- Collecting and treating wastewater through the temporary water treatment system
- Performing ongoing monitoring activities, including turbidity monitoring in the river, monitoring of arsenic and suspended solids concentrations in the influent to and effluent from the water treatment system, and monitoring of fugitive dust emissions from the stabilization activities
- Performing confirmation sampling to document that materials with arsenic concentrations exceeding 50 mg/kg have been removed
- Performing a survey to document the post-Phase III subsurface conditions

- Removing sheet piling and the berm required to provide access for sheet piling installation and removal equipment

### 3.2.5 Post-Dredging Activities

- Teardown, removing, and offsite disposal of temporary infrastructure built on the Tyco property
- Restoring the Tyco property to pre-corrective action conditions, to the extent practical
- Demobilizing equipment and personnel

### 3.2.6 Phase IV Activities, Monitoring Natural Recovery

Sediment containing arsenic at concentrations between 20 and 50 mg/kg will be left in place, and MNR will be allowed to occur for a period of 10 years following dredging activities. An MNR plan will be submitted in accordance with the AOC.<sup>3</sup>

## 3.3 Design Components

This section describes the major components of the SRWP approach design.

### 3.3.1 Bathymetric and Sediment Thickness Surveys

A bathymetric survey of the 2010 sediment investigation area within the Menominee River, including the Main Channel, Turning Basin, Transition Areas, 6th Street Slip, and the South Channel areas, was completed in April 2010. Additionally, water depth and sediment thickness data were collected during the May-June 2010 sediment sampling events. These data were combined to create figures showing the estimated soft sediment surface elevation (Figure 9) and soft sediment thickness (Figure 4).

Before performing mechanical dredging work, the dredging contractor will be required to retain a bathymetric surveying contractor to perform a pre-dredge bathymetric survey that covers areas to be dredged. A post-dredge bathymetric survey will be performed at the conclusion of each phase of dredging activities (Phases I and II) to document final conditions and establish payment quantities. Since the South Channel will be dewatered, a terrestrial-based survey will be performed after dredging in Phase III is completed to document final conditions and establish payment quantities.

### 3.3.2 Bulkhead/Shoreline Stability

The VBW installed along the shoreline adjacent to the Tyco property consists of steel sheet piling, most of which was installed in 2010. Some of the sheet piling is supported with tieback anchors, and other segments are entirely cantilever-supported (Figure 15). Figures 16 and 17 show cross sections through the sheet piling and materials present in the river based on nearby borings (cross section locations on Figure 15). For cross-section A-A', this sheet piling was installed before 2010, and the design documentation was not immediately available. The design river bottom for nearby sheet piling installed in 2010 was used, and specific design documentation for this sheet pile section will be obtained and

<sup>3</sup> "Respondent shall submit the monitoring plans for the monitored natural recovery and barrier wall monitoring 90 days before completion of construction of these components [90 days prior to completion of sediment removal]" per Attachment 2, Section IV.A, 2nd paragraph, of the AOC.

incorporated into future design documents. For cross-section B-B' on Figure 17, the sheet piling was installed in 2010, and the design river bottom elevation is shown, which is 13 feet above the sheet piling toe elevation of 552 feet, and sloping away from the sheet piling at 7 degrees.

Cross-section A-A' (Figure 16) shows that contaminated semi-consolidated material are present against the sheet piling, and removal of this material will result in a river bottom profile lower than that used for the design. This indicates the structural stability of the sheet piling in this area would be compromised. Cross-section B-B' (Figure 17) shows stratigraphy in the river similar to cross-section A-A'. However, the contamination in the region of cross-section B-B' does not extend nearly as deeply into the semi-consolidated material, so removing all contaminated semi-consolidated material here would result in a river bottom profile higher than that used for the design. This indicates the structural stability of the sheet piling in this area would not be compromised.

### 3.3.3 Utilities

Thew Associates performed a utility survey in April 2010 prior to CH2M HILL conducting subsurface investigation activities. A buried high-density polyethylene waterline crossing the South Channel was identified at two spots during the April-May 2010 work, as well as an electrical line associated with the bridge at Ogden Street. It is unlikely that soft sediment removal in the South Channel will come close to these utilities, but this will be verified during development of the final design. The dredging contractor will be required to verify the presence/locations of utilities before beginning work.

### 3.3.4 Arsenic Contamination Evaluation

#### Geostatistical Modeling Interpolation Method

A three-dimensional (3D) interpolation method was used to delineate arsenic in the soft sediment, semi-consolidated material, and glacial till. The model was used to aid in development of the dredge areas and determination of dredge volumes. The computer application, Environmental Visualization System (EVS)-Pro Version 9.4 (Environmental Visualization System, produced by C-Tech Development Corporation) was used to interpolate arsenic concentrations from individual sampling points to a dense 3D mesh. The general procedures for mesh generation and for selecting the interpolation parameters are outlined below.

Key attributes of the EVS-Pro based interpolation approach for the delineation of arsenic extent include the following:

- The dataset used includes analytical results from sediment core sampling and drill rig sampling collected by CH2M HILL during April-May 2010.
- Arsenic concentrations were represented as point values located at corresponding horizontal coordinates (for example, northing and easting) for each sample location. The vertical position was represented by the middle of the sampling interval – there were typically multiple vertical locations for a given sample location on the map.
- The selected grid density used within each subarea was determined by distance between sample locations and the number of sample locations.

- The arsenic concentration distribution was modeled within the 3D mesh using a geostatistical process called kriging. The interpolation process utilized a gridding option best suited for the data and its location (rectilinear), and then kriging was performed.
- Each zone-specific model was built on convex hull-bounded grids limited to the areal extent of each subzone with Z spacing determined by sediment thickness and using the adaptive gridding option. Adaptive gridding automatically refines gridding in the cells surrounding measured samples to ensure that the interpolated results and isosurfaces accurately honor measured sample data. Adaptive gridding provides an effective resolution that cannot be approximated by any other method, often providing more accurate results rather than increasing the number of elements by 100 to 1,000 times. The selected grid density used within each zone and subzone was a compromise between providing the highest detailed resolution and maintaining reasonable model run times.

## Results

Determination of the mechanical dredging material volume was based on a criterion of 50 mg/kg total arsenic. Based on data collected during May-June 2010, approximately 220,000 yd<sup>3</sup> of arsenic contaminated material (including estimated overdredge) will require removal by dredging. Of this total, 71,000 yd<sup>3</sup> will be removed as soft sediment and 149,000 yd<sup>3</sup> will be removed as semi-consolidated material. These volumes include an estimated average 6-inch overdredge depth as well as a 4:1 (horizontal to vertical) side slope stability allowance for soft sediment removal. Figure 18 presents the extent and thickness of the arsenic-contaminated material exceeding 50 mg/kg that needs to be removed.

# Corrective Action Design—Project Delivery Strategy

---

## 4.1 Preliminary Design

The objectives of the preliminary design are to define, in detail, the technical parameters upon which the design will be based, develop the conceptual strategies and ideas that compose the framework of the remediation project, review the strategies and ideas with the agencies, and, to the extent possible, finalize the strategies and ideas so that the final design may proceed with minimal changes (for example, minimal cost and schedule impacts).

## 4.2 Final Design

Once the conceptual strategies and ideas and supporting technical details have been developed, reviewed, finalized, and approved by the agencies in the preliminary design, the final design activities will commence. The conceptual strategies and ideas developed during the preliminary design will be expanded into a set of final design documents consisting of the following:

- Basis of design report
- Specifications
- Drawings
- Cost estimate
- Site-specific plans
- Contract award documents
- Biddability, operability, and constructability reviews
- Revised project delivery strategy
- Construction quality assurance plan

Detailed design drawings and specifications will be prepared for the majority of the selected components. The successful bidder of the work will become the dredging contractor. The contractor will be required to develop a detailed work plan, describing how the work will be executed.

## SECTION 5

# Preliminary Design Approach, Assumptions, and Parameters

---

A general conceptual description of the mechanical dredging support facilities, equipment, and activities is included in this SRWP. During the bid process, bidders for the work will be required to provide a general description of their proposed site layout, dredging equipment, water treatment system, and procedures, so significant proposed modifications can be discussed and evaluated before award of the contract. In addition, before starting the work, the dredging contractor will provide a detailed work plan that will describe the specifics of the proposed mechanical dredging activities.

## 5.1 Minimizing Environmental and Public Impacts

One of the primary objectives of the dredging operations is to minimize the environmental and public impacts. This is achieved through permitting and planning during the design phase, as well as adherence to environmental controls and monitoring during the execution of the dredging project.

### 5.1.1 Planning and Permitting

Permits related to the following items will be completed by Tyco, as necessary:

- Section 10 of the Rivers and Harbor Act of 1899, Section 404 of the Clean Water Act (CWA), and Section 401 of the CWA for dredging
- Revision of Tyco's existing Wisconsin Pollution Discharge Elimination System (WPDES) industrial permit, if necessary
- Chapter NR 347 of the Wisconsin Administrative Code for sediment sampling and analysis, monitoring protocol, and disposal criteria for dredging projects
- RCRA permit for onsite sediment handling and treatment
- Clean Air Act (CAA) permit
- Endangered and threatened species review and Natural Historic Preservation Act permit, if necessary
- Coordination with the U.S. Coast Guard regarding a Notice to Mariners and waterway markers permit
- Building permit from the City of Marinette for temporary facilities
- Soil erosion and sediment control (SESC) permit

- Chapter 30 and NR 216 of the Wisconsin Administrative Code for Stormwater Erosion Control and Post-Construction Stormwater Permit
- Access agreements for use of property not owned by Tyco, if necessary

### 5.1.2 Execution of Dredging Activities

Project information will be communicated with local property owners and other general members of the public before and during the corrective activities to limit the impacts of the project to residents and commercial and recreational activities.

During the dredging activities, BMPs will be employed to control the resuspension of sediment; BMPs are described later in this section. Turbidity will be continuously monitored, and exceedances will be communicated to the dredging contractor so modifications to the process or equipment can be made as necessary, as described in Section 7. It is important to note that control of sediment resuspension does not correlate with control of dissolved arsenic release, and an exceedance of Wisconsin's acute toxicity water quality criterion for arsenic in surface water is likely to occur regardless of the effectiveness of BMPs (refer to Appendix A).

Air monitoring, post-dredging confirmation sampling, and post-dredging bathymetric surveys will be conducted as described in Section 7.

## 5.2 Site Preparation and Mobilization

### 5.2.1 Site Preparation and Mobilization Activities

Before mobilization to the site, the dredging contractor will verify it has obtained or is in compliance with the requirements of necessary permits. In addition, the contractor will deliver necessary preconstruction submittals to Tyco for approval before mobilization.

Prior to mechanical dredging, the contractor will perform site preparation activities at the Tyco property (the term "site" refers to the portion of the Tyco property used for the mechanical dredging and stabilization activities as shown on the drawings in Appendix C). These activities are necessary to allow heavy equipment to access all of the portions of the site and to ensure protection of the environment during the dredging activities. The former Salt Vault area (asphalt pad) and the former 8th Street Slip will be used as the staging and treatment area. Mobilization and site preparation activities will include the following:

- Mobilization of equipment and personnel
- Clearing and grubbing of vegetation and implementation of erosion control measures in the areas disturbed
- Establishment of physical construction limits at the site with temporary fencing or other means of demarcation
- Set up of site trailers for the dredging contractor and oversight contractor
- Construction of temporary partitions on the existing asphalt surface in the former Salt Vault to create areas for staging, stabilization, stockpiling, and water treatment

- Construction of a temporary mooring structure and drip containment at the shoreline of the site
- Construction of a temporary water treatment system
- Installation of turbidity monitoring equipment in the river
- Construction of temporary access roads near the existing boat landing on City of Marinette property to access the South Channel for the dry excavation activities

## 5.2.2 Asphalt Pad and Site Access Roadways

The mechanical dredging of river sediments requires modifying the existing asphalt pad and installing temporary access roads to reach the South Channel for the dry excavation activities. The drawings (Appendix C) include an overview of the conceptual plan and cross-section details. Separate areas will be established on the asphalt surface near the former Salt Vault to accommodate the reagent storage, temporary onsite water treatment plant, dredged material stabilization, stabilized material storage, and decontamination for trucks hauling stabilized sediment offsite. Temporary access roads will be built in areas where no roadways currently exist, and in other cases, designated haul routes will be demarcated on the existing asphalt areas. A description of each of these items is included below.

### Asphalt Concrete Pad

The existing asphalt surface in the former Salt Vault (and the former 8th Street Slip) area will be used as the staging area. There is an existing 250-foot x 250-foot asphalt concrete staging pad with 2-foot-high sealed concrete sidewalls along with a 1 percent slope toward the drain outlet on the west sidewall. The pad area consists of a 6-inch-thick asphalt concrete layer constructed over a compacted fill and a gravel layer. The former 8th Street Slip area consists of a 4-inch-thick asphalt concrete layer constructed over a layer of compacted imported sand. A 10-foot x 10-foot x 2-foot asphalt concrete-lined outfall sump with a maximum holding capacity of approximately 1,200 gallons will be constructed outside of the asphalt pad as shown in the drawings (Appendix C). The bottom of the outfall sump will be constructed at least 2 feet below the existing asphalt concrete pad surface level. A pipe will be installed to connect the drain outlet located on the east sidewall of the asphalt pad to the outfall sump. It is expected that free water from the offloaded dredged material and the stormwater runoff will be collected in the outfall sump through the drain outlet, prior to pumping it out to the temporary water treatment system.

The southwestern corner of the pad will be used as the reagent storage and handling area, and the northwestern corner of the pad will be used for the temporary water treatment system. The remaining portion of the pad will be used as the sediment stabilization and storage area, with temporary berms separating the sediment stabilization and storage area from the water treatment system and reagent storage and handling areas. Water that seeps through the asphalt concrete pad will be contained onsite by the VBW and extracted and treated by the permanent site GWCT system.

### Temporary Access Roads

Since the working area within the Tyco facility is covered with asphalt concrete, no construction of temporary access roads will be necessary in the vicinity of the staging area.

Traffic cones, barrels, or signage will be used to demarcate travel areas for trucks hauling materials to and from the site to keep truck traffic confined to these areas for the safety of site personnel.

Some temporary access roadways will need to be constructed on the property east of the site as shown on the drawings in Appendix C to facilitate the truck hauling and transportation. After clearing and grubbing, the existing surface will be leveled and prepared, and a mid-weight geosynthetic fabric of 6- to 10-ounce/square yard will be laid to separate and stabilize the foundation. Over the geosynthetic fabric, a 6-inch-thick crushed stone aggregate layer will be placed and compacted. This layer of aggregate shall meet the requirements of Wisconsin Department of Transportation Series 21 Class AA or Series 22 Class A. The gravel access roadways will minimize the tracking of loose soil.

### **Asphalt Concrete Pad and Temporary Access Road Removal and Disposal**

Once the dredging activities are completed, the asphalt concrete surfaces will be washed off, and the resulting wastewater will be captured and treated in the temporary onsite water treatment system. Areas where a permanent asphalt concrete surface has been damaged by the corrective activities will be repaired and resurfaced. Access roads constructed on the property east of the site will be tested for leachable arsenic, broken up, removed, and disposed offsite at a nearby nonhazardous landfill or recycled as appropriate (assuming the leachable arsenic results indicate the material is nonhazardous and/or meets regulations for recycling). Areas where the access roads were constructed outside the VBW will be restored by reseeded it with native vegetation and planting new trees to replace those which were removed.

## **5.3 Mechanical Dredging**

Approximately 59,000 yd<sup>3</sup> of soft sediment and 149,000 yd<sup>3</sup> of semi-consolidated material containing arsenic greater than 50 mg/kg (including estimated overdredge volumes) will be mechanically dredged from the river using the SRWP approach as shown on the drawings in Appendix C. These volumes targeted for mechanical dredging do not include 12,000 yd<sup>3</sup> of soft sediment in the South Channel that will be removed by dry excavation. The thickness of soft sediments to be mechanically dredged ranges from less than 1 foot to a maximum of 8 feet. The semi-consolidated material thickness ranges from 6 to 27 feet. Water depth within the mechanical dredging areas is up to 21 feet deep adjacent to the Main Channel. The water depth in the South Channel is approximately 1 to 2 feet, which is too shallow for mechanical dredging.

The performance standards for the mechanical dredging consist of the following:

- Removing soft sediment to specified elevations
- Removing semi-consolidated material to specified elevations
- Minimizing sediment resuspension below the specified turbidity standard

The dredging contractor will perform bathymetric surveys before and after dredging. These bathymetric surveys will be used to determine if the specified dredge cuts have been achieved as well as providing a final dredged sediment volume for payment. Calculations of soft sediment and semi-consolidated material volume in this SRWP include an average of 6 inches overdredge depth.

### 5.3.1 Dredging Equipment

Mechanical dredging of contaminated soft sediments will be performed with a crane and environmental clamshell bucket having the following capabilities and characteristics:

- Provides a level cut during the closing cycle
- Completely encloses the dredged sediment and water captured
- Has escape valves or vents that close when the bucket is withdrawn from the water
- Has a smooth cut surface, with no teeth
- Is controlled by the operator using global positioning system (GPS) equipment with integrated software that allows:
  - The bucket position to be monitored in real time
  - The specified horizontal and vertical accuracy requirements to be met
  - The operator to control bucket penetration to avoid overfilling and minimize sediment resuspension

Since the compacted nature of the semi-consolidated material precludes the use of an environmental bucket, mechanical dredging of contaminated semi-consolidated material will be performed with a conventional clamshell bucket with teeth having the following capabilities and characteristics:

- Provides cut into the densely compacted semi-consolidated material
- Is controlled by the operator using GPS equipment with integrated software that allows:
  - The bucket position to be monitored in real time
  - The specified horizontal and vertical accuracy requirements to be met
  - The operator to control bucket penetration to avoid overfilling and minimize sediment resuspension

Because of the need to use a conventional clamshell bucket to remove the semi-consolidated material, dredging of this material is expected to result in the release of significantly larger amounts of dissolved arsenic as well as suspended solids into the river than with an environmental clamshell bucket (see Appendix A).

### 5.3.2 Dredging Sequence

Mechanical dredging of soft sediment (Phase I) will be completed prior to the dredging of semi-consolidated material (Phase II). The elevation contours and thicknesses for soft sediment and semi-consolidated material are shown on Figures 4, 5, 8, and 10.

### 5.3.3 Dredging Process

The mechanical dredging, offloading, and stabilization process described here is conceptual and will be more specifically defined during design. The dredging contractor will be allowed to propose and utilize a different process if, after an evaluation, the proposed process is cost-effective and can reasonably be expected to meet performance criteria such as production rates and turbidity standards.

The mechanically dredged material will be loaded into watertight scows that will be transported to the temporary docking platform to be constructed near the former 8th Street Slip. The dredged material will be offloaded using a material handler with a clamshell bucket and transferred onto a screen to separate oversized debris. The material passing the screen will fall onto a conveyor belt and be transported to the sediment stabilization and storage area on the asphalt pad. The material will then travel through a pugmill where stabilization reagents will be added. Following reagent addition, the material will be moved by conveyors and/or a front-end loader(s) to a storage area where the mixture will cure for approximately 1 week. Once the material has cured sufficiently, it will be sampled and analyzed for TCLP arsenic to confirm it is nonhazardous. The landfill might require additional analyses to meet disposal requirements. Then, the material will be picked up with a front-end loader and loaded into a truck for transportation offsite. The top of the truck will be covered with a tarp, the exterior of the truck will be decontaminated (if necessary), and the stabilized sediment will be transported to an off-site RCRA Subtitle D (nonhazardous) landfill for disposal.

Free water from the dredged material, decontamination water, and water from rain events will gravity drain to the outfall sump located adjacent to the asphalt pad. Water collecting in the sump will be pumped directly to the temporary water treatment system. Suspended solids and dissolved contaminants in the water will be removed by the water treatment system, which will consist of equalization, chemical feed, microfiltration (MF), two-stage reverse osmosis (RO) filtration, filter press dewatering, and, if cost-effective, mechanical evaporative concentration (see Section 5.6.2).

### 5.3.4 Debris

Debris encountered during mechanical dredging will be segregated as much as possible on the material scow and handled separately once the scow is moved to the offloading area. If significant debris is encountered while dredging soft sediment (Phase I) that would potentially cause damage to the environmental bucket, a conventional clamshell bucket may be used until the debris is removed.

### 5.3.5 Stabilization Reagents

A treatability study is currently being conducted to determine a cost-effective reagent mixture to stabilize the dredged material. The stabilized dredged material must meet three criteria:

- No free water (must pass paint filter test for disposal at the landfill)
- Leachable arsenic is less than 5 mg/L, as measured by the TCLP test
- Minimum strength of 12 pounds per square inch at 7 days of curing, as measured by the unconfined compression test

Preliminary treatability testing results indicate reagents needed to stabilize dredged materials may include a cementitious reagent to provide moderate strength gain and other reagents such as an oxidizing agent and an iron-based compound to create an insoluble arsenic compound and reduce leachability.

### 5.3.6 Dredging Production Rate and Duration

The expected mechanical dredging rate for the soft sediments is estimated to be 1,300 yd<sup>3</sup> per day up to 24 hours per day/7 days per week. A dredging rate of 1,000 yd<sup>3</sup> per day (also on a 24/7 basis) is estimated for semi-consolidated material because of their compacted nature and the associated difficulties that might be encountered in dredging this material. The mobilization, setup, and demobilization phases of the project cumulatively may take approximately 7 weeks. A total duration of 7 weeks of soft sediment dredging (not including soft sediment dry excavation from the South Channel) and 22 weeks of semi-consolidated material dredging are anticipated based on these production rates. Because of the time required to dredge the semi-consolidated material, and the need to incorporate calendar restrictions for fish spawning, a temporary winter shutdown period is assumed to avoid issues with freezing temperatures.

### 5.3.7 Debris Handling

Oversized debris from the screen at the offloading area will be removed using a front-end loader and set aside for decontamination. Debris encountered during dredging that was segregated on the material scows will be offloaded separately from the other dredged material and also set aside for decontamination. After being washed with a pressure washer to remove significant sediment from the debris, the debris will be placed in a rolloff container for eventual transportation and disposal offsite at a RCRA Subtitle D landfill for disposal.

### 5.3.8 Dredging Positioning System

A system that continuously locates and records the horizontal and vertical position of the cutting face will be required. A real-time kinematic positioning system, or an alternative positioning system that can meet the specified tolerance requirements, will be used to provide the horizontal and vertical positioning for the dredge system. The positioning system shall employ software capable of monitoring the x, y, and z position of the dredge bucket in real time. The software will be required to provide the following:

- A real-time view of the barge and clamshell bucket position
- A display indicating the surface derived from the pre-dredge hydrographic survey data
- A display that provides real time feedback showing current depth, final project depth, target depth, and current bucket depth

The following tolerances shall be met:

- Horizontal position accuracy shall be plus or minus 2 feet
- Vertical tolerance shall be plus zero, minus 0.5 foot

## 5.4 Dry Excavation – South Channel

Approximately 12,000 yd<sup>3</sup> of soft sediment with arsenic contamination exceeding 50 mg/kg are present in the South Channel. The water depth in the South Channel is typically 1 to 2 feet, meaning barge-based mechanical dredging equipment cannot be floated into the area. In addition, the South Channel is fairly wide (100 to 200 feet), and the shoreline is heavily vegetated, so using a crane from the shoreline would be problematic for the entire width of the channel. Underwater sediment removal is further complicated by the presence of woody

debris from historical activities in the area. The physical setting of the South Channel allows for cost-effectively dewatering the channel. Therefore, dry excavation was selected as the best option for removing contaminated sediment from the South Channel in Phase III.

#### 5.4.1 Site Preparation and Dewatering

In order to perform dry excavation, access must be obtained to the South Channel directly from land. Since the South Channel does not border the facility, an access agreement would need to be reached with the City of Marinette to use the property south of the South Channel where the boat landing is located. An access road, approximately 220 feet long, 20 feet wide, and 12 inches thick, would need to be built by first clearing and grubbing the existing trees and other vegetation, and then laying down geotextile and gravel. Once the road is built, sheet piling would need to be installed across the west end of the South Channel as shown on the drawings in Appendix C. The existing road through the wetlands area on the Tyco property that adjoins the City of Marinette property will need to be improved as well to handle the truck traffic.

A vibratory hammer will be used to install approximately 300 linear feet of sheet piling across the west end of the South Channel. The sheets are estimated to be 25 feet long.

Once the sheet piling is installed, free water on top of the sediment will be directly discharged to the river until turbidity in the water exceeds 80 mg/L TSS. Water exceeding this threshold will be routed to the onsite temporary water treatment system.

#### 5.4.2 Excavation Activities

Standard excavation equipment will be used to remove the materials from the South Channel. A track-mounted backhoe will be used to stabilize the soft sediment in situ, excavate the stabilized sediment, and load it into articulated trucks for transport back to the staging area on the Tyco property. Debris that interferes with soft sediment removal will be removed with the backhoe and transported to the site to be staged and eventually disposed offsite. In situ stabilization will be accomplished by dumping loads of fly ash and cement next to the mixing operation, using the backhoe to pick up and add the reagents to the soft sediment, and mixing the reagents into the sediment with the backhoe bucket. Once the reagents have been mixed into the sediment, the backhoe will be used to load the sediment into articulated hauling trucks which will transport the material back to the staging area onsite.

The estimated production rate is 600 yd<sup>3</sup> per day, so a total of 20 days is estimated to remove the 12,000 yd<sup>3</sup> of soft sediment.

### 5.5 Dredged Material Disposal

As stated previously, the stabilized dredged material will be tested to verify that it passes the paint filter test and leachable arsenic has been reduced to less than 5 mg/L. The stabilized material will then be directly loaded into trucks and hauled offsite for disposal at an approved facility. It is assumed that the stabilized dredged material will be disposed at a RCRA Subtitle D landfill within 40 miles of the project site.

## 5.6 Water Quality

### 5.6.1 River Water Quality

#### Turbidity Control through Implementation of Best Management Practices

The potential to create turbidity and impact river water quality during mechanical dredging will be minimized by the dredging contractor's adherence to mechanical dredging BMPs. These BMPs will be modified slightly to account for the use of conventional navigational bucket with teeth for dredging of semi-consolidated material and glacial till. A list of BMPs for the dredging of soft sediment is provided below:

- Scows shall be watertight and inspected to confirm water tightness prior to dredging operations and dredged material transport.
- An environmental clamshell bucket shall be used for mechanical dredging of soft sediment.
- "Sweeping" to contour the bottom of the dredge cut shall not be permitted.
- Dredging of slopes shall proceed from top of slope to toe of slope.
- The dredging contractor shall utilize positioning devices (such as GPS) to allow the operator to be aware of the location of the dredge bucket in relation to the top of the sediment.
- The contractor shall use an experienced environmental dredging operator who is capable of implementing appropriate BMPs to limit resuspension of sediment.
- The operator shall minimize overfilling of the dredge bucket.
- The operator shall reduce the rate of bucket descent and retrieval as necessary.
- The operator shall perform single bites with the bucket, and each bucket shall be brought to the surface and emptied between bites.
- The operator shall release excess water at surface slowly.
- The operator shall not overfill scows with dredged material.
- Oil booms shall be available for emergency use.

Silt curtains will be used for the mechanical dredging work. The silt curtains will be placed around the contiguous dredging areas as shown on the drawings in Appendix C.

The success of the contractor's efforts to control release of turbidity will be evaluated through river water monitoring activities as described in Section 7.1. If a turbidity exceedance is noted, the dredging contractor will be consulted and the source of the turbidity will be identified. If dredging activities are suspected, the dredging process or equipment will be modified so the turbidity criterion is met.

#### Release of Dissolved Phase Arsenic during Dredging Activities

The release of particulate arsenic during mechanical dredging operations will be minimized by using BMPs to minimize dredging-induced turbidity. However, turbidity control

measures such as turbidity curtains will not be successful in limiting release of dissolved-phase arsenic during dredging activities. For a complete description of the concerns with arsenic release during dredging activities, refer to the *Sediment Remediation Work Plans Evaluation Memorandum* in Appendix A.

## 5.6.2 Wastewater from Stabilization and Decontamination Activities

### Wastewater Sources

Wastewater will be generated from several sources during the handling, stabilization, and disposal of the dredged material. The following wastewater sources will be routed to the onsite temporary water treatment system:

- Free water from the dredged sediment that is gravity drained (Phases I and II)
- Decontamination water (Phases I, II, and III)
- Precipitation on the staging pad (Phases I, II, and III)
- Direct discharge of water from the South Channel prior to and during dry excavation once the concentration of TSS exceeds 80 mg/L (Phase III)

The water treatment system itself will generate process wastewater, which will need to be hauled offsite and disposed.

### Wastewater Volumes

The rate of water generation and treatment was calculated over a 24 hours per day, 7 days per week period since dredging activities also are assumed to occur over the same period. Volumes given below might not add up precisely because of rounding.

#### *Free Water Removed from Sediment (Phases I and II)*

During Phase I, the dredging rate is estimated to be 1,300 yd<sup>3</sup> per day. The estimated volume of water draining from sediment dredged with an environmental bucket is 11,000 gallons per day (gpd), or 7.4 gallons per minute (gpm). During Phase II, the dredging rate is estimated to be 1,000 yd<sup>3</sup> per day. The estimated volume of water draining from sediment dredged with a conventional clamshell bucket is 29,000 gpd, or 20 gpm.

Total free water generated from dredging will be as follows:

- During Phase I: (11,000 gpd)\*(46 days) = 0.5 million gallons
- During Phase II: (29,000 gpd)\*(149 days) = 4.3 million gallons

#### *Decontamination Water (Phases I, II, and III)*

A 4 gpm pressure washer is assumed to be used for decontamination activities. Decontamination activities performed during the dredging work will include decontamination of debris, equipment, and trucks. Total volume is estimated to be 1,400 gpd, or 1.0 gpm. The wastewater generated from decontamination activities will be collected in the sump along with the other wastewater sources and sent to the water treatment system.

Total water generated will be as follows:

- During Phase I: (1,400 gpd)\*(46 days) = 0.07 million gallons
- During Phase II: (1,400 gpd)\*(149 days) = 0.2 million gallons
- During Phase III: (1,400 gpd)\*(20 days) = 0.03 million gallons

***Water from Precipitation on Pad (Phases I, II, and III)***

Average monthly rainfall for the Green Bay, Wisconsin, area during the potential construction season is as follows (rswweather.com 2010):

- May: 2.75 inches
- June: 3.43 inches
- July: 3.44 inches
- August: 3.77 inches
- September: 3.11 inches
- October: 2.17 inches

A monthly rainfall of 3 inches was used to calculate rainwater that falls on the process pad and requires treatment. Using a proportionate average daily rate, the total volume is estimated to be 18,000 gpd, or 13 gpm. Total water generated will be as follows:

- During Phase I:  $(18,000 \text{ gpd}) \times (46 \text{ days}) = 0.8 \text{ million gallons}$
- During Phase II:  $(18,000 \text{ gpd}) \times (149 \text{ days}) = 2.7 \text{ million gallons}$
- During Phase III:  $(18,000 \text{ gpd}) \times (20 \text{ days}) = 0.4 \text{ million gallons}$

***Direct Discharge of Water from the South Channel (Phase III)***

The volume of wastewater generated during Phase III from dewatering the South Channel cell will be comprised of two components. The first source of wastewater will be the water remaining after the initial phase of dewatering, direct discharge of water to the river, is completed. Approximately 0.5 foot of water over the footprint of the entire cell will need to be pumped to the water treatment system, and this volume is estimated as 1.3 million gallons, which will be pumped out over 14 days, for an average flowrate of 93,000 gpd, or 64 gpm. Maintenance dewatering is estimated to be 65 gpm for the 20 days of active sediment excavation in the South Channel. This is an estimated 94,000 gpd. Total water generated by dewatering activities during Phase III will be 1.3 million gallons +  $(94,000 \text{ gpd}) \times (20 \text{ days}) = 3.2 \text{ million gallons}$ .

***Summary of Wastewater Generated (Phases I through III)***

During Phase I, wastewater generated will be 0.5 million gallons (free water in sediment) plus 0.07 million gallons (decontamination water) plus 0.8 million gallons (precipitation), for a total of 1.4 million gallons, and an average flow rate of 21 gpm over 24 hours.

During Phase II, wastewater generated will be 4.3 million gallons (free water in sediment) plus 0.2 million gallons (decontamination water) plus 2.7 million gallons (precipitation), for a total of 7.2 million gallons, and an average flow rate of 34 gpm over 24 hours.

During Phase III, wastewater generated will be 0.03 million gallons (decontamination water) plus 0.4 million gallons (precipitation) plus 3.2 million gallons (direct discharge for South Channel cell dewatering activities) for a total of 3.6 million gallons, and an average flow rate of 123 gpm over 24 hours.

Total wastewater generated during the corrective activities is estimated to be 12 million gallons. Estimated flow to the water treatment system will vary, but will be at a maximum of 123 gpm during Phase III. Therefore, the treatment system should be designed to handle a peak flow of approximately 150 gpm.

RO process waste will be approximately 20 percent of the total flow to the treatment system. This will be reduced further by the use of an evaporator unit, which will reduce the volume of water by another 75 percent. Therefore, total volume of rejectate water from the evaporator unit requiring disposal at an offsite hazardous waste facility will be 0.6 million gallons.

### **Wastewater Treatment**

The conceptual design for the temporary onsite water treatment system is shown on the drawings in Appendix C. This conceptual design is provided as a possible configuration, but the dredging contractor can propose an alternative water treatment system design. The treated water will be considered for reuse onsite.

The water treatment system will be set up on the northern portion of the asphalt pad. Wastewater sources will be combined in an equalization tank and pumped into an MF unit. The rejectate from the MF unit will be run through a filter press and the filter cake will be added to the dredged materials for stabilization. The filtrate from the filter press will be routed back to the wastewater stream before the MF unit. Water passing through the MF unit will have sulfuric acid added to inhibit scaling before passing through a dual phase RO unit. The concentrate from the RO process will be further concentrated in an evaporator unit. The concentrate from the evaporator unit will be stored in a tank and then hauled away for disposal at a hazardous waste facility. The treated water from both the RO and evaporator units will be stored in holding tanks for reuse at the Tyco facility.

Influent and effluent samples will be collected from the water treatment system to monitor performance. If not all of the treated water can be used at the Tyco facility, a WPDES permit will be obtained for discharge to the Menominee River, and discharge and sampling will be done in compliance with the permit.

## **5.7 Working Season and Hours of Operation**

Most activities associated with the dredging work will be performed up to 24 hours per day, and 7 days per week. Water treatment operations will be performed up to 24 hours per day, 7 days per week. The dredging contractor will determine the actual hours of operation.

Mobilization is anticipated to start in late winter in 2012 (refer to the project schedule in Appendix D). It will be necessary to schedule activities to accommodate the current commercial and industrial uses of the Menominee River. The dredging schedule will be coordinated with USEPA, WDNR, and the U.S. Fish and Wildlife Service (USFWS) to minimize potential disturbance of fish spawning during the spring and fall seasons. The dredging contractor will be responsible to coordinate with local industrial facilities to accommodate the arrival and departure of commercial ships delivering raw materials and with the local agencies as necessary.

## **5.8 Decontamination and Site Restoration**

After mechanical dredging activities have been completed, decontamination activities will be performed. Equipment to be removed from the river will be power washed in place or over the river with water, prior to transport, to remove sediment and invasive species such as mussels.

Land-based equipment will be washed on the asphalt pad with the wash water being captured and treated. Rinse water will be collected in the sump through the outfall pipeline and will be pumped to the water treatment system. Following equipment decontamination, the asphalt pad will be washed to remove visible residual sediment.

Once decontamination has been completed, the temporary infrastructure built for the mechanical dredging work will be removed from the site. The docking platform, drip protection, and access walkway will be disassembled and taken offsite. The water treatment equipment will be decommissioned and taken offsite. Temporary access roadway materials will be sampled and taken offsite for reuse if not contaminated or disposed at an appropriate landfill if contaminated. Previously vegetated areas that were impacted by corrective activities will be restored to pre-construction conditions to the extent practical and replanted with native species.

## SECTION 6

# Compliance with Applicable Requirements

---

This list of applicable requirements was developed based on the review of recent site data and specific components of this design. The requirements that have unique aspects affecting the implementation of the mechanical dredging corrective action at this site are based on the specific components of the project and are discussed below.

## 6.1 Rivers and Harbors Act

Section 10 of the Rivers and Harbors Act of 1899, 33 U.S. Code (USC) §401 et seq. and 33 Code of Federal Regulations (CFR) Parts 403 and 322, prohibits the creation of obstructions to the capacity of (that is, the excavation or fill within the limits of) the navigable waters of the United States. This includes typical requirements to be met for dredging and filling within a navigable waterway such as measures to minimize resuspension of sediments and erosion of sediments and stream banks during excavation. The project will be designed to meet the requirements of Section 10 of the Rivers and Harbors Act.

## 6.2 Clean Air Act

The CAA, 40 CFR Parts 50 through 99, is intended to protect the quality of air and promote public health. Title I of the Act directs USEPA to publish national ambient air quality standards for “criteria pollutants.” The National Ambient Air Quality Standards, Section 109 provides specific requirements for air emissions including, but not limited to, particulates, volatile organic compounds, and hazardous air pollutants. USEPA also has provided national emission standards for hazardous air pollutants under Title III of the CAA. Hazardous air pollutants are designated hazardous substances under the Comprehensive Environmental Response, Compensation, and Liability Act (CERCLA). The CAA Amendments of 1990 greatly expanded the national emission standards for hazardous air pollutants by designating 179 new hazardous air pollutants and directing USEPA to attain maximum achievable control technology standards for emission sources. Such emission standards are potential requirements for remedial actions producing air emissions or regulated hazardous air pollutants.

The CAA is considered applicable for activities that have the potential of causing particulate emissions, such as handling the dewatered sediment. Although significant amounts of airborne particulates are not likely to be generated, stabilization activities may cause some airborne particulates. Therefore, best available practices will be used, as necessary, to control potential particulate emissions. A plan to measure and mitigate air emissions during the implementation of the remedy will be included as part of the site management plan.

## 6.3 Clean Water Act

The CWA, 33 USC §1251 to 1376 and 33 CFR Part 323, provides regulations for the discharge of pollutants into the waters of the United States. It requires USEPA to set water quality

standards for all contaminants in surface waters, and requires that permits be obtained for discharging pollutants from a point source into navigable waters such as the Menominee River. The CWA also regulates dredged and fill discharges. Although actual discharge of the dredged material back into the river is not anticipated, excavation within the river constitutes discharge of dredged material.

Regulations promulgated under the authority of the CWA require permits for dredging or excavating sediments in navigable water. The applicable permits include the Section 404 permit, authorized by USACE, and the Section 401 Water Quality Certification issued by WDNR. A Section 401 certification is necessary for all projects requiring a Section 404 permit and is part of the Section 404 permit review process. Because the Menominee River is designated as a navigable waterway, the requirements and conditions of the Section 404 permit and Section 401 certification will be met. Typical requirements include actions to minimize resuspension of sediment and control erosion during dredging operations.

## 6.4 Soil Erosion and Sediment Control Permit

The SESC permit will be obtained for the dredging activities and construction of support structures. The SESC permit will require implementation and maintenance of soil erosion and sedimentation control measures, which will be included in the design. A notice of coverage will need to be submitted to WDNR and local agencies.

## 6.5 Endangered Species Act

The Endangered Species Act of 1973, 16 USC §1531 et seq. and 15 CFR Part 930, requires that federal agencies ensure that any action authorized, funded, or carried out by the agency is not likely to jeopardize the continued existence of any threatened or endangered species or destroy or adversely modify critical habitat. USFWS lists four species/habitats known to occur in Marinette County: the gray wolf (*Canis lupus*), Kirtland's warbler (*Dendroica kirtlandii*), piping plover (*Charadrius melodus*) [critical habitat], and the Canada lynx (*Lynx Canadensis*). The gray wolf and Kirtland's warbler are listed as endangered and the Canada lynx is listed as threatened (USFWS 2010).

A Wisconsin Natural Heritage Inventory (NHI) request will be performed prior to sediment dredging, and coordination with WDNR will occur based on the results of the NHI request.

Based on the location of dredging activities that will be conducted during this project and where the dewatering process will occur at the Tyco property, it is not anticipated that federal or state listed species or critical habitats will be affected. To comply with these requirements, Tyco will consult with WDNR to obtain concurrence that no critical habitat will be adversely affected during implementation of the dredging operations.

## 6.6 National Historic Preservation Act

The National Historic Preservation Act, 16 USC §661 et seq. and 36 CFR Part 65, establishes procedures for preserving scientific, historic, and archaeological data that might be destroyed through alteration of terrain as a result of a federal construction project or a federally licensed activity or program. If scientific, historic, or archaeological artifacts are discovered at the project site, work that could impact discovered artifacts will be halted

pending the completion of any data recovery and preservation activities required pursuant to the Act.

The likelihood for unanticipated discovery of scientific, historic, or archaeological artifacts during implementation of the corrective action is small. However, if such a discovery is made, appropriate and necessary measures will be implemented to ensure adherence to the Act.

## 6.7 RCRA Regulations and Administrative Order on Consent

As previously mentioned, this sediment removal action is being conducted pursuant to a RCRA 3008(h) AOC, administered by USEPA Region 5. The work described herein complies with the AOC, as well as the applicable RCRA regulations that govern the management and disposal of remediation waste.

The regulatory considerations associated with the sediment removal and disposal work are outlined below:

- In accordance with 40 CFR Section 261.4, because sediment removal is being done under a Section 404 permit, the dredged material exclusion states that the sediments are not considered a hazardous waste. The exclusion states:
  - (g) Dredged material that is not a hazardous waste. Dredged material that is subject to the requirements of a permit that has been issued under Section 404 of the Federal Water Pollution Control Act (33 USC 1344) or Section 103 of the Marine Protection, Research, and Sanctuaries Act of 1972 (33 USC 1413) is not a hazardous waste. For this paragraph (g), the following definitions apply:
    - (1) The term dredged material has the same meaning as defined in 40 CFR 232.2.
    - (2) The term permit means:
      - (i) A permit issued by USACE or an approved state under Section 404 of the Federal Water Pollution Control Act (33 USC 1344);
      - (ii) A permit issued by USACE under Section 103 of the Marine Protection, Research, and Sanctuaries Act of 1972 (33 USC 1413); or
      - (iii) In the case of USACE civil works projects, the administrative equivalent of the permits referred to in paragraphs (g)(2)(i) and (ii) of this section, as provided for in USACE regulations (for example, see 33 CFR 336.1, 336.2, and 337.6); in this case, the exemption is limited to the Section 404 permit activities.
- Since the dredged materials are not at this point considered a hazardous waste, per the exclusion, they can be transported back onsite without being considered a hazardous waste.
- Once the sediments dry out and are ready to be moved, the materials become a new waste stream that needs to be characterized and profiled for the offsite disposal. Under RCRA, a generator does not have the responsibility to characterize their material until it is generated, so characterization samples of the dredge spoils will be taken when they

are onsite to determine next steps. If analytical results indicate the material passes TCLP criteria, the material will be stabilized to the extent necessary to pass a paint-filter test and be accepted at an appropriately permitted Subtitle D facility. If sampling results indicate the materials fail TCLP criteria and would be considered as characteristic, the materials will need to be treated prior to transport to the disposal facility. In order to perform onsite treatment, the site, including the river sediment area and the uplands area, will be defined as an area of contamination.

## 6.8 Coastal Zone Management Act

The Coastal Zone Management Act (CZMA), under 16 USC §1451 et seq. and 15 CFR Part 930, states that all federal agency activities affecting any coastal use, resource, or zone will be conducted in a manner that is consistent, to the maximum extent possible, with the enforceable policies of approved management programs.

The State of Wisconsin – Department of Administration Wisconsin Coastal Management Program (WCMP) was established in 1978 under the federal CZMA. Through its federal consistency review authority, the WCMP has broad opportunities to influence federal government activities, construction, funding, permitting, and other actions proposed within the coastal zone. It promotes coordination between state and federal policies, programs, and agencies. The boundaries of the coastal zone subject to the WCMP extend to the state boundary on the waterward side and, on the inland side, include the 15 counties with frontage on Lake Superior, Lake Michigan, or Green Bay. The dredging activities will be located entirely within the designated Wisconsin Coastal Zone area of the Menominee River.

In order to be subject to federal consistency review, a project must meet the following basic criteria. The project must:

- Be located within or affect Wisconsin's coastal zone;
- Involve the federal government through funding, permitting or direct action; and
- Meet certain thresholds. (The state will focus on projects that involve a state-managed use and meet associated thresholds established under the Wisconsin Environmental Policy Act, which determine if they require detailed environmental review.)

Evaluation of federal consistency with the WCMP is based upon the following criteria:

- Is the activity consistent with the federally approved state coastal policies (set forth in Chapter I.C., including approved county shoreland ordinances and approved floodplain ordinances)?
- Is the activity consistent with specific management policies for designated state managed special coastal areas?
- Does the activity allow for an opportunity for full public participation?

The proposed remediation project meets the criteria established by the WCMP; therefore, a federal consistency review will be initiated.

## 6.9 Wisconsin Chapter 30 permit

Chapter 30 of Wisconsin Statutes declares all lakes, streams, sloughs, bayous, and marsh outlets which are navigable-in-fact for any purpose whatsoever to be navigable and public waters. Placement of structures, dredging, and similar activities in or adjacent to navigable waters are regulated under Chapter 30 of Wisconsin Statutes, and often require permits from WDNR. A Chapter 30 permit will be obtained from WDNR for dredging activities as well as impacts to any jurisdictional wetlands within the project area.

## 6.10 NPDES Stormwater Permit

The National Pollutant Discharge Elimination System (NPDES) is a federal program that originated in the CWA, but has since been delegated to the states. WDNR is authorized to administer the NPDES permit program, which requires permits for the discharge of stormwater associated with construction activities. The Tyco facility has an existing NPDES permit for industrial and manufacturing purposes. A Notice of Intent (NOI) will be submitted to WDNR more than 30 days prior to construction to negotiate use of the temporary treatment system during sediment removal and stabilization activities.

Under 40 CFR Parts 122 and 125, the requirements for the development and implementation of a stormwater pollution prevention plan or a stormwater best management plan are outlined, along with the monitoring and reporting requirements for facilities. The stormwater pollution prevention plan will be submitted along with the NOI 30 days prior to construction.

## 6.11 City of Marinette Building Permit

A temporary building permit is required from the City of Marinette for the support structures at the Tyco property. A permit application will be prepared and submitted to the City of Marinette to obtain a temporary building permit before implementation of the corrective action.

## 6.12 OSHA Requirements

A health and safety plan for construction activities that is in accordance with the Occupational Safety and Health Administration (OSHA) requirements listed in 20 CFR 1910 and 20 CFR 1926 will be required.

## 6.13 Waterway Markers Permit

Waterway markers have to meet U.S. Coast Guard requirements and are also regulated by WDNR through Section 30.74(2), Wisconsin Statutes and Chapter NR 5.09, Wisconsin Administrative Code. Any waterway markers must be in compliance with the U.S. Coast Guard requirements.

A brief summary of Chapter 30.74(2) and 30.77 is that a town, village, or city may adopt an ordinance, in the interest of public health, safety or welfare applicable on waters of the state within the local unit of government's jurisdiction. WDNR assists the community in enforcing the ordinance (30.74(3)).

Under Chapter 30.77(3)(b), it appears that a county could also adopt an ordinance; however, the county ordinance would supercede any local ordinances that would be developed and may not be in the interest of local control or acceptable throughout the county.

WDNR has interpreted the regulation that waterway marker enforcement cannot occur unless the local jurisdiction enacts an ordinance adopting the authority granted under Chapter 30.74(2). For example, while the markers may follow U.S. Coast Guard signage requirements for marking a Slow No-Wake Zone, WDNR would not be able to enforce the Slow No-Wake Zone unless the local jurisdiction first adopted an ordinance to accept local waterway marker acceptance and, thereby, grant WDNR enforcement authority of the ordinance. A WDNR waterways marker permit will be obtained prior to installing the markers on the Menominee River.

## 6.14 Notice to Mariners

A Notice to Mariners will be issued through the U. S. Coast Guard once the dredging schedule is known more precisely. Tyco's corrective activities oversight contractor will coordinate with the U.S. Coast Guard in consultation with the dredging contractor once the dredging contract is awarded.

# Performance Monitoring and Operations and Maintenance Requirements

---

This section provides a brief summary of the performance monitoring and operations and maintenance (O&M) requirements for the corrective activities. Additional details regarding sample collection, sampling methods and data management will be developed as part of the final design.

## 7.1 Water Quality Monitoring

### 7.1.1 River Water Quality Monitoring

The effectiveness of the dredging contractor in performing mechanical dredging while using BMPs to minimize the associated water quality impacts will be determined through monitoring of the turbidity in the river. The proposed turbidity control standard for work during mechanical dredging activities is no more than 80 mg/L TSS above the background reading.

Surface water monitoring of TSS and/or turbidity will be performed to collect data that will be used to evaluate the potential for sediment resuspension during dredging activities. Before commencing dredging activities, two turbidity monitoring stations will be installed for measuring turbidity during dredging and located as shown on the drawings in Appendix C. The first will be located on the southern side of the Menominee River, near the western boundary of the Tyco property. This location will be approximately 800 feet upstream of the Turning Basin and will be used to determine the daily average background turbidity level.

The second turbidity monitoring location will be approximately 1,000 feet east of the eastern side of the Turning Basin and positioned near the southern side of the main river channel. This location will be used to monitor potential suspended sediment entering the river from dredging activities in the Turning Basin. The precise locations will be selected once dredging activities begin based upon observed responses of the upstream and downstream turbidity sensors to background turbidity, as well as the consideration of avoiding damage due to vessel traffic.

Turbidity sensors will be deployed at the background location and at the second location at mid-depth of the channel. Turbidity readings will be transferred by cellular modem telemetry, compiled, and made available on a password-protected Web site within 5 minutes of each reading. Data from the turbidity sensors also will be stored in an integrated data logger that can be accessed in the event the telemetry system is inoperable. The readings will be recorded once every 10 minutes at both turbidity monitoring stations. A rolling average of six consecutive readings (1 hour) for both of the locations will be used as the basis of comparison.

If the turbidity levels exceed the criterion above the background location, additional turbidity measurements between the downstream project extent and the downstream monitoring location will be performed to assess the BMPs and determine the cause for increased turbidity. If the turbidity increase is determined to be caused from non-dredging activities, the dredging will continue. If the turbidity is determined to be elevated because of the dredging activities, work will temporarily stop until implementation of corrective measures are demonstrated and turbidity levels at the downstream monitoring location are below the project turbidity criterion.

If an obvious outlier appears, it shall be eliminated from the rolling average calculation. An outlier will be defined as a reading that is outside the range of 50 to 200 percent of the average of the three previous readings. In addition, to be considered an outlier, the following reading must return to a range of 75 to 133 percent of the average of the three readings preceding the outlier. In practice, it is common to get occasional one-time spikes that cannot be tied to activities in the water. If this happens regularly (that is, more frequently than twice per day), the sensor will be inspected and cleaned, repaired, or replaced.

### **7.1.2 Water Treatment System Monitoring**

Influent and effluent from the water treatment system will be sampled daily for total arsenic concentrations. The treated water might also be sampled for other parameters as required for reuse at the Tyco facility or for discharge in accordance with the WPDES permit, if applicable. Additional points in the treatment system might be sampled and other analyses might be run as well to monitor system performance.

Samples for total arsenic analyses will be submitted to a nearby laboratory and immediate results (or 24-hour turnaround) will be requested. Alternatively, an onsite laboratory might be set up during the corrective activities if the quantity of analyses and turnaround time justify the cost. This will be evaluated later in the design process. If sample results indicate arsenic concentrations or other chemicals above reuse or discharge criteria, discharge of water will stop immediately, and the system will be inspected and modified so that treated water is once again in compliance.

## **7.2 Post-Dredging Sediment Confirmation Sampling and Surveys**

### **7.2.1 Surveys**

As mentioned previously, soft sediment will be removed in Phase I before removing the semi-consolidated material in Phase II. Phase III will be the removal of contaminated soft sediment from the South Channel. A bathymetric or terrestrial survey will be performed after the completion of Phase I, II, and III to document that the dredging cut lines have been achieved.

### **7.2.2 Confirmation Sampling**

Confirmation sampling will be performed after material removal in Phase I, II, and III. Limited confirmation sampling will be performed following Phase I, only where contaminated soft sediment overlies soft sediment with arsenic concentrations less than

50 mg/kg, and no contamination exceeding 50 mg/kg is present in semi-consolidated material beneath. For Phase II, confirmation sampling for arsenic analysis will be performed in areas where semi-consolidated material with arsenic contamination levels below 50 mg/kg remain to document that the contaminated material has been removed. Also in Phase II, confirmation sampling will be conducted for visual verification that glacial till has been reached in areas where all semi-consolidated material are to be removed because they were contaminated with arsenic concentrations greater than 50 mg/kg. For Phase III, confirmation sampling for arsenic analysis will be performed, except in areas where all soft sediment has been removed.

Confirmation sampling locations and other details will be provided in the comprehensive confirmation sampling plan, which will be developed after acceptance of the final design and at least 90 days before completion of construction (per Attachment 2, Section IVA, 2nd paragraph of the AOC).

### 7.3 Air Monitoring

Air monitoring for particulate matter will be performed because of the possibility of dust being released during dredged material and reagent handling. This will only be done during Phase III (excavation of soft sediment from the South Channel), because reagents will be directly mixed with the sediment in situ, and this activity has potential to create dust. During the other phases, reagents will be added to wet materials in a pugmill, which will reduce potential for dust emissions. Real-time monitors that measure particulate matter finer than 10 micrometers in diameter and smaller (PM<sub>10</sub>) will be used for monitoring. Three locations will be used to record continuous data on the Tyco property in the west, south, and east directions between 300 and 400 feet away from the dredged material and reagent handling and operations area.

SECTION 8

# Preliminary Construction Schedule

---

A preliminary project schedule for the sediment removal activities is provided in Appendix D.

## SECTION 9

# Preliminary Cost Estimate

---

A preliminary compensation schedule, which includes lines items and estimated quantities, is included in Appendix E. Implementation of the SRWP is estimated to cost between \$23.7 million and \$50.8 million. The cost estimate has been provided in Appendix F. Preliminary cost estimate assumptions are based on the best available information regarding the anticipated scope of work, previous experience, and general site knowledge. Changes in the cost elements are likely to occur as a result of new information and design results. This is an order-of-magnitude cost estimate that is expected to be within +50 to -30 percent of the actual project costs.

SECTION 10

# Biddability, Constructability, and Operability Review

---

The activities proposed in this SRWP have been reviewed with an emphasis on biddability, constructability, and operability. The final basis of design report will be reviewed using these criteria as well. Any concerns noted during these reviews regarding biddability, constructability, and operability will be addressed before completing the final design.

## SECTION 11

# References

---

Dames & Moore. 1996. *Sediment Phase I Site Assessment*. Milwaukee, Wisconsin. October.

rssweather.com. 2010. Climate for Green Bay, Wisconsin. <http://www.rssweather.com/climate/Wisconsin/Green%20Bay/>. Accessed October 12, 2010.

URS Corporation (URS). 2001. *Summary of Findings Report; 1974 – 2000*. Milwaukee, Wisconsin. February.

URS Corporation (URS). 2002. *2001/2002 RCRA Facility Investigation and Interim Measures Investigation; Tyco Suppression Systems – Ansul; Stanton Street Facility*. Milwaukee, Wisconsin. September.


URS Corporation (URS). 2004. *2004 RCRA Facility Investigation; Addendum No. 4; Tyco Safety Products – Ansul; Stanton Street Facility*. Milwaukee, Wisconsin. September.

U.S. Environmental Protection Agency (USEPA). 2010. <http://www.epa.gov/glnpo/aoc/menominee.html>.

U.S. Fish and Wildlife Service (USFWS). 2010. [http://ecos.fws.gov/tess\\_public/countySearch!speciesByCountyReport.action?fips=55075](http://ecos.fws.gov/tess_public/countySearch!speciesByCountyReport.action?fips=55075). Accessed October 12, 2010.

## Figures


---



**Legend**

- Steel Sheet Pile Wall
- Approximate Location of Slurry Wall
- Approximate Area Previously Dredged to Bedrock
- Approximate Property Boundary
- USACE Project Limits for Federal Navigation Channel
- Sub-Areas

Figure 1  
 Site Map  
 Tyco Fire Products LP Facility  
 Marinette, WI








Figure 2  
 2010 Menomonee River Investigation Sampling Locations  
 Tyco Fire Products LP Facility  
 Marinette, WI



Southwest

Northeast



Not to scale.

FIGURE 3  
Conceptual Site Model – Existing Conditions  
*Tyco Fire Products LP Facility and Menominee River  
Sediment*





Figure 4  
Thickness of Soft Sediment  
Tyco Fire Products LP Facility  
Marinette, WI







Figure 5  
 Thickness of Semi-consolidated Sands and Silts  
 Tyco Fire Products LP Facility  
 Marinette, WI







Figure 6  
 Thickness of Glacial Till  
 Tyco Fire Products LP Facility  
 Marinette, WI







Figure 7  
 Top of Bedrock Elevation Contours  
 Tyco Fire Products LP Facility  
 Marinette, WI



# Surface Water Runoff and Direct Discharge of Slurry




FIGURE 8  
 Conceptual Site Model – Transport Mechanisms  
 Tyco Fire Products LP Facility  
 Marinette, WI





Figure 9  
 Top of Soft Sediment Elevation Contours  
 Tyco Fire Products LP Facility  
 Marinette, WI







Figure 10  
 Top of Semi-consolidated Sands and Silts Elevation Contours  
 Tyco Fire Products LP Facility  
 Marinette, WI







Figure 11  
 Top of Glacial Till Elevation Contours  
 Tyco Fire Products LP Facility  
 Marinette, WI







Figure 12  
 Maximum Arsenic Concentration in Soft Sediment  
 Tyco Fire Products LP Facility  
 Marinette, WI








Figure 13  
 Maximum Arsenic Concentration in  
 Semi-consolidated Sands and Silts  
 Tyco Fire Products LP Facility  
 Marinette, WI





**Legend**

- Maximum Arsenic Concentration Locations in Glacial Till

**Maximum Arsenic Concentration in Glacial Till (ppm)**

- < 20
- 20.01 - 50
- > 50

- Approximate Area Previously Dredged to Bedrock
- USACE Project Limits for Federal Navigation Channel
- Sub-Areas




Figure 14  
 Maximum Arsenic Concentration in Glacial Till  
 Tyco Fire Products LP Facility  
 Marinette, WI




Figure 15  
Sheet Piling Assessment  
Cross Section Locations  
Tyco Fire Products LP Facility  
Marinette, WI

A

A'




FIGURE 16  
 Sheet Piling Assessment  
 Cross Section A-A'  
 Tyco Fire Products Facility

**B**

**B'**




FIGURE 17  
 Sheet Piling Assessment  
 Cross Section B  
 Tyco Fire Products Facility




Figure 18  
Total Thickness of Arsenic Contaminated  
Material to be Removed  
Tyco Fire Products LP Facility  
Marinette, WI

**Appendix A**  
**Sediment Remediation Work Plans Evaluation**  
**Letter**

---



CH2M HILL  
135 South 84th Street  
Milwaukee, WI  
53214  
Tel 414.272.2426  
Fax 414.272.4408

December 1, 2010

**SUBMITTED VIA E-MAIL AND REGULAR MAIL**

Mr. Gary L. Cygan  
U.S. Environmental Protection Agency  
77 West Jackson Blvd. DE-9J  
Chicago, IL 60604-3590

Subject: Sediment Remediation Work Plans Evaluation--Tyco Fire Products LP  
Stanton Street Facility  
USEPA #WID 006 125 215

Dear Mr. Cygan:

On behalf of Tyco Fire Products LP (Tyco, formerly known as Ansul Incorporated), this letter is submitted to support the work plans prepared pursuant to Section VI, 11, paragraphs d, e, and f of the February 26, 2009, Administrative Order on Consent (AOC) between Tyco and the U.S. Environmental Protection Agency (USEPA).

Section VI, 11, paragraph f allows Tyco to propose an alternative to the Section VI, 11, paragraph d requirement to mechanically dredge the semi-consolidated sands and silt layer ("semi-consolidated material") between the soft sediments and the glacial till. Accordingly, an Alternative Menominee River Sediment Removal Plan (AMRSRP) that proposes to cap this layer is being submitted.

USEPA has informed Tyco that USEPA interprets the AOC as requiring Tyco to submit a work plan to mechanically dredge the semi-consolidated material, per Section VI, 11, paragraph d, even if Tyco submits an alternative plan under Section VI, 11, paragraph f. Although Tyco does not understand or agree with this interpretation, to avoid unnecessary procedural disagreements, we also have prepared a Menominee River Sediment Removal Work Plan (SRWP) that uses mechanical dredging for the semi-consolidated material. Tyco does not believe that dredging the semi-consolidated material is technically or economically implementable. As explained in the remainder of this letter and in the work plans to be submitted under separate cover, dredging the semi-consolidated material threatens the structural integrity of the sheet pile barrier wall, will cause a substantial release of arsenic which is likely to endanger populations of aquatic receptors including game fish, and will cost approximately twice as much as the alternative approach detailed in the AMRSRP.

**As a result, Tyco proposes to implement the AMRSRP. The remainder of this letter evaluates and compares the approaches for the semi-consolidated material that are provided in the SRWP and AMRSRP. We believe that dredging the semi-consolidated material is technically and economically impracticable, and this letter and separately filed work plans provide the details necessary to support the approval and implementation of the AMRSRP. The SRWP is submitted only to accommodate USEPA's interpretation of the AOC.**

## Summary

Dredging the semi-consolidated material that exists between the soft sediments and the glacial till, as required by Section VI, 11, paragraph d of the AOC, will destabilize and threaten the integrity of the sheet pile barrier wall that was installed pursuant to Section VI, 11, paragraph b of the AOC. Thus, the SRWP approach as described in paragraph d of the AOC is technically impracticable.

In addition, the SRWP approach will cause uncontrollable releases of arsenic when dredging semi-consolidated material in the Turning Basin and in other areas of the river. The amount of arsenic released from these semi-consolidated materials is likely to result in substantial exceedances of Wisconsin's acute toxicity water quality criterion (WQC) for arsenic in surface water (340 micrograms per liter [ $\mu\text{g}/\text{L}$ ] [Wisconsin Administrative Code NR105]). The AMRSRP approach avoids both of these problems by capping the semi-consolidated material.

Section VI, 11, paragraph f of the AOC allows Tyco to propose "an alternative to removal of the sediment layer...between the soft sediments and the glacial till [i.e., the semi-consolidated material]" if the following conditions are met:

### **1. Removal of semi-consolidated material beneath soft sediment is economically and technologically impractical.**

- Approximately 5,000 cubic yards ( $\text{yd}^3$ ) of contaminated semi-consolidated material with arsenic concentrations significantly greater than 50 milligrams per kilogram ( $\text{mg}/\text{kg}$ ) cannot be removed because this material provides required structural support for the existing sheet pile barrier wall that was installed to contain contamination beneath the Tyco facility. The AMRSRP approach caps these semi-consolidated materials, eliminating the risk to the sheet pile barrier structural integrity and reducing arsenic releases from the semi-consolidated materials during and after active remediation.
- The AMRSRP approach eliminates environmental risks from the release of particle-associated and dissolved arsenic that will be caused by dredging the semi-consolidated material. The arsenic released during dredging will be at levels that are likely to endanger ecological receptors in the Menominee River near to and downstream of the dredging areas.
- Implementation of the SRWP is estimated to cost between \$23.7 million and \$50.8 million. Implementation of the AMRSRP approach is estimated to cost between \$11.7 million and \$25.1 million. Thus, the more environmentally protective alternative approach can be implemented for approximately half the cost of the AOC-specified (SRWP) remedy.

### **2. The proposed alternative protects human health and the environment.**

- The AMRSRP approach protects human health and the environment by removing soft sediment with arsenic concentrations greater than or equal to 50  $\text{mg}/\text{kg}$  and by

capping semi-consolidated material with concentrations greater than or equal to 50 mg/kg<sup>1</sup>. The capping and in-place containment approach for the semi-consolidated material under the AMRSRP is more environmentally protective in the short term as compared to dredging these materials because the AMRSRP reduces the mass of arsenic that will be released during SRWP dredging. The AMRSRP approach also is more environmentally protective in the long term because the SRWP requires removal of contaminated semi-consolidated material that must remain in place to support the existing sheet pile barrier wall, while the AMRSRP caps this material, retains the structural integrity of the barrier wall, and provides ongoing and immediate protection to the Menominee River fisheries and other ecological receptors.

**3. The proposed alternative is legally implementable.**

- The approach in the AMRSRP is legally implementable with the required state, local, and federal authorizations, including the U.S. Army Corps of Engineers (USACE). Permits and authorizations will be required to implement the approaches in either the SRWP or AMRSRP.

**4. The proposed alternative achieves an equivalent level of protection to monitored natural remediation (MNR).**

- The AMRSRP approach, capping those portions of the semi-consolidated material with arsenic concentrations greater than 50 mg/kg, provides superior protection as compared to MNR of these areas because the cap will reduce arsenic released from these areas.

## Project Background

Tyco prepared a corrective measures study (CMS; URS Corporation [URS] 2003a) and an addendum to the CMS (EarthTech 2007) that evaluated the technical and economic feasibility of remedial options for addressing the onshore contamination that exists at the Tyco facility. Corrective measures for the onshore facility included installing a vertical barrier wall (VBW) system and a groundwater collection and treatment system within the VBW.

A CMS was not conducted for the Menominee River sediment.

Tyco prepared and submitted a site-specific baseline risk assessment (URS 2003b) that concluded that the arsenic in the sediment potentially posed an unacceptable risk of adverse effects only to benthic organisms and only at concentrations greater than 89 parts per million (ppm).

In addition, at USEPA's request, Tyco prepared a cost/benefit analysis that compared the dredging costs and arsenic removal benefits of dredging *the soft sediments only* over a range of cleanup levels from 5 to 1,000 ppm total arsenic (URS 2003c). That analysis

---

<sup>1</sup> Tyco's site-specific baseline risk assessment (URS 2003b) concluded that the arsenic in the Menominee River sediments as currently configured poses no threat to human health and threatens benthic organisms and ecosystems only at concentrations greater than 89 mg/kg.

concluded that the cost/benefit point of diminishing returns for dredging the soft sediment was approximately 50 ppm.

USEPA's September 12, 2007 Statement of Basis (SOB) relied on the cost/benefit analysis and evaluated costs, feasibility, and risks of options to address the estimated 74,000 cubic yards of soft sediments that the cost/benefit report identified as containing arsenic contamination greater than 50 ppm. The SOB selected mechanical dredging as the preferred alternative for remediating these soft sediments, see SOB pp. 17 and 23, and both work plans that Tyco is submitting specify mechanical dredging to address contaminated soft sediments. The SOB did not address or consider the costs, feasibility and impacts of alternatives to address contamination in the semi-consolidated sand and silt layer between the soft sediments and the glacial till.

Accordingly, the impacts, feasibility and costs associated with alternatives for addressing contamination in the semi-consolidated materials were not considered in the SOB, or anywhere else, and the public was not provided the opportunity to review and comment on remedial options for the semi-consolidated material.

Instead, without the support of a cost or technical feasibility analysis, Section VI, 11, paragraph d of the AOC specifies a dredging-only remedy for the semi-consolidated material (the SRWP). The presumptive selection of dredging contradicts USEPA guidance as outlined in USEPA Office of Solid Waste and Emergency Response (OSWER) Directives 9200.1-90 (USEPA 2008) and 9285.6-08 (USEPA 2002), ("dredging is not the 'presumptive' remedy, but should be considered on an equal footing with other remedial options").

Tyco did not object to the dredging-only remedy in the AOC because the AOC specifically provided for an alternative (Section VI, 11, paragraph f) if during design development it was determined that the dredging-only remedy was technically and economically impracticable. In fact, this is what has happened. Our evaluation has shown that the presumptive remedy should not be implemented because it will jeopardize the sheet piling structure, it is less environmentally protective, and it is twice as costly as implementing the alternative approach outlined in the AMRSRP.

## Work Plan Approaches

Both the SRWP and the AMRSRP approaches include a plan to remove soft sediment containing arsenic concentrations greater than or equal to 50 mg/kg using mechanical dredging. (Dry excavation is used for removing the soft sediment but only in the South Channel area.) Various dredging technologies were evaluated but have been eliminated from further consideration as detailed in Attachment 1.

The VBW design prepared by AECOM, and implemented by Tyco in 2010, requires that at least 13 feet of semi-consolidated material and glacial till must remain in place adjacent to the sheet pile portion of the VBW to maintain the structural stability of the wall. Based on the 2010 sediment investigation results, much of the semi-consolidated material adjacent to the sheet piling contains arsenic concentrations exceeding 50 mg/kg. The SRWP requires mechanical dredging of this area. If these semi-consolidated materials are removed, the

sheet pile barrier wall will likely fail, which would result in direct long-term release of contamination.

Both the SRWP and AMRSRP use MNR “to remediate sediments remaining after sediment removal activities to a concentration of 20 ppm of arsenic.” The 20 ppm goal must be met within 10 years of completing the sediment removal.

The AMRSRP caps all of the semi-consolidated material that contains arsenic concentrations greater than or equal to 50 mg/kg including the semi-consolidated material that must remain in place to maintain stability of the VBW. In addition, the AMRSRP includes an evaluation of groundwater flow beneath the river following completion of the VBW to verify the elimination of groundwater gradients in the river in the areas proposed to be capped. If it is determined via collection of additional hydraulic data that groundwater continues to discharge to the river, additional measures (such as lowering the onshore groundwater elevation) will be undertaken to eliminate the possibility of groundwater upwelling through the semi-consolidated material. The AMRSRP includes a description of additional hydraulic information to be collected in support of the groundwater flow evaluation.

## RCRA Corrective Measures Alternatives Evaluation

The SRWP and AMRSRP approaches each were evaluated against USEPA’s performance standards and balancing criteria for the evaluation of Resource Conservation and Recovery Act (RCRA) corrective measure alternatives (USEPA 2000).

### USEPA Performance Standards

USEPA has established three performance standards for corrective measures:

- Protect human health and the environment
- Achieve media cleanup objectives
- Remediate the sources of releases

An evaluation against the performance standards for the corrective measures described in the SRWP and AMRSRP is detailed below.

### Protection of Human Health and the Environment

The removal of semi-consolidated material using mechanical dredging as required by Section VI, 11, paragraph d of the AOC and as detailed in the SRWP will release substantially more arsenic into the river during dredging than capping the semi-consolidated materials as described in the AMRSRP. The SRWP will cause greater environmental impacts in the short term as compared to leaving the semi-consolidated material in place and capping them as described in the AMRSRP.

The release of particle-associated and dissolved arsenic from the soft sediments during mechanical dredging operations can be minimized by using best management practices (BMPs). One of the BMPs is using an “environmental bucket” to minimize dredging-induced turbidity and, as a result, the release of arsenic to the environment. Because the corrective measures described in both the SRWP and AMRSRP include mechanical

dredging of the soft sediments using an environmental bucket, the environmental protection for dredging soft sediment under both approaches is identical.

Although using an environmental bucket is feasible for mechanical dredging of soft sediments, an environmental bucket cannot be used when dredging the semi-consolidated material. Based on data obtained during the 2010 sediment investigation, experience from previous mechanical dredging projects, and discussions with a dredging equipment supplier, an environmental bucket cannot be used to remove the semi-consolidated sands and silts because of the material's physical properties (Standard Penetration Test "N" value of 20 to 50 blows per foot). Instead, a conventional "clamshell" bucket with teeth or an open bucket must be used to remove these materials. According to research conducted by USACE (<http://el.erdc.usace.army.mil/resbrief/drbucket/drbucket.html>), mechanical dredging with a conventional clamshell bucket releases twice the suspended solids and, therefore, twice the arsenic that is in the solid phase, as compared to mechanical dredging with an environmental bucket. Much of the arsenic associated with these suspended solids will be desorbed and/or resolubilized when the suspended solids pass through the water column and come into contact with the oxidizing environment.

Unlike most contaminated sediment dredging projects which have hydrophobic contaminants that are strongly sorbed to solid particles, the sediments and semi-consolidated material in the Menominee River project area has a substantial dissolved arsenic component. As discussed in the conceptual site model included in the SRWP, the dissolved arsenic present in the semi-consolidated material is primarily the result of groundwater transport. Not only will the dissolved arsenic in the semi-consolidated material be released during dredging, but the particle-associated arsenic in these materials is in a more soluble form than are contaminants typically encountered at contaminated sediment sites (such as polychlorinated biphenyls and higher molecular weight polycyclic aromatic hydrocarbons). Thus, release of the dissolved as well as the soluble particle-associated arsenic cannot be controlled adequately during dredging.

Controls such as turbidity curtains will not be effective in limiting the release of dissolved-phase arsenic during dredging activities, nor do turbidity curtains prevent particulate-associated arsenic from dissociating from the particles and being dispersed in the dissolved phase to the water column. As a result, mechanical dredging of the semi-consolidated material under the SWRP approach will uncontrollably release a substantial amount of arsenic that is contained in the semi-consolidated material.

The release of arsenic during dredging of the semi-consolidated materials is very likely to cause exceedances of the Wisconsin Department of Natural Resource (WDNR) ambient acute toxicity WQC for arsenic (340 µg/L) during dredging operations in the Turning Basin and adjacent areas to the east. The supporting evaluation is presented in Attachment 2. As an example, an evaluation of the arsenic release shows that the acute toxicity WQC for arsenic would be exceeded while dredging contaminated semi-consolidated material in the Turning Basin with arsenic concentrations exceeding 1,000 mg/kg during average river flow conditions if as little as 0.88 percent of the total (particulate and dissolved) arsenic in the dredged material is released.

Moreover, these calculations assume average river flow in the Menominee River. However, the Turning Basin is physically offset from the main channel of the river and therefore is more quiescent. Because the Turning Basin does not experience the dilution and mixing that occurs with average channel river flows, releases of less than 0.88 percent of the total arsenic in the dredged material is likely to cause the acute toxicity WQC for arsenic to be exceeded.

Results of a National Resource Council (NRC 2007) review of data available from various dredging projects concludes that as high as 10 percent (with a median of 1 percent) of the dredged sediment mass is released into a water body as resuspended sediment. This same study notes that the contaminant mass released to the water column is likely even higher because of dissolved releases from freshly exposed and redeposited sediment (NRC 2007).

The studies cited in the NRC review that support the above statistics are from sites where contaminants typically are more hydrophobic than arsenic. Therefore, it is reasonable to expect, and a preliminary evaluation has concluded, that the mass of arsenic released by dredging the semi-consolidated material likely will be in the upper end of the range (close to 10 percent) presented in the NRC report (NRC 2007).

The AMRSRP proposes to cap rather than dredge the semi-consolidated material. Capping will greatly reduce the release of arsenic from this material, which will eliminate the risk that the acute toxicity WQC for arsenic will be exceeded during and after remediating the semi-consolidated material.

The cap used in the AMRSRP also immediately eliminates direct exposure to the environment of the contaminated semi-consolidated material that must remain in place to maintain VBW stability, thereby eliminating this exposure to ecological receptors in both the short term and long term.

**In summary, capping the semi-consolidated material using the AMRSRP approach is more protective of the environment than implementation of the SRWP.**

#### **Achieve Media Cleanup Objectives**

As required by the AOC, arsenic concentrations greater than or equal to 50 mg/kg are to be removed, or an alternative plan may be proposed. Achieving cleanup objectives, however, does not necessarily mean removal or treatment of all contaminated material above specific constituent concentrations. Standards may be achieved through a combination of removal, treatment, and engineering and institutional controls (USEPA 2003). Implementation of the remedial approach presented in the AMRSRP will result in semi-consolidated material greater than or equal to 50 mg/kg remaining in place, but these materials will be below a protective cap, thus limiting the mobility of the arsenic. With the elimination of a vertical gradient resulting from groundwater discharge, the only transport mechanism acting on the arsenic left under the cap is diffusion. However, diffusion is a slow process.

The estimated time required for the arsenic mass in the upper 4 feet of the semi-consolidated material to diffuse through the cap into the river would be between

960 and 120,000 years (Attachment 3)<sup>2</sup>. The average release rate is so small that, even at the most conservative estimate of 960 years, the average arsenic concentration in the water will be 0.037 µg/L and at no time will the concentration approach Wisconsin's chronic toxicity WQC for arsenic in surface water (148 µg/L [Wisconsin Administrative Code NR105]). From a risk perspective, placing a clean cap over the semi-consolidated material is equivalent to achieving the cleanup objective.

### Remediate the Sources of Releases

Sediment remediation is one part of a comprehensive approach to address soil, groundwater, and sediment impacts resulting from historical practices at the site. The required remedial actions include placing the VBW around the site to contain impacted soil and groundwater. In addition, groundwater management within the barrier system is accomplished through phyto-pumping and operation of a groundwater extraction system. These remedial actions were completed in 2010 and effectively address the primary source of impacts associated with the site.

Under the AMRSRP, sediment remediation will be accomplished through a combination of removal and source control as allowed by USEPA guidance (USEPA 2003, 2005). The AMRSRP approach achieves source control by capping those areas of the semi-consolidated material with arsenic concentrations exceeding 50 mg/kg that must remain in place adjacent to the VBW to prevent failure of the VBW, which would allow new releases of contaminants from the site. The AMRSRP approach also reduces exposure and contains the remaining arsenic located beyond the sheet pile wall. In addition, measures will be implemented under the AMRSRP approach to control groundwater flux through the semi-consolidated material if further evaluation indicates this is required. **Although total source "removal" is not achieved under the AMRSRP approach, effective remediation and "source control" are achieved. Thus, the AMRSRP is more protective than the SRWP approach.**

### Evaluation versus USEPA's Balancing Criteria

If more than one remedial approach meets USEPA performance standards, balancing criteria are considered to select the approach to be implemented. These balancing criteria include (USEPA 2000):

- Long-term reliability and effectiveness
- Reduction of toxicity, mobility, or volume of wastes
- Short-term effectiveness
- Implementability
- Cost
- State and community acceptance

Under RCRA, balancing criteria are not ranked in terms of relative importance; any one of the balancing criteria may prove to be the most important based on site conditions. This section focuses on comparing SRWP and AMRSRP with reference to these balancing criteria.

---

<sup>2</sup> Two processes occur with groundwater flow—an advective and a diffusive process. This estimate was performed assuming there are no advective forces producing groundwater flow upward through the remaining semi-consolidated material. In other words, a combination of engineering controls, including the onshore vertical sheet pile barrier wall will prevent advective groundwater flow through this area. See Attachment 3.

### Long-Term Reliability and Effectiveness

The approach presented in the SRWP includes removing sediment and semi-consolidated materials with arsenic concentrations greater than or equal to 50 mg/kg. Removing the semi-consolidated materials will result in a substantial, uncontrollable release of arsenic into the Menominee River that is expected to exceed acute toxicity WQC and threaten ecological receptors, including fish that inhabit or move through the Turning Basin and the shallower area to the east. In addition, removing the semi-consolidated materials adjacent to the VBW likely will result in structural failure of the wall.

Although semi-consolidated material containing arsenic concentrations greater than or equal to 50 mg/kg will remain in place following implementation of the AMRSRP approach, these materials will not be disturbed further. Instead, these contaminated materials will be capped, reducing the release of arsenic and resulting risks to the environment. Assuming upward groundwater gradients that may exist in the river are properly controlled as part of the AMRSRP (if required), it is estimated that the time required for arsenic mass remaining in the upper 4 feet of the semi-consolidated material to diffuse through the cap into the river will be between 960 and 120,000 years (Attachment 3). This equates to an average release of approximately 42 pounds per year of arsenic into the environment over the course of 960 years, assuming the most conservative (rapid) diffusion. This rate of release of arsenic will not cause an exceedance of the WQC in the Menominee River.

As a point of comparison, successful implementation of the AOC's MNR component could release as much as 700 pounds of arsenic per year.

**Therefore, implementation of the approach presented in the AMRSRP is more effective in the long term than the approach presented in the SRWP.**

### Reduction of Toxicity, Mobility, and Waste Volume

The corrective measure approach presented in the SRWP includes removing soft sediment and semi-consolidated materials with arsenic concentrations greater than or equal to 50 mg/kg. The material removed and landfilled during the SRWP will have reduced toxicity and mobility. Approximately 380,000 tons of waste material will be generated by the SRWP approach for land disposal.

The approach presented in the AMRSRP will reduce the mobility of dissolved arsenic in the semi-consolidated materials because the groundwater recharge through these materials will be eliminated either through engineering controls already applied onshore (VBW and groundwater extraction) or through additional measures if hydraulic data indicate this is required. By eliminating this gradient and capping the semi-consolidated material, the only transport mechanism potentially affecting arsenic mobility is diffusion. As discussed above, diffusion is a slow process. The AMRSRP approach eliminates the release of arsenic that would occur during the dredging of semi-consolidated materials and precludes generation of an estimated 270,000 tons of waste material. Lastly, the mobility of arsenic in the semi-consolidated material that remains following implementation of the AMRSRP is low. As previously stated, it is estimated to take between 960 and 120,000 years for arsenic mass contained in the upper 4 feet of the remaining material to diffuse to the river (Attachment 3).

Since the AMRSRP cap will eliminate exposure of ecological receptors to media that exceed 50 mg/kg arsenic, potential impacts from arsenic in Menominee River sediment will be reduced significantly. From a risk perspective, placement of the clean cap over the semi-consolidated material prevents exposure of ecological receptors to the remaining arsenic and, therefore, is equivalent to a reduction in toxicity.

### **Short-Term Effectiveness**

Arsenic released during dredging of the semi-consolidated material in the SRWP approach is likely to exceed Wisconsin's acute toxicity WQC for arsenic even if as little as 1 percent of the arsenic in these materials is released. As discussed above, it is likely that substantially more than 1 percent of the mass of arsenic in the semi-consolidated materials may be released during dredging of the semi-consolidated material.

Implementation of the SRWP approach uses engineering controls to protect site workers and the community during the estimated 10 months of construction. The SRWP approach will generate an estimated 380,000 tons of waste materials that will require treatment and offsite disposal and increases the risks associated with offsite transportation (an estimated 19,000 roundtrips by trucks between the Tyco facility and the offsite landfill). As described previously, the SRWP approach will result in a release of arsenic to the environment that likely will exceed acute toxicity WQC, which presents a short-term risk.

Implementation of the AMRSRP approach also uses engineering controls to protect site worker and the community during the estimated 4 months of construction. This approach will generate an estimated 108,000 tons of waste materials (an estimated 5,400 roundtrips by trucks between the Tyco facility and the offsite landfill) that require treatment and offsite disposal and eliminates the release of arsenic from the semi-consolidated materials into the environment during remediation.

Thus, implementation of the AMRSRP provides for better short-term effectiveness than the SRWP approach through a significant reduction in the construction duration, an increase in protection to the community (decrease in traffic-related risk because of decrease in waste generation), and a reduction in environmental impacts (that is, arsenic released into the Menominee River) related to dredging activities.

### **Implementability**

The remedial approach specified in Section VI, 11, paragraph d of the AOC and detailed in the SRWP is not implementable because removing the semi-consolidated material adjacent to the VBW likely will result in failure of the wall. Conversely, the AMRSRP approach of a mixed dredging and capping remedy is implementable. The use of capping to control source material has been approved at more than 30 other river remediation sites across the United States since 1990 (Attachment 4). Mixed remedies are routinely being approved and implemented recently as a more cost-effective alternative to a dredging-only remedies both in USEPA Region 5 (for example, Lower Fox River in Wisconsin) and other areas of the United States.

As described under "Short-Term Effectiveness" above, implementing the AMRSRP approach uses engineering controls to protect site workers and the community during the estimated 4

months of construction. Because a 3-foot-thick cap is proposed under the AMRSRP approach, it also is necessary to address navigation channel depth in the river as part of the AMRSRP. Figures 1 through 4 show depth below low water datum (LWD) of the current top of soft sediment (Figure 1), depth below LWD of the top of semi-consolidated materials (Figure 2), depth below LWD of the top of a 1-foot-thick cap placed after soft sediment removal (Figure 3), and depth below LWD of a 3-foot-thick cap placed after soft sediment removal (Figure 4). As indicated on the figures, the placement of a 3-foot-thick cap in the Turning Basin will result in final water depths in the Federal Channel portion of the Turning Basin ranging between 4 and 25 feet below LWD. It should be noted that under the AMRSRP, the majority of the central portion of the Turning Basin will be greater than 20 feet deep.

Tyco has initiated discussions with USACE and navigation channel users to determine the impacts of remediation plans, under either the SRWP or the ASRWP, on commercial navigation. USACE has stated that the channel depths that would remain if the AMRSRP were implemented will require consultation with channel users. Ultimately, either the SRWP or AMRSRP will be subject to USACE's permitting authority.

### Cost

The estimated cost to implement the AMRSRP approach is approximately one-half the cost for implementing the SRWP approach and provides for greater overall protection of the environment. The cost of implementing the SRWP approach is estimated to range from \$23.7 million to \$50.8 million, while the cost to implement the AMRSRP approach is estimated to range from \$11.7 million to \$25.1 million. For both the SRWP and AMRSRP approaches, these cost estimates were prepared in accordance with USEPA guidance and at this stage of conceptual design have an uncertainty range of -30/+50 percent. Under USEPA guidance, cost estimates at this stage are developed primarily for comparing the approaches and not for establishing project budgets.

### Community and State Acceptance

These criteria typically are evaluated formally following the public comment period, although they can be factored into identifying a preferred approach. From the perspective of source control, implementation of either the SRWP or AMRSRP is expected to be viewed positively from the community. However, the SRWP approach of dredging the semi-consolidated material likely will encounter opposition because of the potential acute WQC toxicity impacts to the Menominee River's walleye and other fisheries from arsenic releases.

## Conclusions

Based on an evaluation of site conditions, and the information presented herein, Tyco strongly recommends that the approach presented in the AMRSRP be implemented. The following support this opinion:

- Approximately 5,000 yd<sup>3</sup> of contaminated semi-consolidated material with arsenic concentrations significantly greater than 50 mg/kg cannot be removed because this material provides structural support for the existing sheet pile barrier wall. The AMRSRP proposes to cap these areas to reduce released arsenic and protect the structural integrity of the sheet pile wall.

- Capping and in-place containment of the semi-consolidated material as described in the AMRSRP is more environmentally protective in both the short and long term than dredging of these materials as described in the SRWP. Dredging the semi-consolidated material as proposed in the SRWP will release arsenic at levels likely to expose ecological receptors in the Menominee River adjacent to and downstream of the dredging areas to unacceptable levels of arsenic. The AMRSRP capping of the semi-consolidated materials eliminates the uncontrollable release of arsenic associated with semi-consolidated materials dredging.
- The SRWP scope is estimated to cost between \$23.7 million and \$50.8 million versus \$11.7 million and \$25.1 million for the AMRSRP.

In conclusion, a greater level of environmental protectiveness can be achieved for approximately one-half the cost by implementing the alternative plan. This is the essence of USEPA's contaminated sediment management principles and the specific objective of Section 11, paragraph f of the AOC; that is, to select and implement protective, scientifically sound, and cost-effective remedies (USEPA OSWER Directive 9285.6-08).

Please contact me at 414-847-0386 or John Perkins at 561-912-6197 if you have any questions or require additional information about the concepts included in this document.

Very truly yours,

CH2M HILL



Jeffrey Danko  
Project Manager

Enclosure

cc: Kristin DuFresne, WDNR  
Maritsa Goan, Tyco Fire Products, LP  
John Perkins, Tyco Safety Products  
Doug Clark, Foley & Lardner  
Weldon Bosworth, Ph.D., URS Corporation  
Brenda Allen-Johnson, Foley & Lardner

Enclosures: Figures 1 through 4  
Attachments 1 through 4

## References

- EarthTech. 2007. *Addendum 01 to the Corrective Measures Study, Manufacturing and Wetlands Area, Tyco Safety Products – Ansul, Stanton Street Facility, Marinette, WI*. August.
- National Research Council (NRC). 2007. *Sediment Dredging at Superfund Megsites: Assessing the Effectiveness (DRAFT)*. ISBN:0-309-10974-4.
- URS Corporation (URS). 2003a. *Corrective Measures Study, Manufacturing and Wetlands Area, Tyco Safety Products-Ansul, Stanton Street Facility, Marinette, WI*. May.
- URS Corporation (URS). 2003b. *Baseline Risk Assessment, Tyco Suppression Systems – Ansul Stanton Street Site, Marinette Wisconsin*. February 28.
- URS Corporation (URS). 2003c. *Menominee River Sediment Remedial Alternatives Evaluation, Tyco Safety Products – Ansul Stanton Street Facility*. EPA #WID 006 125 215. November 24.
- U.S. Army Corps of Engineers (USACE). 2010.  
<http://el.erdc.usace.army.mil/resbrief/drbucket/drbucket.html>
- U.S. Environmental Protection Agency (USEPA). 2000. *Fact Sheet #3 – Final Remedy Selection for Results-Based RCRA Corrective Action*. March.
- U.S. Environmental Protection Agency (USEPA). 2003. *Final Guidance on Completion of Corrective Action Activities at RCRA Facilities*. *Federal Register*, Volume 68, No. 37. February 25.
- USEPA Office of Solid Waste and Emergency Response (OSWER). 2002. *Directive 9285.6-08, Principles for Managing Contaminated Sediment Risks at Hazardous Waste Sites*. February 12.
- USEPA Office of Solid Waste and Emergency Response (OSWER). 2005. *Directive 9355.0-85, Contaminated Sediments Remediation Guidance for Hazardous Waste Sites*. December.
- USEPA Office of Solid Waste and Emergency Response (OSWER). 2008. *Directive 9200.1-90, Response to Regional Request Regarding Sediment Cleanup at May 2008 Superfund Division Directors Meeting*. July 3.

## Figures

---





Figure 1  
Depth to Top of Soft Sediment  
Tyco Fire Products LP Facility  
Marinette, WI







Figure 2  
 Depth to Top of Semi-consolidated Sands and Silts  
 2010 Investigation Area  
 Tyco Fire Products LP Facility  
 Marinette, WI







Figure 3  
Depth to Top of 1-Foot Cap Over  
Semi-consolidated Sands and Silts  
2010 Investigation Area  
Tyco Fire Products LP Facility  
Marinette, WI







Figure 4  
Depth to Top of 3-Foot Cap Over  
Semi-consolidated Sands and Silts  
2010 Investigation Area  
Tyco Fire Products LP Facility  
Marinette, WI



**Attachment 1**  
**Alternate Technologies Evaluation**

---

# Alternate Technologies Evaluation

---

Additional discussion is provided herein to address miscellaneous issues that have arisen regarding technologies not identified within the AOC or the Statement of Basis.

## Clamshell Bucket Types

A conventional clamshell bucket, as opposed to an environmental bucket, must be used during dredging of the semi-consolidated sands and soils because of their physical properties (20-50 blows per foot). This decision is based on information and experience from/at the following projects:

- Kinnickinnic River Great Lakes Legacy Act Sediment Removal Project in Milwaukee, Wisconsin for U.S. EPA Great Lakes National Program Office (the standard operating procedure was to switch from an environmental bucket to a conventional bucket when sand was encountered rather than soft sediment.)
- Contaminated river sediment removal project for a confidential CH2M HILL client in Australia. Excerpt from the dredge contractor's Dredge Plan:
  - *"The clamshell bucket will not be able to remove dense sands or debris at all, therefore if this material is encountered when the clamshell is in use the dredge will have to stop work and change over to an open bucket."* (The "clamshell bucket" referred to in the dredge plan was a piston-operated environmental bucket.)

## Hydraulic Dredging

Hydraulic dredging of contaminated materials involves removing sediment and soil by recovering them, along with a significant volume of water (carriage water) through a pipeline, dewatering and stabilizing the dredged materials, and disposing of the materials. A cutterhead is typically used to breakup consolidated materials. The carriage water generated during hydraulic dredging is typically between 5 and 12 percent solids, meaning a significant volume of water would be generated during the process and must be treated. For a project of this scale, a likely water volume flow rate is around 1,500 gallons per minute (gpm), requiring dewatering infrastructure and a water treatment facility with equivalent capacity. For comparison, the mechanical dredging processes currently described in the SRWP and AMRSRP require water treatment facilities to handle less than 150 gpm. Estimated costs for water treatment are included in Table A1-1, including mechanical dredging and hydraulic dredging. Supporting data for the estimated costs in Table A1-1 for mechanical dredging will be included in the respective work plans. The water treatment costs for hydraulic dredging costs were estimated by scaling up the costs of water treatment for the SRWP to the 1,500-gpm value.

TABLE A-1

Estimated Remediation Water Treatment Costs with Two Dredging Technologies

*Tyco Fire Products LP, Marinette, Wisconsin*

	<b>Mechanical Dredging</b>	<b>Hydraulic Dredging</b>
SRWP	\$ 6.6 million	\$ 97 million*
AMRSRP	\$ 5.3 million	\$ 39 million*

\*Includes geotextile tube dewatering and water treatment.

Hydraulic dredging would only be effective for removing semi-consolidated sands and silts if a cutterhead was used. Using such a cutterhead could cause an increase in arsenic release to the river beyond what would be generated using a conventional clamshell bucket, as currently described in the SRWP. Therefore, the arsenic release could be just as significant for hydraulic dredging as mechanical dredging. Hydraulic dredging with plain suction instead of a cutterhead would potentially be effective in limiting release of solids during dredging, but this technology could not be used in the denser semi-consolidated sand and silt material.

Hydraulic dredging was rejected in the AOC's Statement of Basis because of the high cost of treatment of generated wastewater as well as the potential release of arsenic during use of the cutterhead.

## Additional Excavation Technologies

Consideration was given to other technologies that could be employed to limit the release of dissolved arsenic to the river during dredging operations. Two such technologies considered were dry excavation using sheet pile cofferdams and excavation using much smaller sheet pile cells.

### Dry Excavation

Dry excavation has been used at numerous sites to remove contaminated materials from bodies of water. Temporary cofferdams, or cells, are created around the contaminated materials, usually with sheet piling, but in shallow water other products such as water-inflated plastic barriers (such as Aqua-Barriers) can be used. The cell is then dewatered, and the material is excavated using conventional equipment (excavators and articulated hauling trucks). Stabilization of the material can be done either in situ before excavation is performed or on a staging area outside of the dewatered cell.

Because of the significant excavation depths required to remove the semi-consolidated sands and silts for the SRWP, sheet piling would need to be used as the barrier to form cells if dry excavation were to be used in the Turning Basin area of the Menominee River. However, there is not sufficient thickness of semi-consolidated materials and glacial till above bedrock in the Main Channel north of the Turning Basin to support a sheet pile wall (sheet piling driven to form the northern wall of the cell would meet refusal on bedrock only a few feet into the till). Therefore, dry excavation using cofferdams is not a feasible technology for removal of Menominee River sediments.

## Small Sheet Pile Cells

Another potential technology that could be used to remove contaminated sediment and semi-consolidated materials are small sheet pile cells. This process would involve installation of sheet piling to form a relatively small enclosed cell (perhaps 30 feet wide by 30 feet long). The material within the cell is dredged mechanically down to the target elevation, and the water in the cell is pumped out and treated by a temporary water treatment system. The treated water is returned to the cell so that no differential hydraulic pressure is created against the sheet piling. Therefore, a shallow embedment depth would not be problematic for the sheet piling.

It is likely that the water within the cell will need to be treated between three and five times to lower the arsenic to acceptable levels before releasing it to the river. Once this is done, the sheet piling can be extracted and reinstalled at another location to continue the dredging process. The process would probably proceed with three cells being used simultaneously—one being installed, one being dredged, and the last one undergoing treatment of the water after dredging has been completed.

While dredging using small sheet pile cells is technical feasible, and practically no arsenic would be released if they were used, this technology was eliminated from consideration due to the significant cost. The surface area of the dredge area in the river (not including the South Channel) is estimated to be 630,000 square feet (sf). Using cells that are 900 sf, this means that cell removal and installation will need to be done 700 times. If, on average, one of the four sides is common with a previous cell and doesn't need to be installed, this still leaves  $700 \times 3 \times 30 \text{ ft} = 63,000$  linear feet of sheet piling installation and removal in total. Assuming a cost of \$500 per linear foot to install and remove one linear foot of sheet piling, this is \$31,000,000 for sheet piling work alone.

Average water depth is estimated to be 18 ft in the dredge area. Total water volume is  $18 \text{ ft} \times 630,000 \text{ sf} = 11$  million cubic feet, or 85 million gallons. If treatment of three volumes of water is necessary before a cell can be removed, this equates to 260 million gallons of water that must be treated. Treatment of 260 million gallons is going to cost on the order of \$55 million. With the combined cost of sheet piling installation and water treatment being \$86 million, the entire project cost will exceed \$100 million.

In addition to the excessive cost to implement the technology, use of small sheet pile cells will preclude the use of the Turning Basin by maneuvering vessels while the dredging activities are taking place. Therefore, small sheet pile cells were eliminated from further consideration.

**Attachment 2**  
**Estimate of Percentage of Total Arsenic Released**  
**during Dredging to Exceed Acute Toxicity**  
**Standard**

---

# Estimate of Percentage of Total Arsenic Released during Dredging to Exceed Acute Toxicity Standard

---

## Introduction

An Administrative Order on Consent (AOC) has been signed between Tyco Fire Products LP (Tyco) and the U.S. Environmental Protection Agency (USEPA), dated February 26, 2009, that requires the mechanical dredging of sediments from the Menominee River adjacent to the north boundary of the Tyco facility in Marinette, Wisconsin. Material must be removed that has concentrations equal to or greater than 50 milligrams per kilogram (mg/kg) total arsenic. Mechanical dredging of soft sediments can be performed using an environmental bucket, but mechanical dredging of semi-consolidated sands and silts (“semi-consolidated materials”) will require the use of a conventional clamshell bucket because of the material’s physical properties (Standard Penetration Test “N” value of 20 to 50 blows per foot). The use of a conventional clamshell bucket will release a higher amount of solids (and therefore arsenic) into the water column during mechanical dredging than an environmental bucket will release.

Arsenic concentrations in the surface water during dredging activities cannot be calculated with any accuracy without performing a field pilot study due to the myriad of assumptions that must be made and parameters that need to be estimated. The objective of this memorandum is to estimate what percentage of the total mass of arsenic in contaminated sediments has to be released into the water column during mechanical dredging to cause an exceedance of Wisconsin’s acute toxicity water quality criterion (WQC) for arsenic in surface water (340 micrograms per liter [ $\mu\text{g}/\text{L}$ ] [Wisconsin Administrative Code NR105]). Once the percentage of total arsenic is estimated, a semi-quantitative evaluation can be done to determine if a release of that amount of arsenic is likely during mechanical dredging activities.

## Methodology

Samples collected of soft sediment and semi-consolidated materials were analyzed for total arsenic without separating the liquid fraction of the sample from the solids. Therefore, analytical results for total arsenic from these samples includes both dissolved arsenic in the porewater as well as arsenic adhered to solid particles, and can be used to estimate total arsenic present in the soft sediment and in the semi-consolidated materials. The estimation method is summarized below with the full calculation included as Table A2-1.

## Step 1 – Determine areas with high concentrations of arsenic in semi-consolidated sands and silts.

Three-dimensional visualization software (Environmental Visualization System -EVS) was used to create a model of the arsenic concentrations using analytical data from samples collected during 2010 in the river. The highest arsenic concentrations were detected in the Turning Basin. Screening values of 1,000 mg/kg and 2,000 mg/kg were used to isolate areas within the Turning Basin with high concentrations of arsenic that were of a sizeable quantity and would take at least several days to excavate. The screening level of 1,000 mg/kg was selected: 5,353 cubic yards (yd<sup>3</sup>) of soft sediment and 5,521 yd<sup>3</sup> of semi-consolidated materials were present in the Turning Basin with at least 1,000 mg/kg total arsenic. Figures A2-1 and A2-2 show the locations of these materials. The average arsenic concentration for the soft sediment was 2,900 mg/kg and for the semi-consolidated sands and silts was 1,694 mg/kg.

## Step 2 – Determine the total mass of arsenic in materials that can be dredged in one day

The estimated dredging production rate is 1,300 yd<sup>3</sup> per day for soft sediment and 1,000 yd<sup>3</sup> per day for semi-consolidated materials. Estimated in situ dry density is 70 pounds per cubic foot (pcf) for soft sediment and 100 pcf for semi-consolidated materials. Average concentrations listed in step 1 are used (note that mg/kg is the same as pounds per million pounds).

For soft sediment:

$$1,300 \text{ yd}^3/\text{day} \times (2,900 \text{ lbs arsenic}/1,000,000 \text{ lbs}) \times 70 \text{ lbs}/\text{ft}^3 \times 27 \text{ ft}^3/\text{yd}^3 \\ = 7,125 \text{ lbs of arsenic in the soft sediment dredged in one day}$$

For semi-consolidated materials:

$$1,000 \text{ yd}^3/\text{day} \times (1,694 \text{ lbs. arsenic}/1,000,000 \text{ lbs}) \times 100 \text{ lbs}/\text{ft}^3 \times 27 \text{ ft}^3/\text{yd}^3 \\ = 4,574 \text{ lbs. of arsenic in the semi-consolidated materials dredged in one day}$$

## Step 3 – Determine the volume of water flowing through the path of the bucket in one day

The average flow rate of the river was estimated to be 3,500 cubic feet per second based on the 25 year average flow (URS 2003). The cross sectional area of the river was determined to be 12,000 square feet (sf) for the soft sediment, using an estimated dredge depth of 15 feet and a width of 800 feet near the dredging area. For the semi-consolidated materials, the average dredge depth was estimated to be 20 feet, and the width was estimated to be 800 feet, so the cross sectional area was determined to be 16,000 sf. Average stream velocities were 0.292 and 0.219 feet per second for the soft sediment and semi-consolidated materials dredging, respectively. Estimate bucket widths for the soft sediment (environmental bucket) and semi-consolidated materials (conventional clamshell) were 8 and 5 feet, respectively. The volume of water flowing through the path of the environmental bucket travel for the soft sediment dredging was calculated as follows:

$$\text{Quantity of water per day} = \text{Stream velocity} \times \text{cross sectional area of bucket travel}$$

$$= 0.292 \text{ ft/sec} \times 15 \text{ ft} \times 8 \text{ ft}$$

$$= 35.0 \text{ ft}^3/\text{sec}$$

$$= 22,650,000 \text{ gallons/day}$$

$$= 188,900,000 \text{ lbs./day}$$

For semi-consolidated materials, the quantity of water per day is calculated as follows:

Quantity of water per day = Stream velocity X cross sectional area of bucket travel

$$= 0.219 \text{ ft/sec} \times 20 \text{ ft} \times 5 \text{ ft}$$

$$= 21.9 \text{ ft}^3/\text{sec}$$

$$= 14,160,000 \text{ gallons/day}$$

$$= 118,100,000 \text{ lbs/day}$$

**Step 4 – Determine the hypothetical concentration of arsenic in the surface water if all arsenic in the dredged material was released.**

For soft sediment:

$$[\text{As}] \text{ in river} = 7,125 \text{ lbs. As} / 188,900,000 \text{ lbs. river water} = 37,760 \text{ } \mu\text{g/L}$$

For semi-consolidated materials:

$$[\text{As}] \text{ in river} = 4,574 \text{ lbs. As} / 118,100,000 \text{ lbs. river water} = 38,787 \text{ } \mu\text{g/L}$$

**Step 5 – Determine what percentage of the total mass in the sediment would need to be released to equal the WDNR acute toxicity standard of 340  $\mu\text{g/L}$**

For soft sediment:


$$\% \text{ of total mass} = (340 \text{ } \mu\text{g/L}) / (37,760 \text{ } \mu\text{g/L}) = 0.900\%$$

For semi-consolidated materials:


$$\% \text{ of total mass} = (340 \text{ } \mu\text{g/L}) / (38,787 \text{ } \mu\text{g/L}) = 0.877\%$$

## Reference

URS Corporation (URS). 2003. *Baseline Risk Assessment, Tyco Suppression Systems – Ansul Stanton Street Site, Marinette Wisconsin*. February 28.



**Figure A2-1.** Location of soft sediment in the Turning Basin with arsenic contamination greater than 1,000 mg/kg.



**Figure A2-2.** Location of Semi-consolidated Sands and Silts in the Turning Basin with arsenic contamination greater than 1,000 mg/kg.

**Table A2-1  
Dissolved Arsenic Released Calculations  
Sediment Removal Work Plan**

Sub-Area	Lithology	Screened Value (ppm)	Volume (CY)	Total Arsenic Mass (pounds)	Total Soil Mass (pounds)	Average Arsenic Conc. (ppm)	Notes
Turning Basin	Soft Sediment	1000.00	5,353.10	48,411.00	10,117,239.59	2,900.20	Most conc. vol. of soft sediments as calc. by EVS
Turning Basin	SC Sands and Silts	1000.00	5,520.60	29,165.00	14,906,052.47	1,694.20	Most conc. vol. of SC sands & silts as calc. by EVS

**For Soft Sediments, assume 1,300 CY can be dredged in average day:**

1,300 CY dredged from turning basin  
 2,900 mg/kg average arsenic concentration  
 70 lbs./ft<sup>3</sup> in situ dry density  
 7,125 lbs. arsenic released through water column in one day if all arsenic is released

Average flow rate of the river, cfs	3,500	(Based on 25 yr average flow, URS Risk Evaluation Report, February 2003)
Minimum flow rate of the river, cfs	538	(Based on records, Oct 6 1946, URS Risk Evaluation Report, February 2003)
Cross sectional area of the river	12000	Estimated dredge depth = 15 ft and width = 800 ft near the dredging area
Average stream velocity, ft/sec	0.29	
Minimum stream velocity, ft/sec	0.04	
X-sec. area of vertical path of bucket travel, ft <sup>2</sup>	120	Estimated dredge depth = 15 ft and environmental bucket width of 8 ft

	Ave. Flowrate	Min. Flowrate
water flowing through x-sectional area of vertical path of bucket travel in one day, ft <sup>3</sup>	3,024,000	464,832
water flowing through x-sectional area of vertical path of bucket travel in one day, lbs.	188,697,600	29,005,517
concentration of arsenic downstream of dredging assuming all released, µg/l	37,760	245,653

The Wisconsin Department of Natural Resources' ambient water quality standards for arsenic are 340 µg/L for acute toxicity and 148 µg/L for chronic toxicity.

Percentage of total arsenic in sediment that can be released to equal standard for acute toxicity	0.900%	0.138%
Percentage of total arsenic in sediment that can be released to equal standard for chronic toxicity	0.392%	0.060%

**For semi-consolidated sands and silts, assume 1,000 CY can be dredged in average day:**

1,000 CY dredged from turning basin  
 1,694 mg/kg average arsenic concentration  
 100 lbs./ft<sup>3</sup> in situ dry density  
 4,574 lbs. arsenic released through water column in one day if all arsenic is released

Average flow rate of the river, cfs	3,500	(Based on 25 yr average flow, URS Risk Evaluation Report, February 2003)
Minimum flow rate of the river, cfs	538	(Based on records, Oct 6 1946, URS Risk Evaluation Report, February 2003)
Cross sectional area of the river	16000	Estimated dredge depth = 20 ft and width = 800 ft near the dredging area
Average stream velocity, ft/sec	0.22	
Minimum stream velocity, ft/sec	0.03	
X-sec. area of vertical path of bucket travel, ft <sup>2</sup>	100	Estimated dredge depth = 20 ft and clamshell bucket width of 5ft

	Ave. Flowrate	Min. Flowrate
water flowing through x-sectional area of vertical path of bucket travel in one day, ft <sup>3</sup>	1,890,000	290,520
water flowing through x-sectional area of vertical path of bucket travel in one day, lbs.	117,936,000	18,128,448
concentration of arsenic downstream of dredging assuming all released, µg/l	38,787	252,329

The Wisconsin Department of Natural Resources' ambient water quality standards for arsenic are 340 µg/L for acute toxicity and 148 µg/L for chronic toxicity.

Percentage of total arsenic in sediment that can be released to equal standard for acute toxicity	0.877%	0.135%
Percentage of total arsenic in sediment that can be released to equal standard for chronic toxicity	0.382%	0.059%

**Attachment 3**  
**Arsenic Diffusion Calculation**

---

# Arsenic Diffusion Calculation

---

A calculation was performed to estimate a range of potential time periods over which it would take diffusive transport mechanisms to deplete the mass of arsenic that will remain in the semi-consolidated sands and silts unit once the overlying soft sediments are removed as described in the Alternative Menominee River Sediment Removal Work Plan (AMRSRP). The calculation spreadsheet is included as Table A3-1.

Transport of arsenic from the remaining semi-consolidated material will occur through both advective and diffusive flow. Advective flow is the major contributor to transport of dissolved solutes, as it is driven by the movement of subsurface water under a hydraulic gradient. Generally, the diffusive contribution to transport is relatively small, as it is driven only by the concentration gradient and subject to the influence of other geochemical factors as mentioned below. However, groundwater modeling performed for the site has indicated that the hydraulic gradients driving the advective flux of arsenic to the river will be mitigated (and possibly reversed) as a result of implementation of the upland remedy, which involves the placement of a vertical hydraulic barrier wall (VBW) down to the top of the bedrock, and the operation of groundwater extraction wells for flood control within the VBW alignment. Given the results of the modeling, this exercise focuses on estimating the diffusive transport of arsenic and assumes that the advective component of flux is non-existent.

In the case of arsenic, the dissolution from sediments and the subsequent diffusive flux are also affected by a number of other factors, including the organic carbon content, pH and redox conditions, the availability of adsorption sites, and the presence of other competing ions. Once in the dissolved phase, arsenic species, including the relatively mobile dimethylarsonic acid (DMA) which is present at the site, will likely be subjected to additional attenuation through sorption processes that will retard the rate at which they may be transported through the pore space. Quantification of these factors requires a myriad of assumptions or detailed site-specific studies, and the formulation of geochemical transport models. However, the objective of this exercise was to provide a rough order-of-magnitude range of hypothetical times that it might take for remaining sediment sources to be depleted. A conservative approach was used to meet this objective that concentrated on physical transport properties and the reported soil-water partition coefficient range for arsenic (a more generalized chemical attenuation factor).

The diffusive flux of total arsenic (all observed species including arsenate, arsenite, monomethylarsonic acid [MMA] and DMA) was estimated for three separate scenarios. Parameter assumptions were varied between the ranges reported in literature to estimate low, medium, and high mobility scenarios. The calculations and assumed parameter values are included on Table A3-1. The total mass of arsenic in the top four feet of the semi-consolidated material (40,290 lbs) and a volume of 78,000 cubic yards was used to back-calculate an average sediment concentration of 157 mg/kg. Using this concentration along

with a range of partition coefficients ( $K_{ds}$ ) available in EPA Guidance<sup>1</sup> and other available literature<sup>2</sup>, pore water concentrations for the top four feet of the semi-consolidated materials were estimated to be between 5.4 and 8.7 mg/L.

Using the dissolved concentrations of arsenic measured in the river water samples during the 2010 investigation and a range of diffusion coefficients, assumed porosities, and tortuosity factors presented in the available literature for sandy freshwater sediments, diffusion rates of  $1.8 \times 10^{-3}$ ,  $5.9 \times 10^{-2}$ , and  $6.9 \times 10^{-1}$  lbs of arsenic per day were calculated for the low, medium and high mobility scenarios, respectively. Conservatively assuming that the calculated diffusion rates would be constant over time it was estimated that the time it would take to remove only the mass of arsenic in the top 4 feet of the semi-consolidated materials (40% of all semi-consolidated arsenic) could range between 960 and 120,000 years with an estimate of 5,000 years for the medium mobility scenario. (Because of the combination of all the ultra conservative assumptions used for the high mobility number, the medium mobility scenario diffusion time probably represents a more realistic estimate). The calculations and assumptions used to develop these rough order-of-magnitude estimates are provided in Table A3-1.

---

<sup>1</sup> US EPA, 2001. Supplemental Guidance for Developing Soil Screening Levels for Superfund Sites, OSWER 9355.4-24. March.

<sup>2</sup> US EPA, 2006. Reregistration Eligibility Decision for MSMA, DSMA, CAMA, and Cacodylic Acid EPA 738-R-06-021. July; Sanchez et. al, 2003 *Environmental Assessment of Waste Matrices contaminated with arsenic in The Journal of Hazardous Materials* B96 2003 (pp 229-257; C.W. Fetter, Contaminant Hydrogeology 2nd edition, 1999.

**Table A3-1**  
 Partitioning (sediment to pore water)  
 Tyco Fire Products LP

Need to assume linear isotherm given complexity of system and contaminant (Kd - Partitioning Coefficient)

$$Kd = C_s / C_{pw}$$

when: Sediment Conc.(Cs) :	157 mg/kg	Back-calculated average concentration for top 4 feet of subsoils given calculated mass of As in interval	
			<b>Source of Assumed Kd</b>
and: Assumed Kd =	29 L/kg	then: Pore water Conc (C <sub>pw</sub> ) =	5.41 mg/L EPA Soil Screening Guidance (EPA, 2001) (at pH of 6.8)
Assumed Kd =	18 L/kg	then: Pore water Conc (C <sub>pw</sub> ) =	8.72 mg/L Mean of Kd for DMA reported in EPA (Aug. 10, 2006 document)

**Diffusion (Adaptation of Fick's Law - 1st Order [Berner 1980])**

Fick's Law Berner (1980) - for porous media

$$J_j = -D_j \frac{\partial c_j}{\partial x}$$

$$J_s = -\phi \cdot D_s \cdot \frac{\partial C}{\partial x}$$

Assumption Scenarios				
	Low	Medium	High	
Where:	Mobility	Mobility	Mobility	
$\phi$	0.5	0.6	0.7	relative pore water volume in sediments assumed sands and gravel (unitless)
$D_s$	5.45E-11	6.87E-10	1.85E-09	effective diffusion (m <sup>2</sup> /s) ( $D_i/\theta^2$ ) (Berner, 1980)
$D_j$	1.13E-10	1.06E-09	2E-09	molecular diffusion in water (m <sup>2</sup> /s) (Diffusion Coefficient) <sup>1</sup>
$\theta$	1.44	1.24	1.04	tortuosity <sup>2</sup> (unitless)
$C_{pw}$	5414	7068	8722	conc at position 1 (mg/m <sup>3</sup> ) (pore water) (see above for high and low, medium is avg. of high and low)
$C_{sw}$	5.6	3.8	1.9	conc at position 2 (ug/L or mg/m <sup>3</sup> ) (surface water) (high and low from river water dissolved As concentration analysis performed for elutriate sampling event)
$x$	1.52439	1.219512	0.9146341	Distance between position 1 and position 2 (m) (low =depth from surf water to middle of top 4 feet of subsoil + 3.0 ft. cap, high = thickness of proposed cap med = average of low and high values)
$\partial C_j / \partial x$	3548	5793	9534	Concentration Gradient (mg/m <sup>3</sup> /m)
$J$	-9.7E-08	-2.4E-06	-1.2E-05	Diffusive Flux (mg/m <sup>2</sup> -s)
$A$	4.89E+04	4.89E+04	4.89E+04	Surface area over which flux is occurring (m <sup>2</sup> ) or 526255 ft <sup>2</sup>
Total Flux Rate:	-0.00473	-0.11676	-0.603355	mg/s
	-0.0009	-0.02224	-0.114927	lbs/day

**Results**




Total Mass in All Subsoils	98818	98818	98818	lbs
Total mass of As in top 4 feet of subsoils =	40290	40290	40290	lbs
No. of years of linear diffusive flux required to remove mass currently present in top 4 feet =	122,617	4,963	960	years
No. of years of linear diffusive flux required to remove total mass in all subsoils =	300,740	12,173	2,356	years

Very conservatively assumes top 4 feet of sediments are replenished w/arsenic from below at a rate equal to their diffusive flux to the surface water.

Notes:  
 1. Low end estimate taken from Sanchez et. al, 2003 (Environmental Assessment of Waste Matrices contaminated with arsenic in The Journal of Hazardous Materials B96 2003 (pp 229-257). High-End estimate based on the values for similar anions sulfate and bicarbonate (1.07x10<sup>-9</sup>m<sup>2</sup>/sec and 1.18x10<sup>-9</sup>m<sup>2</sup>/sec, respectively)--from C.W. Fetter, Contaminant Hydrogeology 2nd edition,1999. Arsenic is expected to be in a similar anionic form as these ions.  
 2. Tortuosity if the ratio of the distance an ion or molecule travels around particles and the direct path towards the lower concentration) [Swerts (1991) experimentally determined values for freshwater sed of a variety of porosities. Values reported for sandy freshwater sediments in Swerts (1991) were used here as an estimate for toruosity.

**Table A3-1**  
 Estimate of Concentration of Dissolved Arsenic in River Water from Diffusion  
 Tyco Fire Products LP

Total mass of arsenic in top 4' of semi-consolidated materials	40,290	lbs.
Minimum years of linear diff. flux required to remove mass currently present in top 4 feet	960	years
Mass of arsenic released per year, average	41.9	lbs/yr
Mass of arsenic released per day, average	0.115	lbs/day
Average flow rate of the river, cfs	3,500	(Based on 25 yr average flow, URS Risk Evaluation Report, February 2003)
Cross sectional area of the river, ft <sup>2</sup>	12000	Estimated depth = 15 ft and width = 800 ft near the dredging area
Average stream velocity, ft/sec	0.29	
Width of area >50 ppm, ft	500.00	See sketch below
Volume of water flowing by daily within 4' of top of cap	50,400,000	ft <sup>3</sup> /day
Mass of water flowing by daily within 4' of top of cap	3,144,960,000	lbs/day
Concentration of arsenic in river water within 4' of top of cap	0.037	micrograms per liter (parts per billion)



**Attachment 4**  
**US River Sediment Remediation Projects with**  
**Capping Components**

---

ATTACHMENT 4

# US River Sediment Remediation Projects with Capping Components

---

Date: 11/8/2010

A list was compiled (Table A4-1) of remediation sites where capping was an approved and/or constructed component. List is included as Table 1 to this memorandum. Used the following procedure to compile the list:

- Only included sediment sites within rivers/creeks/channels throughout all regions of the U.S. using USEPA website and knowledge of more recent projects where CH2MHILL was directly involved.
- Only included United States projects – no international projects
- Only included projects that had components or construction dated 1990 or later (also included earlier phases of a project if the most recent phase was 1990 or later)
- Reviewed and cross checked the list for each of the USEPA regions on the Sediment Management Work Group (SMWG) website:  
([http://www.smwg.org/MCSS\\_Database/MCSS\\_Database\\_Docs.html](http://www.smwg.org/MCSS_Database/MCSS_Database_Docs.html))
- Attempted to identify whether the site implemented capping as the part of the “remedy” to deal with in-situ contaminated material or if capping was done to cover residuals after dredging

**Table A4-1**  
**Summary of Contaminated Sediment Capping Projects in Rivers within the U.S.\***

Tyco Fire Products LP Facility  
 Marinette, Wisconsin

Site	Location	Contaminants of Concern	Capping Construction Date	Capping Remedy	Capping Residuals	Remedy/Residuals Not Specified
Thea Foss Waterway	Tacoma, WA	PAH, phthalate esters, metals, PCB, dioxin	Not indicated - after 2002	X		
Hylebos Waterway	Tacoma, WA	Metals, PAH	Late 1990s	X		
Williamette River	Portland, OR	Heavy metals; PAHs	2004?	X		
Upper Sheboygan River	Sheboygan, WI	PCBs	1989-90	X		
Manistique Capping Project	Manistique, MI	PCBs	1993	X		
Ottawa River	Toledo, OH	PCBs	1999	X		
Mill-Quinnipiac River	CT	Metals; PAHs	1981-82; 1982-83; 1993-94			X
S-90-1 Harbor Village	Branford River	not specified	1989-90			X
General Motors Superfund Site	St. Lawrence River, Massena, NY	PCBs	1995	X		
ALCOA	Upper Grasse River, Massena, NY	PCBs	2001	X		
Providence River and Harbor Maintenance Dredging	Rhode Island	Metals?	2002 or 2003?		X	
Pine Street Barge Canal	Burlington, VT	PAHs; Metals; VOCs	2003	X		
Housatonic River, GE Site	Pittsfield, MA	PCBs	?	X		
Messer Street Gas Plant	Winnepesaukee River, Laconia, NH	PAHs	2000-01		X	
Rahway River	Linden, NJ	DDT; Metals	?	X		
Koppers Superfund Site	Ashley River, Charleston, SC	PAHs; PCP; dioxin, lead, arsenic	2001	X		
Calhoun Park/Aquarium	Cooper River, Charleston, SC	PAHs (former MGP site)	1996		X	
Gasse River Project 2	St. Lawrence, NY	PCBs	2001	X		
Sheboygan River Project 2	Sheboygan, WI	PCBs; PAHs	1989-1991	X		
Crotty Street Channel	Bay City, MI	PCBs	1999-2000	X		
McCormick & Baxter (Stockton Plant)	Old Morman Slough, Stockton Deepwater Channel, Stockton, CA	Dioxin/furans; PCBs	2003-04	X		
McCormick & Baxter (Portland Plant)	Williamette River, Portland, OR	PAHs	2004	X		
Lower Duwamish Waterway	Norfolk CSO, Duwamish River, Seattle, WA	??	1999		X	
	Duwamish/Diagonal CSO/Storm Drain within the Duwamish River, Seattle, WA	PCBs; BEHP	2003-04		X	
	Duwamish River/Elliott Bay	As, Pb, Hg, Zn, Cu, PCB, PAH	possibly 2003 - 2004		X	
	Duwamish River/Elliott Bay	As above plus TBT	possibly 2003 - 2004		X	
Kinnickinic River	Milwaukee Wisconsin	PCBs, PAHs	2009		X	
Fox River OU1	Appleton, Wisconsin	PCBs	2007-09	X	X	
Velsicol OU2	Pine River, St. Louis, MI	DDT	2000-06		X	
Ashtabula River	Ashtabula, OH	PCBs	2007	X	X	

\*Information compiled from USEPA Sediment Work Group material available on the internet ([http://www.smwg.org/MCSS\\_Database/MCSS\\_Database\\_Docs.html](http://www.smwg.org/MCSS_Database/MCSS_Database_Docs.html)) and from CH2MHILL's direct site experience

**Appendix B**  
**Analytical Data**

---

Table B1

## Arsenic Concentration Data with Area and Layer Assignments

*Tyco Fire Products LP*

Sample Location ID	Area Location	Top of Sediment Elevation	Sample Date	Top depth of Sample Interval (ft)	Bottom Depth of Sample Interval (ft)	Arsenic Concentration (mg/kg)	Layer Assignment
SD536	6th_St_Slip	575.6	5/22/2010	0.0	-0.5	211	soft sediment
SD536	6th_St_Slip	575.6	5/22/2010	-0.5	-1.0	69.7	soft sediment
SD536	6th_St_Slip	575.6	5/22/2010	-1.0	-1.5	227	soft sediment
SD536	6th_St_Slip	575.6	5/22/2010	-1.5	-2.0	159	soft sediment
SD536	6th_St_Slip	575.6	5/22/2010	-2.0	-2.5	99.3	soft sediment
SD536	6th_St_Slip	575.6	5/22/2010	-2.5	-3.0	88.1	soft sediment
SD536	6th_St_Slip	575.6	5/22/2010	-3.0	-3.5	133	soft sediment
SD536	6th_St_Slip	575.6	5/22/2010	-3.5	-4.5	69	soft sediment
SD536	6th_St_Slip	575.6	5/22/2010	-4.5	-5.0	41.5	soft sediment
SD536	6th_St_Slip	575.6	5/22/2010	-5.0	-5.5	19.2	soft sediment
SD536	6th_St_Slip	575.6	5/22/2010	-5.5	-6.0	14.6	soft sediment
SD536	6th_St_Slip	575.6	5/22/2010	-6.0	-6.5	23.2	soft sediment
SD536	6th_St_Slip	575.6	5/22/2010	-6.5	-7.0	26.8	soft sediment
SD536	6th_St_Slip	575.6	5/22/2010	-7.0	-7.5	19.1	soft sediment
SD536	6th_St_Slip	575.6	5/22/2010	-7.5	-8.0	4.9	soft sediment
SD537	6th_St_Slip	576.5	5/24/2010	0.0	-0.5	84	soft sediment
SD537	6th_St_Slip	576.5	5/24/2010	-0.5	-1.0	176	soft sediment
SD537	6th_St_Slip	576.5	5/24/2010	-1.0	-1.5	150	soft sediment
SD537	6th_St_Slip	576.5	5/24/2010	-1.5	-2.0	169	soft sediment
SD537	6th_St_Slip	576.5	5/24/2010	-2.0	-2.5	200	soft sediment
SD537	6th_St_Slip	576.5	5/24/2010	-2.5	-3.0	176	soft sediment
SD537	6th_St_Slip	576.5	5/24/2010	-3.0	-3.5	101	soft sediment
SD537	6th_St_Slip	576.5	5/24/2010	-3.5	-4.0	77.4	soft sediment
SD537	6th_St_Slip	576.5	5/24/2010	-4.0	-4.5	22.1	soft sediment
SD537	6th_St_Slip	576.5	5/24/2010	-4.5	-5.0	16.1	soft sediment
SD537	6th_St_Slip	576.5	5/24/2010	-5.0	-5.5	18.2	soft sediment
SD537	6th_St_Slip	576.5	5/24/2010	-5.5	-6.0	28	soft sediment
SD537	6th_St_Slip	576.5	5/24/2010	-6.0	-6.5	43	soft sediment
SD537	6th_St_Slip	576.5	5/24/2010	-6.5	-6.8	39.4	soft sediment
SD538	6th_St_Slip	577.7	5/25/2010	0.0	-0.5	3.5	soft sediment
SD538	6th_St_Slip	577.7	5/25/2010	-0.5	-1.0	16	soft sediment
SD538	6th_St_Slip	577.7	5/25/2010	-1.0	-1.5	50.9	soft sediment

Table B1

## Arsenic Concentration Data with Area and Layer Assignments

*Tyco Fire Products LP*

Sample Location ID	Area Location	Top of Sediment Elevation	Sample Date	Top depth of Sample Interval (ft)	Bottom Depth of Sample Interval (ft)	Arsenic Concentration (mg/kg)	Layer Assignment
SD538	6th_St_Slip	577.7	5/25/2010	-1.5	-2.0	36.9	soft sediment
SD538	6th_St_Slip	577.7	5/25/2010	-2.0	-2.5	30	soft sediment
SD538	6th_St_Slip	577.7	5/25/2010	-2.5	-3.0	25.7	soft sediment
SD538	6th_St_Slip	577.7	5/25/2010	-3.0	-3.5	19.3	soft sediment
SD502	Menominee_River	553.4	5/20/2010	0.0	-0.5	53.7	soft sediment
SD503	Menominee_River	556.0	5/23/2010	0.0	-0.5	41.3	soft sediment
SD507	Menominee_River	553.3	5/23/2010	0.0	-0.5	35.1	soft sediment
SD508	Menominee_River	553.6	5/23/2010	0.0	-0.5	42.2	soft sediment
SD511	Menominee_River	553.7	5/23/2010	0.0	-0.5	39.9	soft sediment
SD514	Menominee_River	551.8	5/25/2010	0.0	-1.0	852	soft sediment
SD514	Menominee_River	551.8	5/25/2010	-1.0	-2.0	432	soft sediment
SD514	Menominee_River	551.8	5/25/2010	-2.0	-2.3	220	soft sediment
SD517	Menominee_River	557.5	5/19/2010	0.0	-0.5	11.1	soft sediment
SD551	Menominee_River	553.2	5/20/2010	0.0	-0.5	17.6	soft sediment
SD552	Menominee_River	553.9	5/20/2010	0.0	-0.5	7.7	soft sediment
SD553	Menominee_River	554.6	5/21/2010	0.0	-0.5	6.4	soft sediment
SD553	Menominee_River	554.6	5/21/2010	-0.5	-1.0	5.9	soft sediment
SD553	Menominee_River	554.6	5/21/2010	-1.0	-1.5	4.8	soft sediment
SD553	Menominee_River	554.6	5/21/2010	-1.5	-2.0	6.2	soft sediment
SD554	Menominee_River	554.0	5/21/2010	0.0	-0.5	78.7	soft sediment
SD554	Menominee_River	554.0	5/21/2010	-0.5	-1.0	10.5	soft sediment
SD554	Menominee_River	554.0	5/21/2010	-1.0	-1.5	12	soft sediment
SD554	Menominee_River	554.0	5/21/2010	-1.5	-2.0	8.4	soft sediment
SD554	Menominee_River	554.0	5/21/2010	-2.0	-2.5	6.7	soft sediment
SD555	Menominee_River	552.1	5/23/2010	0.0	-0.5	2.2	soft sediment
SD555	Menominee_River	552.1	5/23/2010	-0.5	-1.0	2.1	soft sediment
SD555	Menominee_River	552.1	5/23/2010	-1.0	-1.5	1.8	soft sediment
SD555	Menominee_River	552.1	5/23/2010	-1.5	-2.0	2.2	soft sediment
SD555	Menominee_River	552.1	5/23/2010	-2.0	-2.5	2	soft sediment
SD556	Menominee_River	553.9	5/20/2010	0.0	-0.5	9.3	soft sediment
SD557	Menominee_River	566.0	5/21/2010	0.0	-0.5	11.2	soft sediment
SD557	Menominee_River	566.0	5/21/2010	-0.5	-1.0	8.1	soft sediment

Table B1

## Arsenic Concentration Data with Area and Layer Assignments

*Tyco Fire Products LP*

Sample Location ID	Area Location	Top of Sediment Elevation	Sample Date	Top depth of Sample Interval (ft)	Bottom Depth of Sample Interval (ft)	Arsenic Concentration (mg/kg)	Layer Assignment
SD557	Menominee_River	566.0	5/21/2010	-1.0	-1.5	7.1	soft sediment
SD564	Menominee_River	552.3	5/18/2010	0.0	-0.5	9.7	soft sediment
SD565	Menominee_River	551.6	5/18/2010	0.0	-0.5	16.1	soft sediment
SD566	Menominee_River	553.4	5/20/2010	0.0	-0.5	12.3	soft sediment
SD502	Menominee_River	553.4	6/9/2010	0.0	-1.0	45.9	semiconsolidated
SD502	Menominee_River	553.4	6/9/2010	-2.0	-3.0	12.1	semiconsolidated
SD502	Menominee_River	553.4	6/9/2010	-4.0	-5.0	20.7	semiconsolidated
SD502	Menominee_River	553.4	6/9/2010	-6.0	-7.0	15.1	semiconsolidated
SD511	Menominee_River	553.7	6/7/2010	0.0	-1.0	4.7	semiconsolidated
SD511	Menominee_River	553.7	6/7/2010	-1.0	-2.0	23.7	semiconsolidated
SD511	Menominee_River	553.7	6/7/2010	-2.0	-3.0	96.9	semiconsolidated
SD511	Menominee_River	553.7	6/7/2010	-3.0	-4.0	36.6	semiconsolidated
SD517	Menominee_River	557.5	6/6/2010	0.0	-1.0	2.2	semiconsolidated
SD517	Menominee_River	557.5	6/6/2010	-2.0	-3.0	2.7	semiconsolidated
SD517	Menominee_River	557.5	6/6/2010	-3.0	-4.0	2	semiconsolidated
SD517	Menominee_River	557.5	6/6/2010	-4.0	-5.0	2.1	semiconsolidated
SD517	Menominee_River	557.5	6/6/2010	-5.0	-6.0	2.2	semiconsolidated
SD517	Menominee_River	557.5	6/6/2010	-6.0	-7.0	2.5	semiconsolidated
SD517	Menominee_River	557.5	6/6/2010	-7.0	-8.0	2.1	semiconsolidated
SD517	Menominee_River	557.5	6/6/2010	-8.0	-9.0	2.4	semiconsolidated
SD517	Menominee_River	557.5	6/6/2010	-9.0	-10.0	2.8	semiconsolidated
SD517	Menominee_River	557.5	6/6/2010	-10.0	-11.0	2.6	semiconsolidated
SD517	Menominee_River	557.5	6/6/2010	-11.0	-12.0	3.1	semiconsolidated
SD551	Menominee_River	553.2	6/10/2010	0.0	-1.0	6.2	semiconsolidated
SD551	Menominee_River	553.2	6/10/2010	-2.0	-3.0	3.1	semiconsolidated
SD552	Menominee_River	553.9	6/14/2010	-1.0	-2.0	2.6	semiconsolidated
SD552	Menominee_River	553.9	6/14/2010	-2.0	-3.0	1.9	semiconsolidated
SD552	Menominee_River	553.9	6/14/2010	-4.0	-5.0	1.4	semiconsolidated
SD553	Menominee_River	554.6	6/7/2010	-2.0	-3.0	2	semiconsolidated
SD553	Menominee_River	554.6	6/7/2010	-3.0	-4.0	1.8	semiconsolidated
SD553	Menominee_River	554.6	6/7/2010	-4.0	-5.0	1.9	semiconsolidated
SD554	Menominee_River	554.0	6/5/2010	-3.0	-4.0	3	semiconsolidated

Table B1

## Arsenic Concentration Data with Area and Layer Assignments

*Tyco Fire Products LP*

Sample Location ID	Area Location	Top of Sediment Elevation	Sample Date	Top depth of Sample Interval (ft)	Bottom Depth of Sample Interval (ft)	Arsenic Concentration (mg/kg)	Layer Assignment
SD554	Menominee_River	554.0	6/5/2010	-4.0	-5.0	2.8	semiconsolidated
SD554	Menominee_River	554.0	6/5/2010	-5.0	-6.0	2.8	semiconsolidated
SD555	Menominee_River	552.1	6/5/2010	-3.0	-4.0	2.4	semiconsolidated
SD555	Menominee_River	552.1	6/5/2010	-5.0	-6.0	2.2	semiconsolidated
SD555	Menominee_River	552.1	6/5/2010	-6.0	-7.0	2.2	semiconsolidated
SD555	Menominee_River	552.1	6/5/2010	-7.0	-8.0	2.5	semiconsolidated
SD556	Menominee_River	553.9	6/4/2010	0.0	-1.0	2.7	semiconsolidated
SD556	Menominee_River	553.9	6/4/2010	-1.0	-2.0	2.7	semiconsolidated
SD556	Menominee_River	553.9	6/4/2010	-2.0	-3.0	5.4	semiconsolidated
SD556	Menominee_River	553.9	6/4/2010	-4.0	-5.0	2.3	semiconsolidated
SD556	Menominee_River	553.9	6/4/2010	-5.0	-6.0	2.7	semiconsolidated
SD556	Menominee_River	553.9	6/4/2010	-6.0	-7.0	3	semiconsolidated
SD556	Menominee_River	553.9	6/4/2010	-7.0	-8.0	2.4	semiconsolidated
SD557	Menominee_River	566.0	6/5/2010	-5.0	-6.0	2.2	semiconsolidated
SD557	Menominee_River	566.0	6/5/2010	-7.0	-8.0	2.7	semiconsolidated
SD557	Menominee_River	566.0	6/5/2010	-9.0	-10.0	2	semiconsolidated
SD557	Menominee_River	566.0	6/5/2010	-11.0	-12.0	1.9	semiconsolidated
SD557	Menominee_River	566.0	6/5/2010	-13.0	-14.0	2.2	semiconsolidated
SD557	Menominee_River	566.0	6/5/2010	-14.0	-15.0	2.1	semiconsolidated
SD557	Menominee_River	566.0	6/5/2010	-15.0	-16.0	2	semiconsolidated
SD557	Menominee_River	566.0	6/5/2010	-17.0	-18.0	2.4	semiconsolidated
SD557	Menominee_River	566.0	6/5/2010	-18.0	-19.0	2.8	semiconsolidated
SD557	Menominee_River	566.0	6/5/2010	-19.0	-20.0	3.4	semiconsolidated
SD557	Menominee_River	566.0	6/5/2010	-20.0	-21.0	2.9	semiconsolidated
SD564	Menominee_River	552.3	6/10/2010	0.0	-1.0	6.6	semiconsolidated
SD564	Menominee_River	552.3	6/10/2010	-4.0	-5.0	5.5	semiconsolidated
SD565	Menominee_River	551.6	6/10/2010	0.0	-1.0	3.3	semiconsolidated
SD565	Menominee_River	551.6	6/10/2010	-2.0	-3.0	1.6	semiconsolidated
SD565	Menominee_River	551.6	6/10/2010	-3.0	-4.0	2.1	semiconsolidated
SD565	Menominee_River	551.6	6/10/2010	-4.0	-5.0	1.9	semiconsolidated
SD565	Menominee_River	551.6	6/10/2010	-5.0	-6.0	2.1	semiconsolidated
SD566	Menominee_River	553.4	6/10/2010	0.0	-1.0	4.7	semiconsolidated

Table B1

## Arsenic Concentration Data with Area and Layer Assignments

*Tyco Fire Products LP*

Sample Location ID	Area Location	Top of Sediment Elevation	Sample Date	Top depth of Sample Interval (ft)	Bottom Depth of Sample Interval (ft)	Arsenic Concentration (mg/kg)	Layer Assignment
SD566	Menominee_River	553.4	6/10/2010	-1.0	-2.0	2	semiconsolidated
SD566	Menominee_River	553.4	6/10/2010	-2.0	-3.0	2.2	semiconsolidated
SD566	Menominee_River	553.4	6/10/2010	-3.0	-4.0	1.9	semiconsolidated
SD566	Menominee_River	553.4	6/10/2010	-4.0	-5.0	3	semiconsolidated
SD566	Menominee_River	553.4	6/10/2010	-5.0	-6.0	1.7	semiconsolidated
SD511	Menominee_River	553.7	6/7/2010	-4.0	-5.0	2.7	till
SD511	Menominee_River	553.7	6/7/2010	-5.0	-6.0	1.8	till
SD514	Menominee_River	551.8	6/15/2010	-3.0	-4.0	144	till
SD514	Menominee_River	551.8	6/15/2010	-4.0	-5.0	46.4	till
SD514	Menominee_River	551.8	6/15/2010	-5.0	-6.0	43.9	till
SD514	Menominee_River	551.8	6/15/2010	-6.0	-7.0	7.2	till
SD514	Menominee_River	551.8	6/15/2010	-9.0	-10.0	5.9	till
SD517	Menominee_River	557.5	6/6/2010	-12.0	-13.0	2.6	till
SD517	Menominee_River	557.5	6/6/2010	-13.0	-14.0	3	till
SD551	Menominee_River	553.2	6/10/2010	-3.0	-4.0	2.1	till
SD552	Menominee_River	553.9	6/14/2010	-6.0	-7.0	1.6	till
SD553	Menominee_River	554.6	6/7/2010	-5.0	-6.0	1.9	till
SD554	Menominee_River	554.0	6/5/2010	-6.0	-7.0	2.1	till
SD554	Menominee_River	554.0	6/5/2010	-7.0	-8.0	1.9	till
SD554	Menominee_River	554.0	6/5/2010	-8.0	-9.0	2.1	till
SD554	Menominee_River	554.0	6/5/2010	-9.0	-10.0	2.1	till
SD554	Menominee_River	554.0	6/5/2010	-10.0	-11.0	2	till
SD554	Menominee_River	554.0	6/5/2010	-11.0	-12.0	2.7	till
SD555	Menominee_River	552.1	6/5/2010	-10.0	-11.0	2.1	till
SD556	Menominee_River	553.9	6/4/2010	-8.0	-9.0	2.4	till
SD556	Menominee_River	553.9	6/4/2010	-9.0	-10.0	2.7	till
SD556	Menominee_River	553.9	6/4/2010	-10.0	-11.0	2.3	till
SD556	Menominee_River	553.9	6/4/2010	-11.0	-12.0	2.6	till
SD556	Menominee_River	553.9	6/4/2010	-12.0	-13.0	2.3	till
SD556	Menominee_River	553.9	6/4/2010	-13.0	-14.0	2.2	till
SD564	Menominee_River	552.3	6/10/2010	-5.0	-5.7	14.7	till
SD565	Menominee_River	551.6	6/10/2010	-6.0	-7.0	2.2	till

Table B1

## Arsenic Concentration Data with Area and Layer Assignments

*Tyco Fire Products LP*

Sample Location ID	Area Location	Top of Sediment Elevation	Sample Date	Top depth of Sample Interval (ft)	Bottom Depth of Sample Interval (ft)	Arsenic Concentration (mg/kg)	Layer Assignment
SD565	Menominee_River	551.6	6/10/2010	-7.0	-8.0	2.2	till
SD565	Menominee_River	551.6	6/10/2010	-8.0	-8.8	2.3	till
SD514	Menominee_River	551.8	6/15/2010	-10.0	-11.0	6.8	weathered bedrock
SD541	South_Channel	575.6	5/25/2010	0.0	-0.5	42.5	soft sediment
SD541	South_Channel	575.6	5/25/2010	-0.5	-1.0	20.9	soft sediment
SD541	South_Channel	575.6	5/25/2010	-1.0	-1.5	15.5	soft sediment
SD541	South_Channel	575.6	5/25/2010	-1.5	-2.0	3.9	soft sediment
SD541	South_Channel	575.6	5/25/2010	-2.0	-2.5	3.2	soft sediment
SD541	South_Channel	575.6	5/25/2010	-2.5	-3.0	1.9	soft sediment
SD541	South_Channel	575.6	5/25/2010	-3.0	-3.2	2.7	soft sediment
SD543	South_Channel	575.7	5/24/2010	0.0	-0.5	37.5	soft sediment
SD543	South_Channel	575.7	5/24/2010	-0.5	-1.0	35.9	soft sediment
SD543	South_Channel	575.7	5/24/2010	-1.0	-1.5	22	soft sediment
SD544	South_Channel	576.0	5/23/2010	0.0	-0.5	26.1	soft sediment
SD544	South_Channel	576.0	5/23/2010	-0.5	-1.0	6.2	soft sediment
SD544	South_Channel	576.0	5/23/2010	-1.0	-1.5	3.5	soft sediment
SD544	South_Channel	576.0	5/23/2010	-1.5	-2.0	1.8	soft sediment
SD544	South_Channel	576.0	5/23/2010	-2.0	-2.5	1.7	soft sediment
SD545	South_Channel	576.2	5/26/2010	0.0	-0.5	52.3	soft sediment
SD545	South_Channel	576.2	5/26/2010	-0.5	-1.0	73.2	soft sediment
SD545	South_Channel	576.2	5/26/2010	-1.0	-1.5	53.9	soft sediment
SD545	South_Channel	576.2	5/26/2010	-1.5	-1.9	31.8	soft sediment
SD546	South_Channel	576.0	5/26/2010	0.0	-0.5	69.8	soft sediment
SD546	South_Channel	576.0	5/26/2010	-0.5	-1.0	57.7	soft sediment
SD546	South_Channel	576.0	5/26/2010	-1.0	-1.5	67.2	soft sediment
SD547	South_Channel	576.4	5/24/2010	0.0	-0.5	28.4	soft sediment
SD548	South_Channel	575.7	5/24/2010	0.0	-0.5	95.7	soft sediment
SD548	South_Channel	575.7	5/24/2010	-0.5	-1.0	85.6	soft sediment
SD548	South_Channel	575.7	5/24/2010	-1.0	-1.5	63.9	soft sediment
SD548	South_Channel	575.7	5/24/2010	-1.5	-2.0	25.3	soft sediment
SD548	South_Channel	575.7	5/24/2010	-2.0	-2.2	12.2	soft sediment
SD549	South_Channel	575.7	5/25/2010	0.0	-0.5	94.7	soft sediment

Table B1

## Arsenic Concentration Data with Area and Layer Assignments

*Tyco Fire Products LP*

Sample Location ID	Area Location	Top of Sediment Elevation	Sample Date	Top depth of Sample Interval (ft)	Bottom Depth of Sample Interval (ft)	Arsenic Concentration (mg/kg)	Layer Assignment
SD549	South_Channel	575.7	5/25/2010	-0.5	-1.0	112	soft sediment
SD549	South_Channel	575.7	5/25/2010	-1.0	-1.5	81.7	soft sediment
SD549	South_Channel	575.7	5/25/2010	-1.5	-2.0	55.1	soft sediment
SD549	South_Channel	575.7	5/25/2010	-2.0	-2.4	11	soft sediment
SD550	South_Channel	576.4	5/26/2010	0.0	-0.5	65	soft sediment
SD550	South_Channel	576.4	5/26/2010	-0.5	-1.0	15.1	soft sediment
SD550	South_Channel	576.4	5/26/2010	-1.0	-1.5	3.6	soft sediment
SD567	South_Channel	576.4	5/26/2010	0.0	-0.5	76.6	soft sediment
SD567	South_Channel	576.4	5/26/2010	-0.5	-1.0	31.4	soft sediment
SD568	South_Channel	577.0	5/24/2010	0.0	-0.5	46.5	soft sediment
SD568	South_Channel	577.0	5/24/2010	-0.5	-1.0	5.5	soft sediment
SD569	South_Channel	576.7	5/24/2010	0.0	-0.5	111	soft sediment
SD569	South_Channel	576.7	5/24/2010	-0.5	-1.0	99.3	soft sediment
SD570	South_Channel	576.8	5/26/2010	0.0	-0.5	94.5	soft sediment
SD570	South_Channel	576.8	5/26/2010	-0.5	-1.0	14.8	soft sediment
SD570	South_Channel	576.8	5/26/2010	-1.0	-1.5	23.5	soft sediment
SD570	South_Channel	576.8	5/26/2010	-1.5	-2.0	4.7	soft sediment
SD571	South_Channel	577.0	5/26/2010	0.0	-0.5	10.5	soft sediment
SD571	South_Channel	577.0	5/26/2010	-0.5	-1.0	15.5	soft sediment
SD571	South_Channel	577.0	5/26/2010	-1.0	-1.4	25.7	soft sediment
SD572	South_Channel	576.4	5/24/2010	0.0	-0.5	7.8	soft sediment
SD572	South_Channel	576.4	5/24/2010	-0.5	-1.0	24.8	soft sediment
SD572	South_Channel	576.4	5/24/2010	-1.0	-1.4	52.1	soft sediment
SD573	South_Channel	577.7	5/26/2010	0.0	-0.5	2.8	soft sediment
SD573	South_Channel	577.7	5/26/2010	-0.5	-1.0	4.5	soft sediment
SD573	South_Channel	577.7	5/26/2010	-1.0	-1.5	4.9	soft sediment
SD573	South_Channel	577.7	5/26/2010	-1.5	-2.0	3.8	soft sediment
SD521	Transition_Area_1	576.1	5/20/2010	0.0	-0.5	6.1	soft sediment
SD521	Transition_Area_1	576.1	5/20/2010	-0.5	-1.0	6.5	soft sediment
SD521	Transition_Area_1	576.1	5/20/2010	-1.0	-1.5	4.2	soft sediment
SD521	Transition_Area_1	576.1	5/20/2010	-1.5	-2.0	2.2	soft sediment
SD521	Transition_Area_1	576.1	5/20/2010	-2.0	-2.5	4.2	soft sediment

Table B1

## Arsenic Concentration Data with Area and Layer Assignments

*Tyco Fire Products LP*

Sample Location ID	Area Location	Top of Sediment Elevation	Sample Date	Top depth of Sample Interval (ft)	Bottom Depth of Sample Interval (ft)	Arsenic Concentration (mg/kg)	Layer Assignment
SD521	Transition_Area_1	576.1	5/20/2010	-2.5	-3.0	3.3	soft sediment
SD521	Transition_Area_1	576.1	5/20/2010	-3.0	-3.5	7.7	soft sediment
SD522	Transition_Area_1	577.4	5/24/2010	0.0	-0.5	7.5	soft sediment
SD522	Transition_Area_1	577.4	5/24/2010	-0.5	-1.0	4.7	soft sediment
SD522	Transition_Area_1	577.4	5/24/2010	-1.0	-1.5	4.7	soft sediment
SD522	Transition_Area_1	577.4	5/24/2010	-1.5	-2.0	5.9	soft sediment
SD522	Transition_Area_1	577.4	5/24/2010	-2.0	-2.5	7.1	soft sediment
SD522	Transition_Area_1	577.4	5/24/2010	-2.5	-3.0	7.2	soft sediment
SD522	Transition_Area_1	577.4	5/24/2010	-3.0	-3.5	4.6	soft sediment
SD522	Transition_Area_1	577.4	5/24/2010	-3.5	-4.0	5.8	soft sediment
SD522	Transition_Area_1	577.4	5/24/2010	-4.0	-4.4	7.3	soft sediment
SD523VC	Transition_Area_1	577.1	5/21/2010	0.0	-0.5	13.7	soft sediment
SD523VC	Transition_Area_1	577.1	5/21/2010	-0.5	-1.0	11.1	soft sediment
SD523VC	Transition_Area_1	577.1	5/21/2010	-1.0	-1.5	11.3	soft sediment
SD523VC	Transition_Area_1	577.1	5/21/2010	-1.5	-2.0	15.4	soft sediment
SD523VC	Transition_Area_1	577.1	5/21/2010	-2.0	-2.5	10.4	soft sediment
SD523VC	Transition_Area_1	577.1	5/21/2010	-2.5	-3.0	17	soft sediment
SD524	Transition_Area_1	577.0	5/20/2010	0.0	-0.5	6.4	soft sediment
SD524	Transition_Area_1	577.0	5/20/2010	-0.5	-1.0	5	soft sediment
SD524	Transition_Area_1	577.0	5/20/2010	-1.0	-1.5	5.7	soft sediment
SD524	Transition_Area_1	577.0	5/20/2010	-1.5	-2.0	6	soft sediment
SD524	Transition_Area_1	577.0	5/20/2010	-2.0	-2.5	3.4	soft sediment
SD524	Transition_Area_1	577.0	5/20/2010	-2.5	-3.0	6.4	soft sediment
SD524	Transition_Area_1	577.0	5/20/2010	-3.0	-3.5	3.5	soft sediment
SD532	Transition_Area_1	575.7	5/21/2010	0.0	-0.5	13.6	soft sediment
SD532	Transition_Area_1	575.7	5/21/2010	-0.5	-1.0	16	soft sediment
SD532	Transition_Area_1	575.7	5/21/2010	-1.0	-1.5	8.3	soft sediment
SD532	Transition_Area_1	575.7	5/21/2010	-1.5	-2.0	0.71	soft sediment
SD532	Transition_Area_1	575.7	5/21/2010	-2.0	-2.5	5.3	soft sediment
SD532	Transition_Area_1	575.7	5/21/2010	-2.5	-3.0	5	soft sediment
SD532	Transition_Area_1	575.7	5/21/2010	-3.0	-3.5	4.6	soft sediment
SD539	Transition_Area_1	576.3	5/21/2010	0.0	-0.5	20.7	soft sediment

Table B1

## Arsenic Concentration Data with Area and Layer Assignments

*Tyco Fire Products LP*

Sample Location ID	Area Location	Top of Sediment Elevation	Sample Date	Top depth of Sample Interval (ft)	Bottom Depth of Sample Interval (ft)	Arsenic Concentration (mg/kg)	Layer Assignment
SD539	Transition_Area_1	576.3	5/21/2010	-0.5	-1.0	16	soft sediment
SD539	Transition_Area_1	576.3	5/21/2010	-1.0	-1.5	6.2	soft sediment
SD539	Transition_Area_1	576.3	5/21/2010	-1.5	-2.0	3.1	soft sediment
SD539	Transition_Area_1	576.3	5/21/2010	-2.0	-2.5	1.6	soft sediment
SD539	Transition_Area_1	576.3	5/21/2010	-2.5	-3.0	1.9	soft sediment
SD542	Transition_Area_1	576.4	5/21/2010	0.0	-0.5	19.6	soft sediment
SD542	Transition_Area_1	576.4	5/21/2010	-0.5	-1.0	12.4	soft sediment
SD542	Transition_Area_1	576.4	5/21/2010	-1.0	-1.5	4	soft sediment
SD542	Transition_Area_1	576.4	5/21/2010	-1.5	-2.0	2.1	soft sediment
SD542	Transition_Area_1	576.4	5/21/2010	-2.0	-2.5	1.7	soft sediment
SD542	Transition_Area_1	576.4	5/21/2010	-2.5	-3.0	1.8	soft sediment
SD542	Transition_Area_1	576.4	5/21/2010	-3.0	-3.5	5.9	soft sediment
SD542	Transition_Area_1	576.4	5/21/2010	-3.5	-4.0	2.5	soft sediment
SD523HSA	Transition_Area_1	577.4	6/9/2010	-5.0	-6.0	3.6	semiconsolidated
SD523HSA	Transition_Area_1	577.4	6/9/2010	-7.0	-8.0	4.3	semiconsolidated
SD523HSA	Transition_Area_1	577.4	6/9/2010	-9.0	-10.0	3.6	semiconsolidated
SD523HSA	Transition_Area_1	577.4	6/9/2010	-11.0	-12.0	2.6	semiconsolidated
SD523HSA	Transition_Area_1	577.4	6/9/2010	-13.0	-14.0	2.8	semiconsolidated
SD523HSA	Transition_Area_1	577.4	6/9/2010	-14.0	-15.0	2.8	semiconsolidated
SD523HSA	Transition_Area_1	577.4	6/9/2010	-15.0	-16.0	2.7	semiconsolidated
SD523HSA	Transition_Area_1	577.4	6/9/2010	-16.0	-17.0	2.7	semiconsolidated
SD523HSA	Transition_Area_1	577.4	6/9/2010	-17.0	-18.0	2.6	semiconsolidated
SD523HSA	Transition_Area_1	577.4	6/9/2010	-18.0	-19.0	2.8	semiconsolidated
SD523HSA	Transition_Area_1	577.4	6/9/2010	-19.0	-20.0	3	semiconsolidated
SD523HSA	Transition_Area_1	577.4	6/9/2010	-20.0	-21.0	2.4	semiconsolidated
SD523HSA	Transition_Area_1	577.4	6/9/2010	-21.0	-22.0	2.6	semiconsolidated
SD523HSA	Transition_Area_1	577.4	6/9/2010	-22.0	-23.0	2.2	semiconsolidated
SD523HSA	Transition_Area_1	577.4	6/9/2010	-23.0	-24.0	2.5	semiconsolidated
SD523HSA	Transition_Area_1	577.4	6/9/2010	-24.0	-25.0	2.2	semiconsolidated
SD523HSA	Transition_Area_1	577.4	6/9/2010	-25.0	-26.0	1.9	semiconsolidated
SD523HSA	Transition_Area_1	577.4	6/9/2010	-27.0	-28.0	2.1	semiconsolidated
SD523HSA	Transition_Area_1	577.4	6/9/2010	-29.0	-30.0	2	semiconsolidated

Table B1

## Arsenic Concentration Data with Area and Layer Assignments

*Tyco Fire Products LP*

Sample Location ID	Area Location	Top of Sediment Elevation	Sample Date	Top depth of Sample Interval (ft)	Bottom Depth of Sample Interval (ft)	Arsenic Concentration (mg/kg)	Layer Assignment
SD523HSA	Transition_Area_1	577.4	6/9/2010	-30.0	-31.0	2	semiconsolidated
SD523HSA	Transition_Area_1	577.4	6/9/2010	-31.0	-32.0	2.6	till
SD520	Transition_Area_2	574.5	5/24/2010	0.0	-0.5	17.7	soft sediment
SD520	Transition_Area_2	574.5	5/24/2010	-0.5	-1.0	17.5	soft sediment
SD520	Transition_Area_2	574.5	5/24/2010	-1.0	-1.5	8.6	soft sediment
SD520	Transition_Area_2	574.5	5/24/2010	-1.5	-2.0	3.9	soft sediment
SD520	Transition_Area_2	574.5	5/24/2010	-2.0	-2.5	2.1	soft sediment
SD520	Transition_Area_2	574.5	5/24/2010	-2.5	-3.0	2.9	soft sediment
SD525	Transition_Area_2	577.7	5/24/2010	0.0	-0.5	12.3	soft sediment
SD525	Transition_Area_2	577.7	5/24/2010	-0.5	-1.0	15.8	soft sediment
SD525	Transition_Area_2	577.7	5/24/2010	-1.0	-1.3	10.9	soft sediment
SD526	Transition_Area_2	577.5	5/25/2010	0.0	-0.5	17	soft sediment
SD526	Transition_Area_2	577.5	5/25/2010	-0.5	-1.0	19.3	soft sediment
SD526	Transition_Area_2	577.5	5/25/2010	-1.0	-1.5	6.6	soft sediment
SD526	Transition_Area_2	577.5	5/25/2010	-1.5	-2.0	5.4	soft sediment
SD526	Transition_Area_2	577.5	5/25/2010	-2.0	-2.5	8.7	soft sediment
SD526	Transition_Area_2	577.5	5/25/2010	-2.5	-3.0	3.3	soft sediment
SD527	Transition_Area_2	573.3	5/23/2010	0.0	-0.5	1060	soft sediment
SD527	Transition_Area_2	573.3	5/23/2010	-0.5	-1.0	1200	soft sediment
SD527	Transition_Area_2	573.3	5/23/2010	-1.0	-1.5	1100	soft sediment
SD527	Transition_Area_2	573.3	5/23/2010	-1.5	-2.0	2440	soft sediment
SD527	Transition_Area_2	573.3	5/23/2010	-2.0	-2.5	4090	soft sediment
SD527	Transition_Area_2	573.3	5/23/2010	-2.5	-3.0	2270	soft sediment
SD527	Transition_Area_2	573.3	5/23/2010	-3.0	-3.5	5030	soft sediment
SD527	Transition_Area_2	573.3	5/23/2010	-3.5	-4.0	3980	soft sediment
SD527	Transition_Area_2	573.3	5/23/2010	-4.0	-4.5	1610	soft sediment
SD528	Transition_Area_2	575.4	5/23/2010	0.0	-0.5	29.1	soft sediment
SD528	Transition_Area_2	575.4	5/23/2010	-0.5	-1.0	14.9	soft sediment
SD528	Transition_Area_2	575.4	5/23/2010	-1.0	-1.5	12	soft sediment
SD528	Transition_Area_2	575.4	5/23/2010	-1.5	-2.0	5.8	soft sediment
SD528	Transition_Area_2	575.4	5/23/2010	-2.0	-2.5	5.5	soft sediment
SD528	Transition_Area_2	575.4	5/23/2010	-2.5	-3.0	8.8	soft sediment

Table B1

## Arsenic Concentration Data with Area and Layer Assignments

*Tyco Fire Products LP*

Sample Location ID	Area Location	Top of Sediment Elevation	Sample Date	Top depth of Sample Interval (ft)	Bottom Depth of Sample Interval (ft)	Arsenic Concentration (mg/kg)	Layer Assignment
SD528	Transition_Area_2	575.4	5/23/2010	-3.0	-3.2	6.2	soft sediment
SD529	Transition_Area_2	577.7	5/25/2010	0.0	-0.5	2.6	soft sediment
SD529	Transition_Area_2	577.7	5/25/2010	-0.5	-1.0	3.1	soft sediment
SD529	Transition_Area_2	577.7	5/25/2010	-1.0	-1.5	2.5	soft sediment
SD529	Transition_Area_2	577.7	5/25/2010	-1.5	-2.0	2.7	soft sediment
SD529	Transition_Area_2	577.7	5/25/2010	-2.0	-2.3	3.8	soft sediment
SD530	Transition_Area_2	576.8	5/23/2010	0.0	-0.5	23	soft sediment
SD530	Transition_Area_2	576.8	5/23/2010	-0.5	-1.0	31.2	soft sediment
SD530	Transition_Area_2	576.8	5/23/2010	-1.0	-1.5	13.4	soft sediment
SD530	Transition_Area_2	576.8	5/23/2010	-1.5	-2.0	9.2	soft sediment
SD530	Transition_Area_2	576.8	5/23/2010	-2.0	-2.5	6.8	soft sediment
SD530	Transition_Area_2	576.8	5/23/2010	-2.5	-3.0	7.7	soft sediment
SD530	Transition_Area_2	576.8	5/23/2010	-3.0	-3.4	2.8	soft sediment
SD531	Transition_Area_2	576.1	5/22/2010	0.0	-0.5	9.4	soft sediment
SD531	Transition_Area_2	576.1	5/22/2010	-0.5	-1.0	33.2	soft sediment
SD531	Transition_Area_2	576.1	5/22/2010	-1.0	-1.5	24.3	soft sediment
SD531	Transition_Area_2	576.1	5/22/2010	-1.5	-2.0	15.1	soft sediment
SD531	Transition_Area_2	576.1	5/22/2010	-2.0	-2.5	13.9	soft sediment
SD531	Transition_Area_2	576.1	5/22/2010	-2.5	-3.0	16.2	soft sediment
SD531	Transition_Area_2	576.1	5/22/2010	-3.0	-3.4	17.3	soft sediment
SD533	Transition_Area_2	575.8	5/22/2010	0.0	-0.5	48.1	soft sediment
SD533	Transition_Area_2	575.8	5/22/2010	-0.5	-1.0	55.1	soft sediment
SD533	Transition_Area_2	575.8	5/22/2010	-1.0	-1.5	16.9	soft sediment
SD533	Transition_Area_2	575.8	5/22/2010	-1.5	-2.0	8.3	soft sediment
SD533	Transition_Area_2	575.8	5/22/2010	-2.0	-2.5	5.3	soft sediment
SD533	Transition_Area_2	575.8	5/22/2010	-2.5	-3.0	2.5	soft sediment
SD533	Transition_Area_2	575.8	5/22/2010	-3.0	-3.4	1.8	soft sediment
SD534	Transition_Area_2	575.3	5/22/2010	0.0	-0.5	57.6	soft sediment
SD534	Transition_Area_2	575.3	5/22/2010	-0.5	-1.0	61.1	soft sediment
SD534	Transition_Area_2	575.3	5/22/2010	-1.0	-1.5	58	soft sediment
SD534	Transition_Area_2	575.3	5/22/2010	-1.5	-2.0	6.1	soft sediment
SD534	Transition_Area_2	575.3	5/22/2010	-2.0	-2.5	3.4	soft sediment

Table B1

## Arsenic Concentration Data with Area and Layer Assignments

*Tyco Fire Products LP*

Sample Location ID	Area Location	Top of Sediment Elevation	Sample Date	Top depth of Sample Interval (ft)	Bottom Depth of Sample Interval (ft)	Arsenic Concentration (mg/kg)	Layer Assignment
SD534	Transition_Area_2	575.3	5/22/2010	-2.5	-2.9	3.4	soft sediment
SD535	Transition_Area_2	575.7	5/22/2010	0.0	-0.5	8.3	soft sediment
SD535	Transition_Area_2	575.7	5/22/2010	-0.5	-1.0	8.1	soft sediment
SD535	Transition_Area_2	575.7	5/22/2010	-1.0	-1.5	2.3	soft sediment
SD535	Transition_Area_2	575.7	5/22/2010	-1.5	-2.0	1.5	soft sediment
SD535	Transition_Area_2	575.7	5/22/2010	-2.0	-2.4	1.4	soft sediment
SD540	Transition_Area_2	575.6	5/21/2010	0.0	-0.5	3.2	soft sediment
SD540	Transition_Area_2	575.6	5/21/2010	-0.5	-1.0	2.6	soft sediment
SD540	Transition_Area_2	575.6	5/21/2010	-1.0	-1.5	1.9	soft sediment
SD540	Transition_Area_2	575.6	5/21/2010	-1.5	-2.0	2.2	soft sediment
SD540	Transition_Area_2	575.6	5/21/2010	-2.0	-2.5	2.1	soft sediment
SD558	Transition_Area_2	577.4	5/23/2010	0.0	-0.5	33.9	soft sediment
SD558	Transition_Area_2	577.4	5/23/2010	-0.5	-1.0	21.9	soft sediment
SD558	Transition_Area_2	577.4	5/23/2010	-1.0	-1.5	9.4	soft sediment
SD558	Transition_Area_2	577.4	5/23/2010	-1.5	-2.0	6.7	soft sediment
SD558	Transition_Area_2	577.4	5/23/2010	-2.0	-2.5	3.9	soft sediment
SD558	Transition_Area_2	577.4	5/23/2010	-2.5	-3.0	6.6	soft sediment
SD558	Transition_Area_2	577.4	5/23/2010	-3.0	-3.5	1.9	soft sediment
SD559	Transition_Area_2	576.3	5/23/2010	0.0	-0.5	38.2	soft sediment
SD559	Transition_Area_2	576.3	5/23/2010	-0.5	-1.0	31.4	soft sediment
SD559	Transition_Area_2	576.3	5/23/2010	-1.0	-1.5	10.5	soft sediment
SD559	Transition_Area_2	576.3	5/23/2010	-1.5	-2.0	1.7	soft sediment
SD559	Transition_Area_2	576.3	5/23/2010	-2.0	-2.5	3	soft sediment
SD559	Transition_Area_2	576.3	5/23/2010	-2.5	-3.0	2.3	soft sediment
SD560	Transition_Area_2	573.9	5/23/2010	0.0	-0.5	50.2	soft sediment
SD560	Transition_Area_2	573.9	5/23/2010	-0.5	-1.0	28.6	soft sediment
SD560	Transition_Area_2	573.9	5/23/2010	-1.0	-1.5	10.7	soft sediment
SD560	Transition_Area_2	573.9	5/23/2010	-1.5	-2.0	4.1	soft sediment
SD560	Transition_Area_2	573.9	5/23/2010	-2.0	-2.5	5.9	soft sediment
SD560	Transition_Area_2	573.9	5/23/2010	-2.5	-3.0	13.2	soft sediment
SD560	Transition_Area_2	573.9	5/23/2010	-3.0	-3.5	237	soft sediment
SD560	Transition_Area_2	573.9	6/3/2010	-5.0	-6.0	10.8	semiconsolidated

Table B1

## Arsenic Concentration Data with Area and Layer Assignments

*Tyco Fire Products LP*

Sample Location ID	Area Location	Top of Sediment Elevation	Sample Date	Top depth of Sample Interval (ft)	Bottom Depth of Sample Interval (ft)	Arsenic Concentration (mg/kg)	Layer Assignment
SD560	Transition_Area_2	573.9	6/3/2010	-7.0	-8.0	523	semiconsolidated
SD560	Transition_Area_2	573.9	6/3/2010	-9.0	-10.0	77.1	semiconsolidated
SD560	Transition_Area_2	573.9	6/3/2010	-11.0	-12.0	141	semiconsolidated
SD560	Transition_Area_2	573.9	6/3/2010	-12.0	-13.0	305	semiconsolidated
SD560	Transition_Area_2	573.9	6/3/2010	-13.0	-14.0	52.7	semiconsolidated
SD560	Transition_Area_2	573.9	6/3/2010	-14.0	-15.0	33.3	semiconsolidated
SD560	Transition_Area_2	573.9	6/3/2010	-15.0	-16.0	101	semiconsolidated
SD560	Transition_Area_2	573.9	6/3/2010	-16.0	-17.0	305	semiconsolidated
SD560	Transition_Area_2	573.9	6/3/2010	-17.0	-18.0	230	semiconsolidated
SD560	Transition_Area_2	573.9	6/3/2010	-18.0	-19.0	577	semiconsolidated
SD560	Transition_Area_2	573.9	6/3/2010	-19.0	-20.0	322	semiconsolidated
SD560	Transition_Area_2	573.9	6/3/2010	-20.0	-21.0	418	semiconsolidated
SD560	Transition_Area_2	573.9	6/3/2010	-21.0	-22.0	89.5	semiconsolidated
SD560	Transition_Area_2	573.9	6/3/2010	-22.0	-23.0	139	semiconsolidated
SD560	Transition_Area_2	573.9	6/3/2010	-23.0	-24.0	25.8	semiconsolidated
SD560	Transition_Area_2	573.9	6/3/2010	-24.0	-25.0	4	semiconsolidated
SD560	Transition_Area_2	573.9	6/3/2010	-25.0	-26.0	19.8	semiconsolidated
SD560	Transition_Area_2	573.9	6/3/2010	-26.0	-27.0	1.4	semiconsolidated
SD560	Transition_Area_2	573.9	6/3/2010	-27.0	-28.0	8.7	semiconsolidated
SD560	Transition_Area_2	573.9	6/3/2010	-28.0	-29.0	1.7	semiconsolidated
SD560	Transition_Area_2	573.9	6/3/2010	-29.0	-30.0	3.5	semiconsolidated
SD574	Transition_Area_2	576.7	6/13/2010	-5.0	-6.0	13.2	semiconsolidated
SD574	Transition_Area_2	576.7	6/13/2010	-7.0	-8.0	62.4	semiconsolidated
SD574	Transition_Area_2	576.7	6/13/2010	-9.0	-10.0	61.3	semiconsolidated
SD574	Transition_Area_2	576.7	6/13/2010	-10.0	-11.0	108	semiconsolidated
SD574	Transition_Area_2	576.7	6/13/2010	-11.0	-12.0	55.7	semiconsolidated
SD574	Transition_Area_2	576.7	6/13/2010	-12.0	-13.0	145	semiconsolidated
SD574	Transition_Area_2	576.7	6/13/2010	-13.0	-14.0	79.1	semiconsolidated
SD574	Transition_Area_2	576.7	6/13/2010	-14.0	-15.0	78.4	semiconsolidated
SD574	Transition_Area_2	576.7	6/13/2010	-15.0	-16.0	31.3	semiconsolidated
SD574	Transition_Area_2	576.7	6/13/2010	-16.0	-17.0	5.5	semiconsolidated
SD574	Transition_Area_2	576.7	6/13/2010	-17.0	-18.0	10.5	semiconsolidated

Table B1

## Arsenic Concentration Data with Area and Layer Assignments

*Tyco Fire Products LP*

Sample Location ID	Area Location	Top of Sediment Elevation	Sample Date	Top depth of Sample Interval (ft)	Bottom Depth of Sample Interval (ft)	Arsenic Concentration (mg/kg)	Layer Assignment
SD574	Transition_Area_2	576.7	6/13/2010	-18.0	-19.0	5.1	semiconsolidated
SD574	Transition_Area_2	576.7	6/13/2010	-19.0	-20.0	66.3	semiconsolidated
SD574	Transition_Area_2	576.7	6/13/2010	-20.0	-21.0	87.2	semiconsolidated
SD574	Transition_Area_2	576.7	6/13/2010	-21.0	-22.0	53.8	semiconsolidated
SD574	Transition_Area_2	576.7	6/13/2010	-22.0	-23.0	53.2	semiconsolidated
SD574	Transition_Area_2	576.7	6/13/2010	-23.0	-24.0	4.5	semiconsolidated
SD574	Transition_Area_2	576.7	6/13/2010	-24.0	-25.0	2.8	semiconsolidated
SD574	Transition_Area_2	576.7	6/13/2010	-25.0	-26.0	2.4	semiconsolidated
SD574	Transition_Area_2	576.7	6/13/2010	-26.0	-27.0	2.1	semiconsolidated
SD574	Transition_Area_2	576.7	6/13/2010	-27.0	-28.0	2	semiconsolidated
SD574	Transition_Area_2	576.7	6/13/2010	-28.0	-29.0	2.3	semiconsolidated
SD574	Transition_Area_2	576.7	6/13/2010	-29.0	-30.0	3.1	semiconsolidated
SD575	Transition_Area_2	576.5	6/12/2010	-5.0	-6.0	3.7	semiconsolidated
SD575	Transition_Area_2	576.5	6/12/2010	-7.0	-8.0	2.9	semiconsolidated
SD575	Transition_Area_2	576.5	6/12/2010	-8.0	-9.0	3	semiconsolidated
SD575	Transition_Area_2	576.5	6/12/2010	-9.0	-10.0	2.4	semiconsolidated
SD575	Transition_Area_2	576.5	6/12/2010	-11.0	-12.0	2.1	semiconsolidated
SD575	Transition_Area_2	576.5	6/12/2010	-13.0	-14.0	3.1	semiconsolidated
SD575	Transition_Area_2	576.5	6/12/2010	-14.0	-15.0	2.2	semiconsolidated
SD575	Transition_Area_2	576.5	6/12/2010	-15.0	-16.0	2	semiconsolidated
SD575	Transition_Area_2	576.5	6/12/2010	-16.0	-17.0	2.6	semiconsolidated
SD575	Transition_Area_2	576.5	6/12/2010	-17.0	-18.0	2.3	semiconsolidated
SD575	Transition_Area_2	576.5	6/12/2010	-18.0	-19.0	2.8	semiconsolidated
SD575	Transition_Area_2	576.5	6/12/2010	-19.0	-20.0	2.1	semiconsolidated
SD575	Transition_Area_2	576.5	6/12/2010	-20.0	-21.0	2.3	semiconsolidated
SD575	Transition_Area_2	576.5	6/12/2010	-21.0	-22.0	2.1	semiconsolidated
SD575	Transition_Area_2	576.5	6/12/2010	-22.0	-23.0	2.3	semiconsolidated
SD575	Transition_Area_2	576.5	6/12/2010	-23.0	-24.0	2.9	semiconsolidated
SD575	Transition_Area_2	576.5	6/12/2010	-24.0	-25.0	2.9	semiconsolidated
SD575	Transition_Area_2	576.5	6/12/2010	-25.0	-26.0	2.9	semiconsolidated
SD575	Transition_Area_2	576.5	6/12/2010	-26.0	-27.0	2.6	semiconsolidated
SD575	Transition_Area_2	576.5	6/12/2010	-27.0	-28.0	2.9	semiconsolidated

Table B1

## Arsenic Concentration Data with Area and Layer Assignments

*Tyco Fire Products LP*

Sample Location ID	Area Location	Top of Sediment Elevation	Sample Date	Top depth of Sample Interval (ft)	Bottom Depth of Sample Interval (ft)	Arsenic Concentration (mg/kg)	Layer Assignment
SD575	Transition_Area_2	576.5	6/12/2010	-28.0	-29.0	3.1	semiconsolidated
SD575	Transition_Area_2	576.5	6/12/2010	-29.0	-30.0	3.5	semiconsolidated
SD575	Transition_Area_2	576.5	6/12/2010	-30.0	-31.0	2.8	semiconsolidated
SD576	Transition_Area_2	575.3	6/13/2010	-5.0	-6.0	1.5	semiconsolidated
SD576	Transition_Area_2	575.3	6/13/2010	-7.0	-8.0	1.9	semiconsolidated
SD576	Transition_Area_2	575.3	6/13/2010	-9.0	-10.0	3.5	semiconsolidated
SD576	Transition_Area_2	575.3	6/13/2010	-10.0	-11.0	2.3	semiconsolidated
SD576	Transition_Area_2	575.3	6/13/2010	-11.0	-12.0	2.6	semiconsolidated
SD576	Transition_Area_2	575.3	6/13/2010	-13.0	-14.0	2.1	semiconsolidated
SD576	Transition_Area_2	575.3	6/13/2010	-15.0	-16.0	5.6	semiconsolidated
SD576	Transition_Area_2	575.3	6/13/2010	-16.0	-17.0	3.1	semiconsolidated
SD576	Transition_Area_2	575.3	6/13/2010	-17.0	-18.0	1.7	semiconsolidated
SD576	Transition_Area_2	575.3	6/13/2010	-18.0	-19.0	2.2	semiconsolidated
SD576	Transition_Area_2	575.3	6/13/2010	-19.0	-20.0	1.8	semiconsolidated
SD576	Transition_Area_2	575.3	6/13/2010	-21.0	-22.0	2.2	semiconsolidated
SD576	Transition_Area_2	575.3	6/13/2010	-23.0	-24.0	2.9	semiconsolidated
SD576	Transition_Area_2	575.3	6/13/2010	-24.0	-25.0	2.9	semiconsolidated
SD576	Transition_Area_2	575.3	6/13/2010	-25.0	-26.0	2.7	semiconsolidated
SD576	Transition_Area_2	575.3	6/13/2010	-26.0	-27.0	2.5	semiconsolidated
SD576	Transition_Area_2	575.3	6/13/2010	-27.0	-28.0	2.3	semiconsolidated
SD576	Transition_Area_2	575.3	6/13/2010	-29.0	-30.0	2.8	semiconsolidated
SD576	Transition_Area_2	575.3	6/13/2010	-30.0	-31.0	3.5	semiconsolidated
SD560	Transition_Area_2	573.9	6/3/2010	-30.0	-31.0	2.9	till
SD574	Transition_Area_2	576.7	6/13/2010	-30.0	-31.0	3.1	till
SD574	Transition_Area_2	576.7	6/13/2010	-31.0	-32.0	2	till
SD574	Transition_Area_2	576.7	6/13/2010	-32.0	-33.0	2.1	till
SD576	Transition_Area_2	575.3	6/13/2010	-31.0	-32.0	3.3	till
SD576	Transition_Area_2	575.3	6/13/2010	-32.0	-33.0	2.9	till
SD561	Transition_Area_3	572.7	5/25/2010	0.0	-0.5	542	soft sediment
SD561	Transition_Area_3	572.7	5/25/2010	-0.5	-1.0	615	soft sediment
SD561	Transition_Area_3	572.7	5/25/2010	-1.0	-1.5	370	soft sediment
SD561	Transition_Area_3	572.7	5/25/2010	-1.5	-2.0	637	soft sediment

Table B1

## Arsenic Concentration Data with Area and Layer Assignments

*Tyco Fire Products LP*

Sample Location ID	Area Location	Top of Sediment Elevation	Sample Date	Top depth of Sample Interval (ft)	Bottom Depth of Sample Interval (ft)	Arsenic Concentration (mg/kg)	Layer Assignment
SD561	Transition_Area_3	572.7	5/25/2010	-2.0	-2.5	281	soft sediment
SD561	Transition_Area_3	572.7	5/25/2010	-2.5	-3.0	81.7	soft sediment
SD561	Transition_Area_3	572.7	5/25/2010	-3.0	-3.5	61.6	soft sediment
SD561	Transition_Area_3	572.7	5/25/2010	-3.5	-4.0	40.8	soft sediment
SD561	Transition_Area_3	572.7	5/25/2010	-4.0	-4.5	12.8	soft sediment
SD562	Transition_Area_3	575.1	5/22/2010	0.0	-0.5	101	soft sediment
SD562	Transition_Area_3	575.1	5/22/2010	-0.5	-1.0	97.8	soft sediment
SD562	Transition_Area_3	575.1	5/22/2010	-1.0	-1.5	111	soft sediment
SD562	Transition_Area_3	575.1	5/22/2010	-1.5	-2.0	71.9	soft sediment
SD562	Transition_Area_3	575.1	5/22/2010	-2.0	-2.5	9.7	soft sediment
SD562	Transition_Area_3	575.1	5/22/2010	-2.5	-3.0	5.9	soft sediment
SD562	Transition_Area_3	575.1	5/22/2010	-3.0	-3.5	29.8	soft sediment
SD563	Transition_Area_3	575.6	5/22/2010	0.0	-0.5	217	soft sediment
SD563	Transition_Area_3	575.6	5/22/2010	-0.5	-1.0	245	soft sediment
SD563	Transition_Area_3	575.6	5/22/2010	-1.0	-1.5	119	soft sediment
SD563	Transition_Area_3	575.6	5/22/2010	-1.5	-2.0	79.2	soft sediment
SD563	Transition_Area_3	575.6	5/22/2010	-2.0	-2.5	41.2	soft sediment
SD563	Transition_Area_3	575.6	5/22/2010	-2.5	-3.0	3.9	soft sediment
SD563	Transition_Area_3	575.6	5/22/2010	-3.0	-3.5	14.1	soft sediment
SD561	Transition_Area_3	572.7	6/3/2010	-5.0	-6.0	524	semiconsolidated
SD561	Transition_Area_3	572.7	6/3/2010	-7.0	-8.0	261	semiconsolidated
SD561	Transition_Area_3	572.7	6/3/2010	-9.0	-10.0	896	semiconsolidated
SD561	Transition_Area_3	572.7	6/3/2010	-11.0	-12.0	1320	semiconsolidated
SD561	Transition_Area_3	572.7	6/3/2010	-12.0	-13.0	408	semiconsolidated
SD561	Transition_Area_3	572.7	6/3/2010	-13.0	-14.0	143	semiconsolidated
SD561	Transition_Area_3	572.7	6/3/2010	-14.0	-15.0	18.4	semiconsolidated
SD561	Transition_Area_3	572.7	6/3/2010	-15.0	-16.0	64.3	semiconsolidated
SD561	Transition_Area_3	572.7	6/3/2010	-16.0	-17.0	60	semiconsolidated
SD561	Transition_Area_3	572.7	6/3/2010	-17.0	-18.0	4	semiconsolidated
SD561	Transition_Area_3	572.7	6/3/2010	-18.0	-19.0	2.4	semiconsolidated
SD561	Transition_Area_3	572.7	6/3/2010	-19.0	-20.0	38.2	semiconsolidated
SD561	Transition_Area_3	572.7	6/3/2010	-20.0	-21.0	14.2	semiconsolidated

Table B1

## Arsenic Concentration Data with Area and Layer Assignments

*Tyco Fire Products LP*

Sample Location ID	Area Location	Top of Sediment Elevation	Sample Date	Top depth of Sample Interval (ft)	Bottom Depth of Sample Interval (ft)	Arsenic Concentration (mg/kg)	Layer Assignment
SD561	Transition_Area_3	572.7	6/3/2010	-21.0	-22.0	3.2	semiconsolidated
SD561	Transition_Area_3	572.7	6/3/2010	-22.0	-23.0	2.3	semiconsolidated
SD561	Transition_Area_3	572.7	6/3/2010	-23.0	-24.0	3	semiconsolidated
SD561	Transition_Area_3	572.7	6/3/2010	-24.0	-25.0	2.1	semiconsolidated
SD561	Transition_Area_3	572.7	6/3/2010	-25.0	-26.0	2.2	semiconsolidated
SD561	Transition_Area_3	572.7	6/3/2010	-26.0	-27.0	2.4	semiconsolidated
SD561	Transition_Area_3	572.7	6/3/2010	-27.0	-28.0	5.9	semiconsolidated
SD561	Transition_Area_3	572.7	6/3/2010	-28.0	-29.0	2.5	semiconsolidated
SD561	Transition_Area_3	572.7	6/3/2010	-29.0	-30.0	2.6	semiconsolidated
SD561	Transition_Area_3	572.7	6/3/2010	-30.0	-31.0	2.9	semiconsolidated
SD561	Transition_Area_3	572.7	6/3/2010	-31.0	-32.0	2.1	semiconsolidated
SD562	Transition_Area_3	575.1	6/16/2010	-5.0	-6.0	37	semiconsolidated
SD562	Transition_Area_3	575.1	6/16/2010	-7.0	-8.0	23.3	semiconsolidated
SD562	Transition_Area_3	575.1	6/16/2010	-8.0	-9.0	24.1	semiconsolidated
SD562	Transition_Area_3	575.1	6/16/2010	-9.0	-10.0	28.8	semiconsolidated
SD562	Transition_Area_3	575.1	6/16/2010	-11.0	-12.0	65.6	semiconsolidated
SD562	Transition_Area_3	575.1	6/16/2010	-12.0	-13.0	34.6	semiconsolidated
SD562	Transition_Area_3	575.1	6/16/2010	-13.0	-14.0	19.5	semiconsolidated
SD562	Transition_Area_3	575.1	6/16/2010	-14.0	-15.0	24.7	semiconsolidated
SD562	Transition_Area_3	575.1	6/16/2010	-15.0	-16.0	12.5	semiconsolidated
SD562	Transition_Area_3	575.1	6/16/2010	-16.0	-17.0	5.3	semiconsolidated
SD562	Transition_Area_3	575.1	6/16/2010	-17.0	-18.0	4.1	semiconsolidated
SD562	Transition_Area_3	575.1	6/16/2010	-18.0	-19.0	2.2	semiconsolidated
SD562	Transition_Area_3	575.1	6/16/2010	-19.0	-20.0	5.8	semiconsolidated
SD562	Transition_Area_3	575.1	6/16/2010	-20.0	-21.0	2.5	semiconsolidated
SD562	Transition_Area_3	575.1	6/16/2010	-21.0	-22.0	3.4	semiconsolidated
SD562	Transition_Area_3	575.1	6/16/2010	-22.0	-23.0	2.3	semiconsolidated
SD562	Transition_Area_3	575.1	6/16/2010	-25.0	-26.0	2	semiconsolidated
SD562	Transition_Area_3	575.1	6/16/2010	-26.0	-27.0	1.7	semiconsolidated
SD562	Transition_Area_3	575.1	6/16/2010	-27.0	-28.0	1.9	semiconsolidated
SD562	Transition_Area_3	575.1	6/16/2010	-28.0	-29.0	2.1	semiconsolidated
SD562	Transition_Area_3	575.1	6/16/2010	-29.0	-30.0	2.4	semiconsolidated

Table B1

Arsenic Concentration Data with Area and Layer Assignments

*Tyco Fire Products LP*

Sample Location ID	Area Location	Top of Sediment Elevation	Sample Date	Top depth of Sample Interval (ft)	Bottom Depth of Sample Interval (ft)	Arsenic Concentration (mg/kg)	Layer Assignment
SD562	Transition_Area_3	575.1	6/16/2010	-30.0	-31.0	1.9	semiconsolidated
SD563	Transition_Area_3	575.6	6/4/2010	-5.0	-6.0	1.1	semiconsolidated
SD563	Transition_Area_3	575.6	6/4/2010	-6.0	-7.0	1.4	semiconsolidated
SD563	Transition_Area_3	575.6	6/4/2010	-7.0	-8.0	1.2	semiconsolidated
SD563	Transition_Area_3	575.6	6/4/2010	-8.0	-9.0	1.4	semiconsolidated
SD563	Transition_Area_3	575.6	6/4/2010	-9.0	-10.0	1.2	semiconsolidated
SD561	Transition_Area_3	572.7	6/3/2010	-32.0	-33.0	2.7	till
SD562	Transition_Area_3	575.1	6/16/2010	-31.0	-32.0	1.6	till
SD500	Turning_Basin	572.3	5/24/2010	0.0	-1.0	111	soft sediment
SD500	Turning_Basin	572.3	5/25/2010	-1.0	-2.0	9.6	soft sediment
SD500	Turning_Basin	572.3	5/25/2010	-2.0	-2.4	4.5	soft sediment
SD501	Turning_Basin	574.6	5/19/2010	0.0	-1.0	1370	soft sediment
SD501	Turning_Basin	574.6	5/19/2010	-1.0	-2.0	379	soft sediment
SD504	Turning_Basin	557.9	5/19/2010	0.0	-1.0	72	soft sediment
SD504	Turning_Basin	557.9	5/19/2010	-1.0	-2.0	543	soft sediment
SD504	Turning_Basin	557.9	5/19/2010	-2.0	-3.0	740	soft sediment
SD505	Turning_Basin	558.7	5/19/2010	0.0	-1.0	11000	soft sediment
SD505	Turning_Basin	558.7	5/19/2010	-1.0	-2.0	14800	soft sediment
SD505	Turning_Basin	558.7	5/19/2010	-2.0	-3.0	12100	soft sediment
SD506VC	Turning_Basin	576.4	5/18/2010	0.0	-0.5	134	soft sediment
SD509	Turning_Basin	557.1	5/20/2010	0.0	-1.0	3650	soft sediment
SD509	Turning_Basin	557.1	5/20/2010	-1.0	-2.0	6760	soft sediment
SD509	Turning_Basin	557.1	5/20/2010	-2.0	-3.0	11900	soft sediment
SD509	Turning_Basin	557.1	5/20/2010	-3.0	-3.8	12000	soft sediment
SD510	Turning_Basin	562.4	5/23/2010	0.0	-1.0	3000	soft sediment
SD510	Turning_Basin	562.4	5/23/2010	-1.0	-2.0	884	soft sediment
SD510	Turning_Basin	562.4	5/23/2010	-2.0	-2.7	554	soft sediment
SD512	Turning_Basin	557.7	5/19/2010	0.0	-1.0	8640	soft sediment
SD512	Turning_Basin	557.7	5/19/2010	-1.0	-2.0	8090	soft sediment
SD512	Turning_Basin	557.7	5/19/2010	-2.0	-3.0	13000	soft sediment
SD512	Turning_Basin	557.7	5/19/2010	-3.0	-3.8	19600	soft sediment
SD513	Turning_Basin	566.6	5/18/2010	0.0	-0.5	4.2	soft sediment

Table B1

## Arsenic Concentration Data with Area and Layer Assignments

*Tyco Fire Products LP*

Sample Location ID	Area Location	Top of Sediment Elevation	Sample Date	Top depth of Sample Interval (ft)	Bottom Depth of Sample Interval (ft)	Arsenic Concentration (mg/kg)	Layer Assignment
SD515	Turning_Basin	569.9	5/23/2010	0.0	-1.0	6.9	soft sediment
SD515	Turning_Basin	569.9	5/23/2010	-1.0	-2.0	4.6	soft sediment
SD515	Turning_Basin	569.9	5/23/2010	-2.0	-2.4	4.8	soft sediment
SD516	Turning_Basin	576.4	5/23/2010	0.0	-0.5	6.8	soft sediment
SD516	Turning_Basin	576.4	5/23/2010	-0.5	-1.0	5.6	soft sediment
SD516	Turning_Basin	576.4	5/23/2010	-1.0	-1.5	4.3	soft sediment
SD516	Turning_Basin	576.4	5/23/2010	-1.5	-2.0	3.5	soft sediment
SD516	Turning_Basin	576.4	5/23/2010	-2.0	-2.4	5.9	soft sediment
SD518	Turning_Basin	572.1	5/20/2010	0.0	-0.5	11.1	soft sediment
SD518	Turning_Basin	572.1	5/20/2010	-0.5	-1.0	11.1	soft sediment
SD518	Turning_Basin	572.1	5/20/2010	-1.0	-1.5	10.9	soft sediment
SD518	Turning_Basin	572.1	5/20/2010	-1.5	-2.0	14.2	soft sediment
SD518	Turning_Basin	572.1	5/20/2010	-2.0	-2.5	12.6	soft sediment
SD518	Turning_Basin	572.1	5/20/2010	-2.5	-3.0	11.2	soft sediment
SD518	Turning_Basin	572.1	5/20/2010	-3.0	-3.5	8.8	soft sediment
SD519	Turning_Basin	576.6	5/23/2010	0.0	-0.5	8.7	soft sediment
SD519	Turning_Basin	576.6	5/23/2010	-0.5	-1.0	8.5	soft sediment
SD519	Turning_Basin	576.6	5/23/2010	-1.0	-1.5	3.1	soft sediment
SD519	Turning_Basin	576.6	5/23/2010	-1.5	-2.0	2.5	soft sediment
SD519	Turning_Basin	576.6	5/23/2010	-2.0	-2.5	2.3	soft sediment
SD519	Turning_Basin	576.6	5/23/2010	-2.5	-3.0	2.6	soft sediment
SD500	Turning_Basin	572.3	6/7/2010	-3.0	-4.0	367	semiconsolidated
SD500	Turning_Basin	572.3	6/7/2010	-5.0	-6.0	77.1	semiconsolidated
SD500	Turning_Basin	572.3	6/7/2010	-6.0	-7.0	183	semiconsolidated
SD501	Turning_Basin	574.6	6/14/2010	-5.0	-6.0	1550	semiconsolidated
SD501	Turning_Basin	574.6	6/14/2010	-7.0	-8.0	379	semiconsolidated
SD501	Turning_Basin	574.6	6/14/2010	-8.0	-9.0	166	semiconsolidated
SD506HSA	Turning_Basin	572.3	6/6/2010	0.0	-1.0	1710	semiconsolidated
SD506HSA	Turning_Basin	572.3	6/6/2010	-2.0	-3.0	2870	semiconsolidated
SD506HSA	Turning_Basin	572.3	6/6/2010	-4.0	-5.0	189	semiconsolidated
SD506HSA	Turning_Basin	572.3	6/6/2010	-6.0	-7.0	39.8	semiconsolidated
SD506HSA	Turning_Basin	572.3	6/6/2010	-8.0	-9.0	26.2	semiconsolidated

Table B1

## Arsenic Concentration Data with Area and Layer Assignments

*Tyco Fire Products LP*

<b>Sample Location ID</b>	<b>Area Location</b>	<b>Top of Sediment Elevation</b>	<b>Sample Date</b>	<b>Top depth of Sample Interval (ft)</b>	<b>Bottom Depth of Sample Interval (ft)</b>	<b>Arsenic Concentration (mg/kg)</b>	<b>Layer Assignment</b>
SD506HSA	Turning_Basin	572.3	6/6/2010	-9.0	-10.0	37.7	semiconsolidated
SD509	Turning_Basin	557.1	6/6/2010	-4.0	-5.0	525	semiconsolidated
SD509	Turning_Basin	557.1	6/6/2010	-5.0	-6.0	182	semiconsolidated
SD509	Turning_Basin	557.1	6/6/2010	-6.0	-7.0	328	semiconsolidated
SD509	Turning_Basin	557.1	6/6/2010	-7.0	-8.0	39.9	semiconsolidated
SD510	Turning_Basin	562.4	6/2/2010	-5.0	-6.0	520	semiconsolidated
SD510	Turning_Basin	562.4	6/2/2010	-6.0	-7.0	612	semiconsolidated
SD513	Turning_Basin	566.6	6/2/2010	-0.5	-1.5	108	semiconsolidated
SD513	Turning_Basin	566.6	6/2/2010	-1.5	-2.5	82.6	semiconsolidated
SD513	Turning_Basin	566.6	6/2/2010	-2.5	-3.5	103	semiconsolidated
SD513	Turning_Basin	566.6	6/2/2010	-3.5	-4.5	83.7	semiconsolidated
SD513	Turning_Basin	566.6	6/2/2010	-4.5	-5.5	52.6	semiconsolidated
SD513	Turning_Basin	566.6	6/2/2010	-5.5	-6.5	24.4	semiconsolidated
SD513	Turning_Basin	566.6	6/2/2010	-6.5	-7.5	44.7	semiconsolidated
SD513	Turning_Basin	566.6	6/2/2010	-7.5	-8.5	106	semiconsolidated
SD513	Turning_Basin	566.6	6/2/2010	-8.5	-9.5	394	semiconsolidated
SD513	Turning_Basin	566.6	6/2/2010	-9.5	-10.5	787	semiconsolidated
SD513	Turning_Basin	566.6	6/2/2010	-10.5	-11.5	1410	semiconsolidated
SD513	Turning_Basin	566.6	6/2/2010	-11.5	-12.5	993	semiconsolidated
SD513	Turning_Basin	566.6	6/2/2010	-12.5	-13.5	694	semiconsolidated
SD513	Turning_Basin	566.6	6/2/2010	-13.5	-14.5	326	semiconsolidated
SD513	Turning_Basin	566.6	6/2/2010	-14.5	-15.5	349	semiconsolidated
SD513	Turning_Basin	566.6	6/2/2010	-15.5	-16.5	45.1	semiconsolidated
SD515	Turning_Basin	569.9	6/15/2010	-4.0	-5.0	3	semiconsolidated
SD515	Turning_Basin	569.9	6/15/2010	-6.0	-7.0	2.5	semiconsolidated
SD515	Turning_Basin	569.9	6/15/2010	-8.0	-9.0	2.5	semiconsolidated
SD515	Turning_Basin	569.9	6/15/2010	-9.0	-10.0	3.2	semiconsolidated
SD515	Turning_Basin	569.9	6/15/2010	-10.0	-11.0	3.8	semiconsolidated
SD515	Turning_Basin	569.9	6/15/2010	-12.0	-13.0	48.8	semiconsolidated
SD515	Turning_Basin	569.9	6/15/2010	-13.0	-14.0	152	semiconsolidated
SD515	Turning_Basin	569.9	6/15/2010	-14.0	-15.0	262	semiconsolidated
SD515	Turning_Basin	569.9	6/15/2010	-15.0	-16.0	522	semiconsolidated

Table B1

## Arsenic Concentration Data with Area and Layer Assignments

*Tyco Fire Products LP*

Sample Location ID	Area Location	Top of Sediment Elevation	Sample Date	Top depth of Sample Interval (ft)	Bottom Depth of Sample Interval (ft)	Arsenic Concentration (mg/kg)	Layer Assignment
SD515	Turning_Basin	569.9	6/15/2010	-16.0	-17.0	631	semiconsolidated
SD515	Turning_Basin	569.9	6/15/2010	-17.0	-18.0	692	semiconsolidated
SD515	Turning_Basin	569.9	6/15/2010	-18.0	-19.0	332	semiconsolidated
SD516	Turning_Basin	576.4	6/15/2010	-5.0	-6.0	66.5	semiconsolidated
SD516	Turning_Basin	576.4	6/15/2010	-7.0	-8.0	60.3	semiconsolidated
SD516	Turning_Basin	576.4	6/15/2010	-9.0	-10.0	211	semiconsolidated
SD516	Turning_Basin	576.4	6/15/2010	-10.0	-11.0	297	semiconsolidated
SD516	Turning_Basin	576.4	6/15/2010	-11.0	-12.0	251	semiconsolidated
SD516	Turning_Basin	576.4	6/15/2010	-12.0	-13.0	253	semiconsolidated
SD516	Turning_Basin	576.4	6/15/2010	-13.0	-14.0	210	semiconsolidated
SD516	Turning_Basin	576.4	6/15/2010	-14.0	-15.0	247	semiconsolidated
SD516	Turning_Basin	576.4	6/15/2010	-15.0	-16.0	275	semiconsolidated
SD516	Turning_Basin	576.4	6/15/2010	-16.0	-17.0	414	semiconsolidated
SD516	Turning_Basin	576.4	6/15/2010	-17.0	-18.0	490	semiconsolidated
SD516	Turning_Basin	576.4	6/15/2010	-19.0	-20.0	959	semiconsolidated
SD516	Turning_Basin	576.4	6/15/2010	-20.0	-21.0	1310	semiconsolidated
SD516	Turning_Basin	576.4	6/15/2010	-21.0	-22.0	1000	semiconsolidated
SD516	Turning_Basin	576.4	6/15/2010	-23.0	-24.0	751	semiconsolidated
SD516	Turning_Basin	576.4	6/15/2010	-24.0	-25.0	493	semiconsolidated
SD516	Turning_Basin	576.4	6/15/2010	-25.0	-26.0	513	semiconsolidated
SD516	Turning_Basin	576.4	6/15/2010	-26.0	-27.0	217	semiconsolidated
SD516	Turning_Basin	576.4	6/15/2010	-27.0	-28.0	273	semiconsolidated
SD519	Turning_Basin	576.6	6/11/2010	-5.0	-6.0	4.3	semiconsolidated
SD519	Turning_Basin	576.6	6/11/2010	-7.0	-8.0	4.8	semiconsolidated
SD519	Turning_Basin	576.6	6/11/2010	-9.0	-10.0	61.7	semiconsolidated
SD519	Turning_Basin	576.6	6/11/2010	-10.0	-11.0	133	semiconsolidated
SD519	Turning_Basin	576.6	6/11/2010	-11.0	-12.0	44	semiconsolidated
SD519	Turning_Basin	576.6	6/11/2010	-12.0	-13.0	6.9	semiconsolidated
SD519	Turning_Basin	576.6	6/11/2010	-13.0	-14.0	30.9	semiconsolidated
SD519	Turning_Basin	576.6	6/11/2010	-14.0	-15.0	42.5	semiconsolidated
SD519	Turning_Basin	576.6	6/11/2010	-15.0	-16.0	2.3	semiconsolidated
SD519	Turning_Basin	576.6	6/11/2010	-16.0	-17.0	1.7	semiconsolidated

Table B1

## Arsenic Concentration Data with Area and Layer Assignments

*Tyco Fire Products LP*

Sample Location ID	Area Location	Top of Sediment Elevation	Sample Date	Top depth of Sample Interval (ft)	Bottom Depth of Sample Interval (ft)	Arsenic Concentration (mg/kg)	Layer Assignment
SD519	Turning_Basin	576.6	6/11/2010	-17.0	-18.0	2.3	semiconsolidated
SD519	Turning_Basin	576.6	6/11/2010	-18.0	-19.0	1.5	semiconsolidated
SD519	Turning_Basin	576.6	6/11/2010	-19.0	-20.0	2.3	semiconsolidated
SD519	Turning_Basin	576.6	6/11/2010	-20.0	-21.0	1.6	semiconsolidated
SD519	Turning_Basin	576.6	6/11/2010	-21.0	-22.0	6	semiconsolidated
SD519	Turning_Basin	576.6	6/11/2010	-22.0	-23.0	1.9	semiconsolidated
SD519	Turning_Basin	576.6	6/11/2010	-23.0	-24.0	6.3	semiconsolidated
SD519	Turning_Basin	576.6	6/11/2010	-24.0	-25.0	1.8	semiconsolidated
SD519	Turning_Basin	576.6	6/11/2010	-25.0	-26.0	2.5	semiconsolidated
SD519	Turning_Basin	576.6	6/11/2010	-26.0	-27.0	2.4	semiconsolidated
SD519	Turning_Basin	576.6	6/11/2010	-27.0	-28.0	2.6	semiconsolidated
SD519	Turning_Basin	576.6	6/11/2010	-28.0	-29.0	3	semiconsolidated
SD577	Turning_Basin	576.7	6/15/2010	-8.0	-9.0	3.3	semiconsolidated
SD577	Turning_Basin	576.7	6/15/2010	-10.0	-11.0	2.8	semiconsolidated
SD577	Turning_Basin	576.7	6/15/2010	-11.0	-12.0	2	semiconsolidated
SD577	Turning_Basin	576.7	6/15/2010	-12.0	-13.0	2.3	semiconsolidated
SD577	Turning_Basin	576.7	6/15/2010	-14.0	-15.0	2.4	semiconsolidated
SD577	Turning_Basin	576.7	6/15/2010	-15.0	-16.0	2	semiconsolidated
SD577	Turning_Basin	576.7	6/15/2010	-16.0	-17.0	2.2	semiconsolidated
SD577	Turning_Basin	576.7	6/15/2010	-18.0	-19.0	2.5	semiconsolidated
SD577	Turning_Basin	576.7	6/15/2010	-19.0	-20.0	1.8	semiconsolidated
SD577	Turning_Basin	576.7	6/15/2010	-20.0	-21.0	3.3	semiconsolidated
SD577	Turning_Basin	576.7	6/15/2010	-21.0	-22.0	2.2	semiconsolidated
SD500	Turning_Basin	572.3	6/7/2010	-7.0	-8.0	28.2	till
SD500	Turning_Basin	572.3	6/7/2010	-9.0	-10.0	12.5	till
SD501	Turning_Basin	574.6	6/14/2010	-9.0	-10.0	139	till
SD501	Turning_Basin	574.6	6/14/2010	-10.0	-11.0	47	till
SD501	Turning_Basin	574.6	6/14/2010	-11.0	-12.0	55.8	till
SD504	Turning_Basin	557.9	6/11/2010	-5.0	-6.0	2.6	till
SD506HSA	Turning_Basin	572.3	6/6/2010	-10.0	-11.0	160	till
SD509	Turning_Basin	557.1	6/6/2010	-8.0	-9.0	4.1	till
SD510	Turning_Basin	562.4	6/2/2010	-7.5	-10.5	111	till

Table B1

## Arsenic Concentration Data with Area and Layer Assignments

*Tyco Fire Products LP*

<b>Sample Location ID</b>	<b>Area Location</b>	<b>Top of Sediment Elevation</b>	<b>Sample Date</b>	<b>Top depth of Sample Interval (ft)</b>	<b>Bottom Depth of Sample Interval (ft)</b>	<b>Arsenic Concentration (mg/kg)</b>	<b>Layer Assignment</b>
SD512	Turning_Basin	557.7	6/9/2010	-5.0	-6.0	310	till
SD512	Turning_Basin	557.7	6/9/2010	-6.0	-7.0	182	till
SD512	Turning_Basin	557.7	6/9/2010	-7.0	-8.0	144	till
SD513	Turning_Basin	566.6	6/2/2010	-16.5	-17.5	95.7	till
SD513	Turning_Basin	566.6	6/2/2010	-17.5	-18.3	4.6	till
SD515	Turning_Basin	569.9	6/15/2010	-19.0	-20.0	94.6	till
SD515	Turning_Basin	569.9	6/15/2010	-20.0	-21.0	246	till
SD515	Turning_Basin	569.9	6/15/2010	-21.0	-22.0	22.1	till
SD515	Turning_Basin	569.9	6/15/2010	-22.0	-23.0	4.3	till
SD515	Turning_Basin	569.9	6/15/2010	-23.0	-24.0	3.3	till
SD515	Turning_Basin	569.9	6/15/2010	-24.0	-25.0	2.7	till
SD516	Turning_Basin	576.4	6/15/2010	-28.0	-29.0	28.6	till
SD519	Turning_Basin	576.6	6/11/2010	-29.0	-30.0	1.8	till
SD519	Turning_Basin	576.6	6/11/2010	-30.0	-31.0	1.6	till
SD519	Turning_Basin	576.6	6/11/2010	-31.0	-32.0	2	till
SD519	Turning_Basin	576.6	6/11/2010	-32.0	-33.0	2.4	till
SD519	Turning_Basin	576.6	6/11/2010	-33.0	-33.8	3.6	till
SD515	Turning_Basin	569.9	6/15/2010	-25.0	-26.0	3.3	weathered bedrock

TABLE B2

2010 Sediment Laboratory Analytical Data - Arsenic Speciation

*Sediment Removal Work Plan - Tyco Fire Products LP, Marinette, Wisconsin*

Field ID	Interval	Sample Date	Arsenate [mg/kg]	Arsenite [mg/kg]	Dimethylarsenic Acid [mg/kg]	Monomethylarsonic Acid [mg/kg]
SD501001.0	0 - 1	5/19/2010	5,320 J	292	126 U	836
SD501002.0	1 - 2	5/19/2010	160 J	24.7	4.54	238
SD501006.0	5 - 6	6/14/2010	53.6	25.1	2.75 J	22.9
SD501008.0	7 - 8	6/14/2010	167 J	75.7 J	7.39	260 J
SD501009.0	8 - 9	6/14/2010	55.1	42	5.09 J	75.5
SD501010.0	9 - 10	6/14/2010	29.8	1.68 J	1.77 J	51.3
SD501010.0/D	9 - 10	6/14/2010	27.6	1.35 J	1.22 J	48.5
SD501011.0	10 - 11	6/14/2010	11.1	0.36 U	0.73 U	16.9
SD505001.0	0 - 1	5/19/2010	517 J	649	306	2,950
SD505002.0	1 - 2	5/19/2010	293 J	329	383	5,520
SD505003.0	2 - 3	5/19/2010	338 J	259	422	5,410
SD509001.0	0 - 1	5/20/2010	48 J	69.7	142	1,310
SD509001.0/D	0 - 1	5/20/2010	52 J	62.9	111	832
SD509002.0	1 - 2	5/20/2010	162 J	184	252	2,530
SD509002.0/D	1 - 2	5/20/2010	172 J	205	297	2,470
SD509003.0	2 - 3	5/20/2010	368 J	4,460	4,590	5,930
SD509003.0/D	2 - 3	5/20/2010	390 J	323	590	7,640
SD509003.8	3 - 3.8	5/20/2010	254 J	4,190	4,480	7,780
SD509003.8/D	3 - 3.8	5/20/2010	238 J	294	618	7,470
SD509005.0	4 - 5	6/6/2010	14.7	1 J	36.7	311 J
SD509006.0	5 - 6	6/6/2010	11.6	0.136 J	29.8	246
SD509007.0	6 - 7	6/6/2010	16.5	5.52	22.3	263
SD509008.0	7 - 8	6/6/2010	3.16	0.145 J	8.61	54.8
SD509009.0	8 - 9	6/6/2010	33.9	4.8 J	53.3	481
SD517001.0	0 - 1	6/6/2010	0.308	0.013 J	0.0037 U	0.113
SD517003.0	2 - 3	6/6/2010	0.351	0.0208 J	0.0098 J	0.157
SD517004.0	3 - 4	6/6/2010	0.195	0.006 J	0.0043 J	0.0392
SD517005.0	4 - 5	6/6/2010	0.386	0.0063 J	0.004 U	0.011 U
SD517006.0	5 - 6	6/6/2010	0.408	0.0045 J	0.004 U	0.011 U
SD517007.0	6 - 7	6/6/2010	0.34	0.005 J	0.005 J	0.102
SD517008.0	7 - 8	6/6/2010	0.441	0.0087 J	0.004 U	0.012 U
SD517009.0	8 - 9	6/6/2010	0.354	0.0032 J	0.004 U	0.016 J
SD517009.0/D	8 - 9	6/6/2010	0.376	0.0051 J	0.004 U	0.033
SD517010.0	9 - 10	6/6/2010	0.52	0.0052 J	0.004 U	0.018 J
SD517011.0	10 - 11	6/6/2010	0.501	0.0123 J	0.004 U	0.02 J
SD517011.0/D	10 - 11	6/6/2010	0.461	0.0086 J	0.004 U	0.012 U
SD517012.0	11 - 12	6/6/2010	0.569	0.0123 J	0.0047 J	0.033
SD517013.0	12 - 13	6/6/2010	0.453	0.012 J	0.004 U	0.013 J
SD517014.0	13 - 14	6/6/2010	0.202	0.0048 J	0.003 U	0.011 U
SD521000.5	0 - 0.5	5/20/2010	8 J	8.45	0.17 U	0.36
SD521001.0	0.5 - 1	5/20/2010	6.3 J	1.3 J	0.0328 J	0.389 J
SD521001.5	1 - 1.5	5/20/2010	4.11 J	0.732	0.0063 J	0.125
SD521002.0	1.5 - 2	5/20/2010	1.73 J	0.825	0.134	0.025 J
SD521002.5	2 - 2.5	5/20/2010	2.73 J	0.603	0.048 U	0.045

TABLE B2

2010 Sediment Laboratory Analytical Data - Arsenic Speciation

*Sediment Removal Work Plan - Tyco Fire Products LP, Marinette, Wisconsin*

Field ID	Interval	Sample Date	Arsenate [mg/kg]	Arsenite [mg/kg]	Dimethylarsenic Acid [mg/kg]	Monomethylarsonic Acid [mg/kg]
SD521003.0	2.5 - 3	5/20/2010	3.13 J	0.28	0.054 U	0.035 J
SD521003.5	3 - 3.5	5/20/2010	4.61 J	1.05	0.083 U	0.032 J
SD526000.5	0 - 0.5	5/25/2010	12.2	1.25	0.034 J	0.064 J
SD526000.5/D	0 - 0.5	5/25/2010	8.4	1.72	0.052 J	0.059 J
SD526001.0	0.5 - 1	5/25/2010	13.3 J	0.211 J	0.038 J	0.145
SD526001.0/D	0.5 - 1	5/25/2010	22.8 J	0.531 J	0.06	0.281
SD526001.5	1 - 1.5	5/25/2010	2.08	0.0375	0.0183 J	0.0309 J
SD526001.5/D	1 - 1.5	5/25/2010	2.23	0.0495	0.019 J	0.0319 J
SD526002.0	1.5 - 2	5/25/2010	2.02	0.234	0.019 J	0.0122 J
SD526002.0/D	1.5 - 2	5/25/2010	1.82	0.129	0.023 J	0.0113 J
SD526002.5	2 - 2.5	5/25/2010	2.89	0.3 J	0.021 J	0.0167 J
SD526002.5/D	2 - 2.5	5/25/2010	4.63	0.61 J	0.03 J	0.0146 J
SD526003.0	2.5 - 3	5/25/2010	7.97 J	1.96	0.12 U	0.12 U
SD526003.0/D	2.5 - 3	5/25/2010	2.93 J	2.82	0.18 U	0.18 U
SD536000.5	0 - 0.5	5/22/2010	68.3 J	3.26 J	0.62 UJ	0.915 J
SD536001.0	0.5 - 1	5/22/2010	8.4	0.652	0.0068 J	0.191
SD536001.5	1 - 1.5	5/22/2010	10.2	1.29	0.0054 J	0.626
SD536002.0	1.5 - 2	5/22/2010	16.7	3.53	0.0166 J	0.808
SD536002.5	2 - 2.5	5/22/2010	11.4	1.38	0.0164 J	1.09
SD536003.0	2.5 - 3	5/22/2010	10.7	1.65	0.0125 J	1.15
SD536003.5	3 - 3.5	5/22/2010	14.8	1.96	0.0129 J	1.33
SD536004.5	3.5 - 4.5	5/22/2010	6.69	0.847	0.0118 J	0.542
SD536005.0	4.5 - 5	5/22/2010	2.73	0.369	0.0075 J	0.128
SD536005.5	5 - 5.5	5/22/2010	1.89	0.226	0.0073 J	0.023 J
SD536006.0	5.5 - 6	5/22/2010	2.3	0.329	0.0116 J	0.0411
SD536006.5	6 - 6.5	5/22/2010	3.67	0.405	0.0122 J	0.0346
SD536007.0	6.5 - 7	5/22/2010	5.37	0.219	0.0107 J	0.0441
SD536007.5	7 - 7.5	5/22/2010	3.21	0.136	0.0094 J	0.0339
SD536008.0	7.5 - 8	5/22/2010	2.57	0.504	0.0158 J	0.0262 J

## Qualifier Notes:

J = The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.

U = The analyte was analyzed for but was not detected above the reported sample quantitation limit. Value was detected in the blank sample.

UJ = The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.

TABLE B3

2010 Sediment Laboratory Analytical Data - Elutriate\* Analytes

*Sediment Removal Work Plan - Tyco Fire Products LP, Marinette, Wisconsin*

Field ID	Interval	Sample Date	Arsenic [ug/L]	Dissolved Arsenic [ug/L]	Dissolved Iron [ug/L]	Ammonia as N [mg/L]	Total Suspended Solids [mg/L]	Material Sampled
EW001		5/23/2010	7.4	5.6	21.6 J	0.05 U	4	river water
SD557001.6C	0 - 1.6	5/21/2010	8.1	5.6	36.4	0.89	7.1	soft sediment
SD503000.5C	0 - 0.5	5/23/2010	32.7	12.2	99.4	4	31	soft sediment
SD510002.7C	0 - 2.7	5/23/2010	82,000 J	68,400	5,960	1.1	54	soft sediment
SD511000.5C	0 - 0.5	5/23/2010	47.6	17	87	1.9	14	soft sediment
SD528003.2C	0 - 3.2	5/23/2010	17.1 J	28.2 J	395	1.9	20	soft sediment
SD520003.0C	0 - 3	5/24/2010	11	6.1	45.4	2.1	7.7	soft sediment
EW002		6/15/2010	2.7	1.9	27.5 J	0.16 U	8.8	river water
SD510011.0C	5 - 11	6/15/2010	4,880	4,780	29 U	0.43	2.9	semi-consol
SD514007.0C	3 - 7	6/15/2010	44,400	40,600	593	0.63	2.9	semi-consol
SD515018.0C	4 - 18	6/15/2010	9,450 J	9,710 J	29 U	0.47	2.9	semi-consol
SD516023.0C	3 - 23	6/15/2010	47,500	45,600	361	0.56	10	semi-consol

## Notes:

\*Elutriate samples were processed using a 4 to 1 ratio (by volume) of river water with a bulk sediment sample sent to laboratory for processing

J = The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.

U = The analyte was analyzed for but was not detected above the reported sample quantitation limit. Value was detected in the blank sample.

TABLE B4

2010 Sediment Laboratory Analytical Data - Wisconsin NR347 Analytes

Sediment Removal Work Plan - Tyco Fire Products LP, Marinette, Wisconsin

Sample ID		SD500002.4C	SD501001.0C	SD501002.0C	SD501009.0C	SD504003.2C	SD504003.2C/D	SD511000.5C	SD512003.8C	SD512007.0C	SD517014.0C	SD517014.0C/D	SD520003.0C	SD521003.5C	SD522004.4C	SD529002.3C	SD534002.9C
Interval		0 - 2.4	0 - 1.2	1.2 - 2.2	5 - 9	0 - 3.2	0 - 3.2	0 - 0.5	0 - 3.8	5 - 7	0 - 14	0 - 14	0 - 3	0 - 3.5	0 - 4.4	0 - 2.3	0 - 2.9
Sample Date		5/25/2010	5/19/2010	5/19/2010	6/14/2010	5/19/2010	5/19/2010	5/23/2010	5/19/2010	6/9/2010	6/6/2010	6/6/2010	5/24/2010	5/20/2010	5/24/2010	5/25/2010	5/22/2010
TOTAL SOLIDS	PERCENT	82.6			80.7	34.8	35.9	39.8	37.2	94.4 J	87.1	84.7		56.4	51.5	76.8	30.9
MOISTURE, PERCENT	PERCENT	25	28	14.1	21	66	65.3	61.3	62.8	6	14.5	13.6	30.2	29.8	43.1	16.1	69.2
RESIDUE, TOTAL	PERCENT	82.6			80.7	34.8	35.9	39.8	37.2	94.4 J	87.1	84.7		56.4	51.5	76.8	30.9
Metals																	
ARSENIC	MG/KG		3,120	110	424			35.7			2.6	2.5	13.7	10.5	7		3.2
BARIUM	MG/KG		12.1	10	8.2			53.1			29.4	26.3	17.1	16.6	35.5		12.1
CADMIUM	MG/KG		6.3	0.28 J	0.13 J			0.74 J			0.13 UB	0.11 UB	0.22 J	0.22 UJ	0.24 J		0.051 J
CHROMIUM, TOTAL	MG/KG		11.8	6.5	6.6			18.4			12.1	11.1	12.3	9.6	19.9		9.3
COPPER	MG/KG		15	6.2	5.2			23.7			8.7	8.4	9.7	13.5	24.4		4.8
IRON	MG/KG		4,830	6,480	8,470			14,800			10,400	9,500	8,870	8,820	15,600		6,540
LEAD	MG/KG		30.2 J	2.3 J	4.9			22.3			3.7	3.5	9.8	8.6	16.4		1.9
MANGANESE	MG/KG		28.4	219	290 J			840 J			238	230	233 J	200	352 J		120
NICKEL	MG/KG		48.8	5.4	5			9.7			7	6.6	6.2	5.9	10.5		7.1
SELENIUM	MG/KG		0.86 J	0.18 U	0.19 U			0.41 U			0.19 U	0.19 U	0.21 U	0.22 U	0.51 J		0.18 U
ZINC	MG/KG		14.4	7.7	18.1			82.1			11.5	10.8	45	38.9	51.5		18.4
MERCURY	MG/KG		0.023	0.0028 J	0.035			0.23			0.0041 J	0.0039 J	0.18	0.078	0.17		0.011 J
CYANIDE	MG/KG		0.3 UJ	0.24 UJ	0.36 U			0.66 U			0.31 UJ	0.22 UJ	0.24 U	0.45 U	0.39 U		0.27 U
Pesticides																	
2,4'-DDD	UG/KG		16.4 U	0.69 U	0.75 UJ			1.5 J			0.69 U	0.68 U	0.85 U	0.84 U	1 U		0.7 U
2,4'-DDE	UG/KG		16.5 U	0.69 U	0.75 UJ			1.5 U			0.69 U	0.69 U	0.98 J	0.84 U	1.8 J		0.71 U
2,4'-DDT	UG/KG		16 U	0.67 U	0.73 UJ			1.5 U			0.67 U	0.67 U	1 J	0.82 U	1 U		0.69 U
ALDRIN	UG/KG		12.5 UJ	0.52 UJ	0.57 UJ			1.2 U			0.52 U	0.52 U	0.64 U	0.64 U	0.79 U		0.53 U
CHLORDANE	UG/KG		353 U	14.8 U	16.1 UJ			32.8 U			14.9 U	14.7 U	18.2 U	18.1 U	22.3 U		15.1 U
DIELDRIN	UG/KG		32.8 U	1.4 U	1.5 UJ			3 U			1.4 U	1.4 U	1.7 U	1.7 U	2.1 U		1.4 U
ENDRIN	UG/KG		26.9 U	1.1 U	1.2 UJ			2.5 U			1.1 U	1.1 U	1.4 U	1.4 U	1.7 U		1.2 U
GAMMA BHC (LINDANE)	UG/KG		13 U	0.54 U	0.59 UJ			1.2 U			0.55 U	0.54 U	0.67 U	0.67 U	0.82 U		0.56 U
HEPTACHLOR	UG/KG		14.8 U	0.62 U	0.67 UJ			1.4 U			0.62 U	0.61 U	0.76 U	0.76 U	0.93 U		0.63 U
p,p'-DDD	UG/KG		42 U	1.8 U	1.9 UJ			3.9 U			1.8 U	1.7 U	2.2 U	2.2 U	2.7 U		1.8 U
p,p'-DDE	UG/KG		27.5 U	1.2 U	1.3 UJ			2.6 U			1.2 UJ	1.1 UJ	1.4 U	1.4 U	1.7 U		1.2 UJ
p,p'-DDT	UG/KG		42.5 U	1.8 U	1.9 UJ			3.9 U			1.8 U	1.8 U	2.2 U	2.2 U	2.7 U		1.8 U
TOXAPHENE	UG/KG		626 U	26.2 U	28.5 UJ			58.2 U			26.3 U	26.1 U	32.3 U	32.1 U	39.6 U		29 J
Wet Chemistry																	
OIL & GREASE, TOTAL REC	MG/KG		368	128 J	92.1 U			620 J			73 U	73 U	573	135 J	128 U		86.6 U
NITROGEN, NITRATE (AS N)	MG/KG		5.7	2.3 J	3.9 J			5.2 U			2.3 J	2.3 U	2.9 U	2.8 U	3.5 U		2.4 U
NITROGEN, NITRITE	MG/KG		1.7 J	1.2 U	1.3 U			2.6 U			1.2 U	1.2 U	1.4 U	1.4 U	1.8 U		1.2 U
NITROGEN, AMMONIA (AS N)	MG/KG		6 U	6.6 J	16.6			181			6.1 J	5.8 J	58.2	127	175		77.5
NITROGEN, KJELDAHL, TOTAL	MG/KG		1,210 J	68.5 UJ	190			3,710			48.3 J	51.3 J	979	682 J	2,050		1,040
PHOSPHORUS	MG/KG		154	248	164			893			290	223	271	266	398		176
TOC REPLICATE 1	MG/KG		282,000	1,340	8,730			38,800			824	933	31,600	15,900	37,100		38,700
TOC REPLICATE 2	MG/KG		183,000	761	13,100			48,200			917	840	12,700	14,300	70,000		43,100
TOC REPLICATE 3	MG/KG		320,000	892	4,720			36,100			870	879	17,300	12,500	59,300		24,400
TOC REPLICATE 4	MG/KG		165,000	1,210	9,970			51,000			917	844	12,400	19,500	45,100		44,900
TOC AVERAGE	MG/KG		238,000 J	1,050 J	9,140 J			43,600			882	874	18,500	15,600 J	52,900		37,800
TOC RSD%	PERCENT		31.7	25.6	38			16.5			5.1	4.9	48.7	19	27.7		24.6

J = The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.

U = The analyte was analyzed for but was not detected above the reported sample quantitation limit. Value was detected in the blank sample.

UB = The analyte was reported as not detected at an elevated detection limit due to blank contamination.

UJ = The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.

TABLE B4

2010 Sediment Laboratory Analytical Data - Wisconsin I

Sediment Removal Work Plan - Tyco Fire Products LP,

Sample ID	SD537006.8C	SD537006.8C/D	SD541001.7C	SD541003.2C	SD552004.0C	SD562003.6C	SD566000.5C	SD573002.0C	SD577010.0C	SD577020.0C
Interval	0 - 6.8	0 - 6.8	0 - 1.7	1.7 - 3.2	0 - 4	0 - 3.6	0 - 0.5	0 - 2.1	8 - 10	10 - 20
Sample Date	5/24/2010	5/24/2010	5/25/2010	5/25/2010	6/14/2010	5/22/2010	5/20/2010	5/26/2010	6/15/2010	6/15/2010
TOTAL SOLIDS	23.1	18.4	51.3	76.7	85.6	34.6	47.8	65.1	86.1	77.6
MOISTURE, PERCENT	76.6	81.5	52.8	20.1	14.7	67	51.6	33.3	16.7	21
RESIDUE, TOTAL	23.1	18.4	51.3	76.7	85.6	34.6	47.8	65.1	86.1	77.6
Metals										
ARSENIC	138	121	24.3	3.3	4				3.5	2 J
BARIUM	134	121	43.6	8.1	10.8				8.3	10.2
CADMIUM	2.5	2.5	0.67 J	0.03 U	0.11 J				0.035 UB	0.1 UB
CHROMIUM, TOTAL	33.4	29.2	20.1	5.7	5.5				8.3	6.1
COPPER	72.9	65	26.8	3.7	3.4				4.8	5.1
IRON	20,000	17,500	14,800	8,380	7,910				8,640	6,900
LEAD	141	122	32	1.1 J	2.5				1.2	2.4
MANGANESE	475 J	407 J	290	141	189 J				147	213
NICKEL	16.7	13.7	10.8	3.6	5.5				5.6	4.1
SELENIUM	1.4 J	0.61 J	0.34 U	0.19 U	0.22 J				0.4 UB	0.31 UB
ZINC	399	361	100	19.4	23.6				16	6.8
MERCURY	1.8	1.4	0.53	0.0022 U	0.025				0.0021 U	0.0022 U
CYANIDE	0.99 J	0.85 U	0.42 U	0.22 U	0.24 U				0.19 U	0.24 U
Pesticides										
2,4'-DDD	7.7	2.3 U	1.3 U	0.74 U	0.69 U				0.71 U	0.75 U
2,4'-DDE	9.9 J	6.7 J	1.3 U	0.74 U	0.69 U				0.71 U	0.75 U
2,4'-DDT	2.6 U	2.3 U	1.2 U	0.72 U	0.67 U				0.69 U	0.73 U
ALDRIN	2 U	1.8 U	0.95 U	0.56 U	0.52 U				0.54 U	0.57 U
CHLORDANE	151	85.5 J	26.9 U	15.9 U	14.9 U				15.3 U	16.1 U
DIELDRIN	5.2 U	4.7 U	2.5 U	1.5 U	1.4 U				1.4 U	1.5 U
ENDRIN	4.3 U	3.8 U	2.1 U	1.2 U	1.1 U				1.2 U	1.2 U
GAMMA BHC (LINDANE)	2.1 U	1.9 U	0.99 U	0.59 U	0.55 U				0.56 U	0.59 U
HEPTACHLOR	2.4 U	2.1 U	1.1 U	0.66 U	0.62 U				0.64 U	0.67 U
p,p'-DDD	7.7 J	6 U	3.2 U	1.9 U	1.8 U				1.8 U	1.9 U
p,p'-DDE	24.2	8 J	2.1 UJ	1.2 UJ	1.2 U				1.2 U	1.3 U
p,p'-DDT	10.1 J	6.1 U	3.2 U	1.9 U	1.8 U				1.8 U	1.9 U
TOXAPHENE	302 J	256 J	54.6 J	28.2 U	26.4 U				27.1 U	28.5 U
Wet Chemistry										
OIL & GREASE, TOTAL REC	2,220	1,590	154 U	90.7 U	84.9 U				87.1 U	91.7 U
NITROGEN, NITRATE (AS N)	8.9 U	7.9 U	4.2 J	2.5 U	2.3 U				2.4 U	2.7 J
NITROGEN, NITRITE	5.3 J	4 U	2.1 U	1.3 U	1.2 U				1.2 U	1.3 U
NITROGEN, AMMONIA (AS N)	817	695	95.9	5.6 J	8 J				7 J	7.3 U
NITROGEN, KJELDAHL, TOTAL	9,670	76.2 UB	2,690	68.1	151				32.5 J	25.7 J
PHOSPHORUS	3,240	351	695	112	134				114	217
TOC REPLICATE 1	175,000	186,000	48,000	428	2,610				219 J	337
TOC REPLICATE 2	192,000	191,000	94,200	610	3,780				216 J	354
TOC REPLICATE 3	139,000	188,000	58,300	356	3,010				175 J	363
TOC REPLICATE 4	235,000	195,000	42,300	529	3,670				236 J	329
TOC AVERAGE	185,000	190,000	60,700	481	3,270 J				212 J	346
TOC RSD%	21.4	2	38.4	23.2	16.9				12.2	4.5

J = The analyte was positively identified; the associated numerical value is the approximate concentration of the analyte in the sample.

U = The analyte was analyzed for but was not detected above the reported sample quantitation limit. Value was detected in the blank sample.

UB = The analyte was reported as not detected at an elevated detection limit due to blank contamination.

UJ = The analyte was not detected above the reported sample quantitation limit. However, the reported quantitation limit is approximate and may or may not represent the actual limit of quantitation necessary to accurately and precisely measure the analyte in the sample.

Table B5  
 2010 Sediment Geotechnical Data  
 Sediment Removal Work Plan - Tyco Fire Products LP, Marinette, Wisconsin

Date Sampled	Sample Number	Depth (ft)	Layer Assignment	Grain Size Analysis		Sampled Water	Sampled Water	Atterberg Limits			U.S.C.S.	Specific Gravity	Dry Density (pcf)	Water Content (%)
				%Fines <#200	%Clay <.005	Content % Wet Basis	Content % Dry Basis	Liquid Limit	Plastic Limit	Plasticity Index				
6/14/10	SD552007.0C	5.0'-7.0'	mixed									137.9	5.9	
6/16/10	SD562032.0C	0.0'-32.0'	mixed	61.0	4.5	15.3	18.0			NP	ML	2.782		
6/7/10	SD500004.0	3.0'-4.0'	semiconsolidated			34.2	52.1							
6/7/10	SD500006.0	5.0'-6.0'	semiconsolidated			20.3	25.4							
6/7/10	SD500006.0/D	5.0'-6.0'	semiconsolidated			29.3	41.5							
6/7/10	SD500007.0	6.0'-7.0'	semiconsolidated			19.1	23.6							
6/7/10	SD500007.0C	3.0'-7.0'	semiconsolidated	69.5	6.0	16.1	19.1	16.3	11.5	4.8	SC-SM	2.852	130.5	7.7
6/6/10	SD517002.0	1.0'-2.0'	semiconsolidated			16.1	19.2							
6/6/10	SD517003.0	2.0'-3.0'	semiconsolidated			11.9	13.5							
6/6/10	SD517004.0	3.0'-4.0'	semiconsolidated			15.6	18.4							
6/6/10	SD517005.0	4.0'-5.0'	semiconsolidated			14.6	17.1							
6/6/10	SD517006.0	5.0'-6.0'	semiconsolidated			14.5	17.0							
6/6/10	SD517007.0	6.0'-7.0'	semiconsolidated			16.1	19.2							
6/6/10	SD517008.0	7.0'-8.0'	semiconsolidated			16.3	19.5							
6/6/10	SD517009.0	8.0'-9.0'	semiconsolidated			15.6	18.5							
6/6/10	SD517010.0	9.0'-10.0'	semiconsolidated			15.9	18.9							
6/6/10	SD517010.0C	0.0'-10.0'	semiconsolidated	80.2	26.0	14.6	17.2			NP	ML	2.740		
6/6/10	SD517012.0C	10.0'-12.0'	semiconsolidated									113.4	15.8	
6/14/10	SD552004.0C	0.0'-4.0'	semiconsolidated	5.4	0.0	20.0	24.9			NP	SP-SM	2.727		
6/14/10	SD552006.0	5.0'-6.0'	semiconsolidated			9.1	10.1							
6/16/10	SD562006.0	5.0'-6.0'	semiconsolidated			16.0	19.0							
6/16/10	SD562006.0/D	5.0'-6.0'	semiconsolidated			16.0	19.0							
6/16/10	SD562008.0	7.0'-8.0'	semiconsolidated			16.3	19.4							
6/16/10	SD562009.0	8.0'-9.0'	semiconsolidated			17.6	21.3							
6/16/10	SD562010.0	9.0'-10.0'	semiconsolidated			15.7	18.7							
6/16/10	SD562012.0	11.0'-12.0'	semiconsolidated			16.1	19.1							
6/16/10	SD562013.0	12.0'-13.0'	semiconsolidated			14.1	16.4							
6/16/10	SD562013.0C	11.0'-13.0'	semiconsolidated									107.4	17.7	
6/16/10	SD562014.0	13.0'-14.0'	semiconsolidated			11.2	12.6							
6/16/10	SD562015.0	14.0'-15.0'	semiconsolidated			12.8	14.7							
6/16/10	SD562016.0	15.0'-16.0'	semiconsolidated			14.8	17.4							
6/16/10	SD562016.0/D	15.0'-16.0'	semiconsolidated			14.8	17.4							
6/16/10	SD562017.0	16.0'-17.0'	semiconsolidated			14.8	17.3							
6/16/10	SD562018.0	17.0'-18.0'	semiconsolidated			12.8	14.7							
6/16/10	SD562019.0	18.0'-19.0'	semiconsolidated			14.6	17.0							
6/16/10	SD562020.0	19.0'-20.0'	semiconsolidated			12.1	13.8							
6/16/10	SD562021.0	20.0'-21.0'	semiconsolidated			16.7	20.0							
6/16/10	SD562022.0	21.0'-22.0'	semiconsolidated			14.7	17.2							
6/16/10	SD562023.0	22.0'-23.0'	semiconsolidated			13.7	15.9							
6/16/10	SD562026.0	25.0'-26.0'	semiconsolidated			15.3	18.1							
6/16/10	SD562027.0	26.0'-27.0'	semiconsolidated			18.4	22.5							
6/16/10	SD562028.0	27.0'-28.0'	semiconsolidated			14.3	16.7							
6/16/10	SD562029.0	28.0'-29.0'	semiconsolidated			12.7	14.6							
6/16/10	SD562030.0	29.0'-30.0'	semiconsolidated			17.2	20.8							
6/16/10	SD562031.0	30.0'-31.0'	semiconsolidated			15.6	18.5							
6/10/10	SD566001.0	0.0'-1.0'	semiconsolidated			21.6	27.5							

Table B5  
 2010 Sediment Geotechnical Data  
 Sediment Removal Work Plan - Tyco Fire Products LP, Marinette, Wisconsin

Date Sampled	Sample Number	Depth (ft)	Layer Assignment	Grain Size Analysis		Sampled Water	Sampled Water	Atterberg Limits			U.S.C.S.	Specific Gravity	Dry Density (pcf)	Water Content (%)
				%Fines <#200	%Clay <.005	Content % Wet Basis	Content % Dry Basis	Liquid Limit	Plastic Limit	Plasticity Index				
6/10/10	SD566002.0	1.0'-2.0'	semiconsolidated			9.8	10.9							
6/10/10	SD566002.0C	0.0'-2.0'	semiconsolidated									126.5	9.3	
6/10/10	SD566003.0	2.0'-3.0'	semiconsolidated			10.3	11.4							
6/10/10	SD566004.0	3.0'-4.0'	semiconsolidated			9.6	10.6							
6/10/10	SD566004.0C	0.0'-4.0'	semiconsolidated	41.3	16.5	12.0	13.6	16.3	10.8	5.5	SC-SM	2.757		
6/10/10	SD566005.0	4.0'-5.0'	semiconsolidated			9.2	10.2							
6/10/10	SD566006.0	5.0'-6.0'	semiconsolidated			7.8	8.5							
6/10/10	SD566006.0C	5.0'-6.0'	semiconsolidated									122.1	9.7	
6/12/10	SD575006.0	5.0'-6.0'	semiconsolidated			17.6	21.3							
6/12/10	SD575008.0	7.0'-8.0'	semiconsolidated			17.9	21.8							
6/12/10	SD575009.0	8.0'-9.0'	semiconsolidated			16.9	20.3							
6/12/10	SD575009.0/D	8.0'-9.0'	semiconsolidated			17.5	21.1							
6/12/10	SD575009.0C	7.0'-9.0'	semiconsolidated									102.4	18.8	
6/12/10	SD575010.0	9.0'-10.0'	semiconsolidated			17.8	21.6							
6/12/10	SD575012.0	11.0'-12.0'	semiconsolidated			16.6	19.9							
6/12/10	SD575012.0/D	11.0'-12.0'	semiconsolidated			16.2	19.3							
6/12/10	SD575014.0	13.0'-14.0'	semiconsolidated			14.3	16.7							
6/12/10	SD575014.0C	5.0'-14.0'	semiconsolidated	2.5	0.0	14.8	17.3			NP	SP	2.768		
6/12/10	SD575015.0	14.0'-15.0'	semiconsolidated			16.8	20.3							
6/12/10	SD575016.0	15.0'-16.0'	semiconsolidated			18.1	22.1							
6/12/10	SD575017.0	16.0'-17.0'	semiconsolidated			17.5	21.2							
6/12/10	SD575018.0	17.0'-18.0'	semiconsolidated			15.4	18.3							
6/12/10	SD575019.0	18.0'-19.0'	semiconsolidated			16.3	19.5							
6/12/10	SD575019.0C	17.0'-19.0'	semiconsolidated									103.4	17.9	
6/12/10	SD575020.0	19.0'-20.0'	semiconsolidated			15.4	18.2							
6/12/10	SD575021.0	20.0'-21.0'	semiconsolidated			15.4	18.1							
6/12/10	SD575022.0	21.0'-22.0'	semiconsolidated			15.2	17.9							
6/12/10	SD575023.0	22.0'-23.0'	semiconsolidated			14.8	17.3							
6/12/10	SD575024.0	23.0'-24.0'	semiconsolidated			17.6	21.3							
6/12/10	SD575024.0/D	23.0'-24.0'	semiconsolidated			18.2	22.2							
6/12/10	SD575025.0	24.0'-25.0'	semiconsolidated			16.0	19.1							
6/12/10	SD575026.0	25.0'-26.0'	semiconsolidated			16.7	20.1							
6/12/10	SD575027.0	26.0'-27.0'	semiconsolidated			14.9	17.4							
6/12/10	SD575028.0	27.0'-28.0'	semiconsolidated			18.6	22.8							
6/12/10	SD575029.0	28.0'-29.0'	semiconsolidated			20.4	25.7							
6/12/10	SD575029.0C	27.0'-29.0'	semiconsolidated									103.6	17.3	
6/12/10	SD575030.0	29.0'-30.0'	semiconsolidated			21.2	27.0							
6/12/10	SD575031.0	30.0'-31.0'	semiconsolidated			17.0	20.5							
6/12/10	SD575031.0C	14.0'-31.0'	semiconsolidated	72.6	17.5	15.7	18.7	17.2	13.6	3.6	ML	2.753		
6/15/10	SD577009.0	8.0'-9.0'	semiconsolidated			14.4	16.9							
6/15/10	SD577010.0C	8.0'-10.0'	semiconsolidated	5.2	0.0	12.5	14.3			NP	SP-SM	2.788		
6/15/10	SD577013.0	12.0'-13.0'	semiconsolidated			19.5	24.2							
6/15/10	SD577013.0/D	12.0'-13.0'	semiconsolidated			17.3	21.0							
6/15/10	SD577015.0	14.0'-15.0'	semiconsolidated			14.5	17.0							
6/15/10	SD577016.0	15.0'-16.0'	semiconsolidated			16.2	19.3							
6/15/10	SD577017.0	16.0'-17.0'	semiconsolidated			15.9	18.9							
6/15/10	SD577019.0	18.0'-19.0'	semiconsolidated			16.1	19.2							

Table B5  
2010 Sediment Geotechnical Data  
Sediment Removal Work Plan - Tyco Fire Products LP, Marinette, Wisconsin

Date Sampled	Sample Number	Depth (ft)	Layer Assignment	Grain Size Analysis		Sampled Water	Sampled Water	Atterberg Limits			U.S.C.S.	Specific Gravity	Dry Density (pcf)	Water Content (%)
				%Fines <#200	%Clay <.005	Content % Wet Basis	Content % Dry Basis	Liquid Limit	Plastic Limit	Plasticity Index				
6/15/10	SD577020.0	19.0'-20.0'	semiconsolidated			18.3	22.3							
6/15/10	SD577020.0C	10.0'-20.0'	semiconsolidated	61.7	5.0	18.9	23.3			NP	ML	2.773		
6/15/10	SD577020.0C	18.0'-20.0'	semiconsolidated										105.3	18.0
6/15/10	SD577021.0	20.0'-21.0'	semiconsolidated			10.6	11.9							
6/15/10	SD577022.0	21.0'-22.0'	semiconsolidated			16.5	19.7							
5/25/10	SD500002.4C	0.0'-2.4'	Soft Sediment	8.7	0.0	25.7	34.6	26.9	24.2	2.7	SP-SM	2.671	82.8	37.8
5/19/10	SD501001.0C	0.0'-1.0'	Soft Sediment	1.2	0.0	35.3	54.5				GW			
5/19/10	SD501002.0C	1.0'-2.0'	Soft Sediment	39.8	0.0	14.0	16.3				SM			
5/23/10	SD503000.5C	0.0'-0.5'	Soft Sediment			60.0	150.0							
5/19/10	SD504003.2C	0.0'-3.2'	Soft Sediment	34.5	6.5	65.6	190.5	130.1	61.0	69.1	SM	2.395	27.2	182.8
5/19/10	SD504003.2C/D	0.0'-3.2'	Soft Sediment	46.4	8.0	63.7	175.7	137.2	61.0	76.2	SM	2.451	30.8	151.3
5/23/10	SD511000.5C	0.0'-0.5'	Soft Sediment	32.1	6.0	62.0	163.4	102.9	49.1	53.8	SM	2.643		
5/19/10	SD512003.8C	0.0'-3.8'	Soft Sediment	37.0	15.5	63.0	170.2	134.7	59.4	75.3	SC	2.521	37.3	106.6
6/6/10	SD517001.0	0.0'-1.0'	Soft Sediment			15.4	18.3							
5/24/10	SD520003.0C	0.0'-3.0'	Soft Sediment			38.4	62.3							
5/20/10	SD521003.5C	0.0'-3.5'	Soft Sediment	14.5	0.0	26.9	36.8			NP	SM	2.632	39.0	112.4
5/24/10	SD522004.4C	0.0'-4.4'	Soft Sediment	30.2	6.5	40.9	69.1	69.9	44.2	25.7	SM	2.551	58.8	62.2
5/25/10	SD529002.3C	0.0'-2.3'	Soft Sediment	3.2	0.0	16.0	19.0				SP			
5/22/10	SD534002.9C	0.0'-2.9'	Soft Sediment	14.3	2.5	39.2	64.4			NP	SM	2.623	106.2	20.0
5/24/10	SD537006.8C	0.0'-6.8'	Soft Sediment	17.2	2.0	79.9	398.0	265.5	76.6	188.9	SM	2.353	13.0	392.7
5/24/10	SD537006.8C/D	0.0'-6.8'	Soft Sediment	29.5	2.0	78.7	369.8	289.8	89.5	200.3	SM	2.347	10.1	533.0
5/25/10	SD541001.7C	0.0'-1.7'	Soft Sediment	35.4	9.0	53.9	116.8	101.5	52.1	49.4	SM	2.454	36.8	130.4
5/25/10	SD541003.2C	1.7'-3.2'	Soft Sediment	1.4	0.0	15.2	17.9			NP	SP	2.719	105.6	19.5
5/26/10	SD546001.6C	0.0'-1.6'	Soft Sediment			68.6	218.6							
6/14/10	SD552001.0	0.0'-1.0'	Soft Sediment			16.5	19.7							
6/14/10	SD552001.0/D	0.0'-1.0'	Soft Sediment			12.8	14.7							
5/22/10	SD562003.6C	0.0'-3.6'	Soft Sediment	38.0	8.0	67.3	206.3	162.5	72.8	89.7	SM	2.376	20.7	250.0
5/20/10	SD566000.5C	0.0'-0.5'	Soft Sediment	13.4	4.0	51.3	105.4	65.8	42.7	23.1	SM	2.674		
5/26/10	SD573002.0C	0.0'-2.0'	Soft Sediment	5.9	1.0	34.7	53.2	40.5	33.4	7.1	SP-SM	2.608	40.2	112.9
6/7/10	SD500010.0	9.0'-10.0'	till			8.5	9.3							
6/7/10	SD500011.0C	9.0'-11.0'	till										130.5	8.1
6/11/10	SD504006.0C	5.0'-6.0'	till										137.3	6.7
6/9/10	SD512007.0C	5.0'-7.0'	till	50.4	22.0	7.2	7.8	16.5	9.6	6.9	CL-ML	2.775		
6/9/10	SD512008.4C	7.0'-8.4'	till										126.1	8.3
6/16/10	SD562032.0	31.0'-32.0'	till			11.3	12.7							
6/16/10	SD562032.0C	30.0'-32.0'	till										115.0	16.3

**Appendix C**  
**Sediment Removal Preliminary Design**  
**Drawings**

---


# TYCO FIRE PRODUCTS LP MENOMINEE RIVER SEDIMENT REMOVAL DESIGN



MARINETTE, WISCONSIN  
OCTOBER 2010



AERIAL VIEW



PROJECT LOCATION

## INDEX OF DRAWINGS

SHEET NO.	DWG NO.	DESCRIPTION
-----------	---------	-------------

### GENERAL

1	G-1	COVER, PROJECT LOCATION, AND INDEX OF DRAWINGS
2	G-2	ABBREVIATIONS
3	G-3	CIVIL LEGENDS AND DESIGNATION LEGENDS

### INSTRUMENTATION AND CONTROL

4	N-1	CONCEPTUAL TEMPORARY WATER TREATMENT SYSTEM PROCESS FLOW DIAGRAM
---	-----	---

### CIVIL

5	C-1	OVERALL SITE PLAN
6	C-2	DREDGING PLAN
7	C-3	WATER QUALITY MONITORING PLAN
8	C-4	ACCESS ROADWAYS, STAGING AND OFFLOADING AREA CONCEPTUAL PLAN AND SECTION


PREPARED FOR  
TYCO FIRE PRODUCTS LP  
ONE STANTON STREET  
MARINETTE, WI 54143-2542

**CH2MHILL**











**NOTES:**

1. SURVEY CONTROL AND BENCH MARK DATA IS AVAILABLE FROM THE DETROIT DISTRICT ENGINEERING & TECHNICAL SERVICES, OPERATIONS TECHNICAL SUPPORT BRANCH, KEWAUNEE AREA OFFICE.
2. THE COORDINATE GRID SYSTEM SHOWN IS REFERENCED TO THE WISCONSIN STATE PLANE COORDINATE SYSTEM, LAMBERT PROJECTION, CENTRAL ZONE (4802), NORTH AMERICAN DATUM 1983 (NAD83), US FOOT.
3. ALL SOUNDINGS ARE IN FEET AND ARE REFERENCED TO LOW WATER DATUM ELEVATION, 577.5 FEET ABOVE MEAN WATER LEVEL AT RIMOUSKI, QUEBEC (INTERNATIONAL GREAT LAKES DATUM 1985).




<b>CH2MHILL</b> CIVIL <b>OVERALL SITE PLAN</b>		TYCO FIRE PRODUCTS LP		BY APVD	
		MENOMINEE RIVER		CHK	
SEDIMENT REMOVAL DESIGN		NO. DATE		APVD	
MARINETTE, WISCONSIN		DR		CJ DAHL	
REUSE OF DOCUMENTS: THIS DOCUMENT AND THE IDEAS AND DESIGNS INCORPORATED HEREIN AS AN INSTRUMENT OF PROFESSIONAL SERVICE IS THE PROPERTY OF CH2MHILL AND IS NOT TO BE USED, IN WHOLE OR IN PART, FOR ANY OTHER PROJECT WITHOUT THE WRITTEN AUTHORIZATION OF CH2MHILL.					
DATE: OCTOBER 2010 PROJ: 405439 DWG: C-1 SHEET: 5					

© CH2MHILL 2009. ALL RIGHTS RESERVED.  
 S. RAMAMURTHY  
 PRELIMINARY




**NOTES:**

1. SURVEY CONTROL AND BENCH MARK DATA IS AVAILABLE FROM THE DETROIT DISTRICT ENGINEERING & TECHNICAL SERVICES, OPERATIONS TECHNICAL SUPPORT BRANCH, KEWAUNEE AREA OFFICE.
2. THE COORDINATE GRID SYSTEM SHOWN IS REFERENCED TO THE WISCONSIN STATE PLANE COORDINATE SYSTEM, LAMBERT PROJECTION, CENTRAL ZONE (4802), NORTH AMERICAN DATUM 1983 (NAD83), US FOOT.
3. ALL SOUNDINGS ARE IN FEET AND ARE REFERENCED TO LOW WATER DATUM ELEVATION, 577.5 FEET ABOVE MEAN WATER LEVEL AT RIMOUSKI, QUEBEC (INTERNATIONAL GREAT LAKES DATUM 1985).




<b>CH2MHILL</b> CIVIL <b>DREDGING PLAN</b>		TYCO FIRE PRODUCTS LP		BY APVD	
		MENOMINEE RIVER		CHK	
SEDIMENT REMOVAL DESIGN		NO. DATE		DR	
MARINETTE, WISCONSIN		DGSN		CJ DAHL	
REUSE OF DOCUMENTS: THIS DOCUMENT AND THE IDEAS AND DESIGNS INCORPORATED HEREIN AS AN INSTRUMENT OF PROFESSIONAL SERVICE IS THE PROPERTY OF CH2MHILL AND IS NOT TO BE USED, IN WHOLE OR IN PART, FOR ANY OTHER PROJECT WITHOUT THE WRITTEN AUTHORIZATION OF CH2MHILL. © CH2MHILL 2009. ALL RIGHTS RESERVED.					
1"=150' VERIFY SCALE BAR IS ONE INCH ON ORIGINAL DRAWING.		DATE OCTOBER 2010 PROJ 405439 DWG C-2 SHEET 6			





**NOTES:**

1. SURVEY CONTROL AND BENCH MARK DATA IS AVAILABLE FROM THE DETROIT DISTRICT ENGINEERING & TECHNICAL SERVICES, OPERATIONS TECHNICAL SUPPORT BRANCH, KEWAUNEE AREA OFFICE.
2. THE COORDINATE GRID SYSTEM SHOWN IS REFERENCED TO THE WISCONSIN STATE PLANE COORDINATE SYSTEM, LAMBERT PROJECTION, CENTRAL ZONE (4802), NORTH AMERICAN DATUM 1983 (NAD83), US FOOT.
3. ALL SOUNDINGS ARE IN FEET AND ARE REFERENCED TO LOW WATER DATUM ELEVATION, 57.5 FEET ABOVE MEAN WATER LEVEL AT RIMOUSKI, QUEBEC (INTERNATIONAL GREAT LAKES DATUM 1985).



<b>CH2MHILL</b> CIVIL <b>WATER QUALITY MONITORING PLAN</b>		TYCO FIRE PRODUCTS LP		BY APVD	
		MENOMINEE RIVER		CHK	
SEDIMENT REMOVAL DESIGN		MARINETTE, WISCONSIN		APVD	
DATE: OCTOBER 2010 PROJ: 405439 DWG: C-3 SHEET: 7		NO. DATE DSGN		REVISION DR	
1"=150' VERIFY SCALE BAR IS ONE INCH ON ORIGINAL DRAWING.		S. RAMAMURTHY C. DAHLGREN DR			

REUSE OF DOCUMENTS: THIS DOCUMENT AND THE IDEAS AND DESIGNS INCORPORATED HEREIN AS AN INSTRUMENT OF PROFESSIONAL SERVICE IS THE PROPERTY OF CH2MHILL AND IS NOT TO BE USED, IN WHOLE OR IN PART, FOR ANY OTHER PROJECT WITHOUT THE WRITTEN AUTHORIZATION OF CH2MHILL. © CH2MHILL 2009. ALL RIGHTS RESERVED.



- NOTES:**
1. SURVEY CONTROL AND BENCH MARK DATA IS AVAILABLE FROM THE DETROIT DISTRICT, ENGINEERING & TECHNICAL SERVICES, OPERATIONS TECHNICAL SUPPORT BRANCH, KEWAUNEE AREA OFFICE.
  2. THE COORDINATE GRID SYSTEM SHOWN IS REFERENCED TO THE WISCONSIN STATE PLANE COORDINATE SYSTEM, LAMBERT PROJECTION, CENTRAL ZONE (4802), NORTH AMERICAN DATUM 1983 (NAD83), US FOOT.
  3. ALL SOUNDINGS ARE IN FEET AND ARE REFERENCED TO LOW WATER DATUM ELEVATION, 577.5 FEET ABOVE MEAN WATER LEVEL AT RIMOUSKI, QUEBEC (INTERNATIONAL GREAT LAKES DATUM 1985).


<b>CH2MHILL</b> CIVIL <b>ACCESS ROADWAYS, STAGING AND OFF-LOADING AREA AND SECTION</b>		TYCO FIRE PRODUCTS LP MENOMINEE RIVER SEDIMENT REMOVAL DESIGN MARINETTE, WISCONSIN	
		VERIFY VERIFY SCALE BAR IS ONE INCH ON ORIGINAL DRAWING.	DATE: OCTOBER 2010 PROJ: 405439 DWG: C-4 SHEET: 8
REVISION NO. DATE DSGN	DR C.J. DAHL	REVISION CHK APVD	BY APVD

© CH2M HILL 2009. ALL RIGHTS RESERVED.  
 THIS DOCUMENT AND THE IDEAS AND DESIGNS INCORPORATED HEREIN AS AN INSTRUMENT OF PROFESSIONAL SERVICE IS THE PROPERTY OF CH2M HILL AND IS NOT TO BE USED, IN WHOLE OR IN PART, FOR ANY OTHER PROJECT WITHOUT THE WRITTEN AUTHORIZATION OF CH2M HILL.

**Appendix D**  
**Project Schedule**

---

ID	Task Name	Duration	Start	Finish	Predecessors	2011		2012				2013				2014	
						Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2
1	Submittal of SRWP, AMRSRP, & Schedule	0 days	Wed 12/1/10	Wed 12/1/10			12/1										
2	Development of Design Plans & Specs	90 days	Tue 5/24/11	Tue 9/27/11	3SF												
3	Prepare Bid Package	10 days	Tue 9/27/11	Tue 10/11/11	4SF												
4	<b>Procurement</b>	<b>45 days</b>	<b>Tue 10/11/11</b>	<b>Mon 12/12/11</b>													
5	Dredger	45 days	Tue 10/11/11	Mon 12/12/11													
6	Landside Operation Subcontractor	45 days	Tue 10/11/11	Mon 12/12/11													
7	<b>Long Lead Items</b>	<b>76 days</b>	<b>Wed 1/4/12</b>	<b>Wed 4/18/12</b>													
8	Evaporator	76 days	Wed 1/4/12	Wed 4/18/12													
9	<b>Prepare Plans and Fact Sheets</b>	<b>124 days</b>	<b>Fri 10/14/11</b>	<b>Thu 4/5/12</b>													
10	Project Manual	60 days	Tue 12/13/11	Mon 3/5/12	5,6												
11	Confirmation Sampling Plan	60 days	Fri 10/14/11	Fri 1/6/12	20SF-64 days												
12	Construction Quality Assurance Plan	60 days	Tue 12/13/11	Mon 3/5/12	5,6												
13	O & M Plan	60 days	Tue 12/13/11	Mon 3/5/12	5,6												
14	H&S Plan	60 days	Tue 12/13/11	Mon 3/5/12	5,6												
15	QA/QC Plan	60 days	Tue 12/13/11	Mon 3/5/12	5,6												
16	<b>Fact Sheet</b>	<b>20 days</b>	<b>Thu 3/8/12</b>	<b>Thu 4/5/12</b>													
17	Distributed to USEPA	10 days	Thu 3/8/12	Thu 3/22/12	18SF												
18	Distributed to Public	10 days	Thu 3/22/12	Thu 4/5/12	20SF												
19	Pre-construction Inspection Meeting	0 days	Tue 3/27/12	Tue 3/27/12	20SF-7 days												
20	<b>Mobilization</b>	<b>29 days</b>	<b>Thu 4/5/12</b>	<b>Tue 5/15/12</b>													
21	Set up Solidification Pad	10 days	Thu 4/5/12	Wed 4/18/12													
24	Mobilize WWT System	16 days	Thu 4/19/12	Thu 5/10/12	10,14,15												
29	Mobilize Solidification Equipment	9 days	Thu 5/3/12	Tue 5/15/12													
35	Place Bin Blocks	5 days	Wed 5/9/12	Tue 5/15/12	33FF												
36	Mobilize Dredge	19 days	Thu 4/19/12	Tue 5/15/12													
41	<b>Dredging Tasks</b>	<b>288 days</b>	<b>Tue 5/15/12</b>	<b>Thu 6/20/13</b>													
42	Dredge Soft Sediment	33 days	Tue 5/15/12	Thu 6/28/12													
43	Dredge Semi Consolidated Sands/Silts - Part 1	80 days	Fri 6/29/12	Thu 10/18/12	42												
44	Dredge Semi Consolidated Sands/Silts - Part 2	27 days	Wed 5/15/13	Thu 6/20/13													
45	<b>Pre-final Constr. Inspection (at 80% compl.)</b>	<b>23 days</b>	<b>Fri 5/10/13</b>	<b>Tue 6/11/13</b>													
46	Notification of USEPA (30 days prior)	0 days	Fri 5/10/13	Fri 5/10/13	47SF-23 days												
47	Pre-final Inspection	0 days	Tue 6/11/13	Tue 6/11/13	44FF-7 days												
48	<b>Interim Demobilization</b>	<b>136 days</b>	<b>Fri 10/19/12</b>	<b>Fri 4/26/13</b>													
51	<b>South Channel Dredging</b>	<b>33 days</b>	<b>Fri 6/21/13</b>	<b>Tue 8/6/13</b>													
52	Install Sheet Pile	7 days	Fri 6/21/13	Mon 7/1/13	44												
53	Pump Free Water	5 days	Tue 7/2/13	Mon 7/8/13	52												
54	In-situ Stabilization	14 days	Tue 7/9/13	Fri 7/26/13	53												
55	Remove Sheet Pile	7 days	Mon 7/29/13	Tue 8/6/13	54												
56	<b>Final Construction Inspection (at completion)</b>	<b>23 days</b>	<b>Thu 7/11/13</b>	<b>Tue 8/13/13</b>													
57	Notification of USEPA (30 days prior)	0 days	Thu 7/11/13	Thu 7/11/13	58SF-23 days												
58	Final Construction Inspection	0 days	Tue 8/13/13	Tue 8/13/13	67SF-2 days												
59	<b>Demobilization</b>	<b>49 days</b>	<b>Fri 6/21/13</b>	<b>Wed 8/28/13</b>													
71	<b>Transportation and Disposal</b>	<b>314 days</b>	<b>Tue 5/15/12</b>	<b>Fri 7/26/13</b>													
83	<b>Water Treatment</b>	<b>331 days</b>	<b>Tue 5/15/12</b>	<b>Tue 8/20/13</b>													
92	<b>Project Oversight</b>	<b>365 days</b>	<b>Thu 4/5/12</b>	<b>Wed 8/28/13</b>													
95	<b>Project Management</b>	<b>799 days</b>	<b>Thu 10/7/10</b>	<b>Tue 10/29/13</b>													



Project: Tyco SRWP Approach  
Date: Tue 11/30/10

Task Progress Summary External Tasks Deadline   
Split Milestone Project Summary External Milestone

ID	Task Name	Duration	Start	Finish	Predecessors	2011				2012				2013				2014		
						Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1	Qtr 2	Qtr 3	Qtr 4	Qtr 1
98	Final Report	60 days	Wed 8/7/13	Tue 10/29/13	55															
99	AOC Deadline for Sediment Removal Completion	0 days	Fri 11/1/13	Fri 11/1/13																
100	AOC Deadline for Sediment Construction Report	0 days	Sat 3/1/14	Sat 3/1/14																
101	<b>MNR Plan</b>	<b>60 days</b>	<b>Wed 2/20/13</b>	<b>Wed 5/15/13</b>																
102	Development of MNR Plan	60 days	Wed 2/20/13	Wed 5/15/13	103FF															
103	Submittal of MNR Plan	0 days	Wed 5/15/13	Wed 5/15/13	58SF-64 days															



Project: Tyco SRWP Approach  
Date: Tue 11/30/10

Task		Progress		Summary		External Tasks		Deadline	
Split		Milestone		Project Summary		External Milestone			

**Appendix E**  
**Compensation Schedule**

---

**TYCO SRWP Approach Compensation Schedule**  
**Tyco Fire Products, LP**  
**Marinette, Wisconsin**

Item	Task	Estimated Quantity	Unit	Unit Price	Extended Total
<b>A</b>	<b>Lump Sum Items</b>				
A.1	Insurance Premiums	1	LS	\$	\$
A.2	Performance and Payment Bonds	1	LS	\$	\$
A.3	Mobilization	1	LS	\$	\$
A.4	Infrastructure Construction	1	LS	\$	\$
A.5	Site Maintenance (includes pumping wastewater to water treatment system)	1	LS	\$	\$
A.6	Surveys	1	LS	\$	\$
A.7	Site Restoration	1	LS	\$	\$
A.8	Demobilization	1	LS	\$	\$
A.9	Subcontract Closeout	1	LS	\$	\$
A.10	Interim Demobilization	1	LS	\$	\$
<b>B</b>	<b>Unit Price Items</b>				
B.1	Mechanical Dredging of Soft Sediment	59,300	CY	\$	\$
B.2	Mechanical Dredging of Semi-consolidated Sands and Silts	149,000	CY	\$	\$
B.3	Dry Excavation of Soft Sediment in South Channel	12,000	CY	\$	\$
B.4	Supply Fluidized Bed Boiler Ash Reagent	11,243	TON	\$	\$
B.5	Supply Portland Cement Reagent	0	TON	\$	\$
B.6	Supply Sodium Polyacrylate (SAP) Reagent	0	TON	\$	\$
B.7	Supply 60% Ferric Sulfate Solution Reagent	0	TON	\$	\$
B.8	Supply Calcium Hypochlorite Reagent	0	TON	\$	\$
B.9	Mix Reagents, stockpile on pad (staged for 7 days)	220,300	CY	\$	\$
B.10	Load Stabilized Materials into Trucks, Transport and Dispose at RCRA Subtitle D Landfill	385,056	TON	\$	\$
B.11	Load Stabilized Materials into Trucks, Transport and Dispose at RCRA Subtitle C Landfill	0	TON	\$	\$
B.12	Water Treatment	12,143,943	GAL	\$	\$
B.13	Debris Removal and RCRA Subtitle D Disposal	169	TON	\$	\$
B.14	Mechanical Dredge Standby Time	50	HR	\$	\$
				<b>Total:</b>	<b>\$</b>

**Appendix F**  
**Cost Estimate**

---

**TYCO SRWP Approach Cost Estimate 2010-11-30**  
**Tyco Fire Products, LP**  
**Marinette, Wisconsin**

Item	Task	Estimated Quantity	Unit	Unit Price	Extended Total
<b>A</b>	<b>Lump Sum Items</b>				
A.1	Insurance Premiums	1	LS	\$ 496,326.78	\$ 496,327
A.2	Performance and Payment Bonds	1	LS	\$ 496,326.78	\$ 496,327
A.3	Mobilization	1	LS	\$ 517,427.13	\$ 517,427
A.4	Infrastructure Construction	1	LS	\$ 283,433.84	\$ 283,434
A.5	Site Maintenance (includes pumping wastewater to water treatment system)	1	LS	\$ 40,000.00	\$ 40,000
A.6	Surveys	1	LS	\$ 122,645.60	\$ 122,646
A.7	Site Restoration	1	LS	\$ 50,000.00	\$ 50,000
A.8	Demobilization	1	LS	\$ 363,191.25	\$ 363,191
A.9	Subcontract Closeout	1	LS	\$ 11,000.00	\$ 11,000
A.10	Interim Demobilization	1	LS	\$ 745,483.63	\$ 745,484
<b>B</b>	<b>Unit Price Items</b>				
B.1	Mechanical Dredging of Soft Sediment	59,300	CY	\$ 24.36	\$ 1,444,475
B.2	Mechanical Dredging of Semi-consolidated Sands and Silts	149,000	CY	\$ 28.84	\$ 4,297,266
B.3	Dry Excavation of Soft Sediment in South Channel	12,000	CY	\$ 19.82	\$ 237,875
B.4	Supply Fluidized Bed Boiler Ash Reagent	11,243	TON	\$ 60.50	\$ 680,208
B.5	Supply Portland Cement Reagent	0	TON	\$ -	\$ -
B.6	Supply Sodium Polyacrylate (SAP) Reagent	0	TON	\$ -	\$ -
B.7	Supply 60% Ferric Sulfate Solution Reagent	0	TON	\$ -	\$ -
B.8	Supply Calcium Hypochlorite Reagent	0	TON	\$ -	\$ -
B.9	Mix Reagents, stockpile on pad (staged for 7 days)	220,300	CY	\$ 13.07	\$ 2,880,035
B.10	Load Stabilized Materials into Trucks, Transport and Dispose at RCRA Subtitle D Landfill	385,056	TON	\$ 33.31	\$ 12,827,747
B.11	Load Stabilized Materials into Trucks, Transport and Dispose at RCRA Subtitle C Landfill	0	TON	\$ -	\$ -
B.12	Water Treatment	12,143,943	GAL	\$ 0.45	\$ 5,499,192
B.13	Debris Removal and RCRA Subtitle D Disposal	169	TON	\$ 121.62	\$ 20,608
B.14	Mechanical Dredge Standby Time	50	HR	\$ 1,196.48	\$ 59,824
				<b>Total:</b>	<b>\$ 31,073,064</b>

Total Contingency (Included in Estimate Range)

\$ -

**TOTAL WITH CONTINGENCY**

**\$ 31,073,064**

Project Management

0% \$ -

Remedial Design

2% \$ 621,461

Construction Management

7% \$ 2,175,114

**Total Estimated COST**

**\$ 33,869,640**

Estimate Range

Top estimate range +50%

50% \$ 50,804,460

Bottom estimate range -30%

-30% \$ 23,708,748

*This estimate is offered as an opinion of cost to perform the work and is not an offer to contract for construction services, procure and/or provide such services*