

Note: This is a reference cited in *AP 42, Compilation of Air Pollutant Emission Factors, Volume I Stationary Point and Area Sources*. AP42 is located on the EPA web site at [www.epa.gov/ttn/chief/ap42/](http://www.epa.gov/ttn/chief/ap42/)


The file name refers to the reference number, the AP42 chapter and section. The file name "ref02\_c01s02.pdf" would mean the reference is from AP42 chapter 1 section 2. The reference may be from a previous version of the section and no longer cited. The primary source should always be checked.

**AP-42 Section Number:** 1.8

**Reference Number:** 43

**Title:** Osceola Farms Company Compliance  
Particulate Emissions Test Report  
Boiler #2

February 1991



*Eastmount Engineering*

*Environmental Consultants — Air Quality Specialists*

Ref-30

OSW OFC-1

**OSCEOLA FARMS COMPANY  
COMPLIANCE PARTICULATE EMISSIONS TEST REPORT  
BOILER #2**

**PREPARED FOR:**

Osceola Farms Company  
316 Royal Poinciana Plaza  
Palm Beach, Florida 33480

**CONCERNING:**

Particulate Emissions Testing  
Osceola Farms Company  
Boiler #2  
Pahokee, Florida Facility  
February 7, 1991

**PREPARED BY:**

S. Joseph Mercadante  
President  
Eastmount Engineering, Inc.  
420 Main Street  
Walpole, MA 02081

S. Joseph Mercadante  
President

Date

## TABLE OF CONTENTS

- 1.0 COMPENDIUM
- 2.0 STACK SCHEMATIC
- 3.0 TRAVERSE POINT LOCATION & SAMPLING TIME PER POINT
- 4.0 SAMPLING TRAIN AND ANALYTICAL TEST PROCEDURES
- 5.0 QUALITY CONTROL PROCEDURES

## APPENDIX

- I COMPUTER INPUT SHEETS
- II ISOKINETIC CALCULATION SHEETS
- III ENTHALPY CALCULATION SHEETS
- IV HEAT INPUT CALCULATION SHEETS
- V EMISSION CALCULATION SHEETS
- VI NOMENCLATURE SHEETS
- VII FIELD DATA SHEETS - UNIT OPERATING CONDITIONS
- VIII FIELD DATA SHEETS - STACK TESTING
- IX EQUIPMENT CALIBRATION SHEETS

Osceola Farms - Boiler #2  
Particulate Emissions Test Report

1.0 COMPENDIUM

Eastmount Engineering Inc., conducted a Compliance Particulate Emissions Test Program on Unit #2 at Osceola Farms Pahokee, Florida facility on February 7, 1991. The test program consisted of a series of three EPA Method 5 test runs.

All testing was conducted in strict accordance with the Environmental Protection Agency Reference Methods 1 through 5 as found in the Federal Register (40 CFR 60) as amended and were consistent with the State of Florida Department of Environmental Regulation's guidelines.

The purpose of this test was to determine compliance with the rules of the Department of Environmental Regulation (DER), Chapter 17-2.600 Air Pollution, Section 2.05 Prohibitive Acts, Subsection 6, Stationary Sources, Table II, Emission Limiting Standards.

During testing the boiler was burning bagasse as fuel. Boiler No. 2 is rated at 140,000 pounds of steam per hour. Results of the test program indicate Boiler No. 2 to be in compliance with the Florida DER emission standard. The following table summarizes the emission results, emission standards and boiler operating conditions.

RUN#	DATE	EMISSION RATE		ALLOWABLE		LOAD #/HR	% OF 140 KPH
		#/MMBtu	#/HR	#MMBtu	#/HR		
1	02-07-91	.200	55.35	.200	55.20	139,520	99.7%
2	02-07-91	.188	51.32	.200	54.70	138,240	98.7%
3	02-07-91	.198	55.14	.200	55.70	140,800	100.6%
3 RUN AVG.		.195	53.94	.200	55.22	139,520	99.7%

S. Joseph Mercadante, President, was in charge of and responsible for all stack testing, conducted all calculations and performed the Orsat analysis. Ray Valdez operated the meter box and maintained chain of custody of all samples. Brian Gibson performed the field laboratory aspects of the program and Jim Jardin located the probe at the proper traverse point locations and assisted where required. Mr. Kenneth Tucker of the Florida Department of Environmental Regulation observed the stack testing and boiler operations. Mr. P. Farinas was the boiler room superintendent responsible for boiler operation and acquisition of all pertinent process data.


Osceola Farms - Boiler #2  
Particulate Emissions Test Report

**2.0 STACK SCHEMATIC**

OSCEOLA FARMS COMPANY  
UNIT # 2  
PAHOKEE, FLORIDA FACILITY

The following is a schematic of the stack which services Boiler #2 at Osceola Farms Pahokee, Florida facility.

Defined are the sampling port locations, interior stack dimensions and distances from the ports to the nearest upstream and downstream interferences.




NUMBER OF STACKS	2
DISTANCE UPSTREAM FROM FLOW DISTURBANCE (A)	17'
DISTANCE DOWNSTREAM FROM FLOW DISTURBANCE (B)	26'
DIAMETER OF PORT SLEEVE (C)	3"
LENGTH OF PORT SLEEVE (D)	3"
NUMBER OF PORTS	2
INTERNAL DIAMETER OF STACK AT SAMPLING PORTS	60"

Drawing not to scale

Osceola Farms - Boiler #2  
Particulate Emissions Test Report

3.0 NUMBER OF TRAVERSE POINTS AND SAMPLING TIME PER POINT

OSCEOLA FARMS COMPANY  
UNIT # 2  
PAHOKEE, FLORIDA FACILITY



Minimum number of traverse points for particulate traverses.

Distance A = 17' or 3.4 diameters.

Distance B = 26' or 5.2 diameters.

In accordance with Method 1, 20 traverse points were needed for each stack for a total of 40 traverse points.

In order to sample for a minimum of one hour and draw at least 30 cubic feet, each traverse point was sampled for 1.5 minutes.

Osceola Farms - Boiler #2  
Particulate Emissions Test Report

3.0 NUMBER OF TRAVERSE POINTS AND SAMPLING TIME PER POINT

OSCEOLA FARMS COMPANY  
UNIT # 2  
PAHOKEE, FLORIDA FACILITY

DIAMETER OF STACK: NORTH 5.0 FEET  
DIAMETER OF STACK: SOUTH 5.0 FEET  
PORT SLEEVE LENGTH: 3 INCHES

TRAVERSE POINT	DISTANCE % OF DIAMETER	DISTANCE (INCHES)	PROBE MARK (INCHES)
1	2.6	1.6	4.6
2	8.2	4.9	7.9
3	14.6	8.8	11.8
4	22.6	13.6	16.6
5	34.2	20.5	23.5
6	65.8	39.5	42.5
7	77.4	46.4	49.4
8	85.4	51.2	54.2
9	91.8	55.1	58.1
10	97.4	58.4	61.4

Osceola Farms - Boiler #2  
Particulate Emissions Test Report

4.0 SAMPLING TRAIN AND ANALYTICAL TEST PROCEDURES

The following is a description of the sampling train and specifications of particulate collection media used in the tests.

1. EMISSION SAMPLING EQUIPMENT

The specific train used during this test is one manufactured by Research Appliance Company (RAC). The design specifications of this train meets all the requirements of Environmental Protection Agency's Method 5 as found in the Federal Regulations under Section 40 CFR 60 as amended. The following is a description of the individual pieces of equipment used:

Nozzle - The nozzle was of seamless stainless steel tubing construction of the button hook design. A range of sizes suitable for isokinetic sampling was available. All nozzles were calibrated before testing. A nozzle calibration sheet may be found in the calibration section of this report.

Probe - An 10 foot steel probe with a stainless steel liner was used.

Heating System - The filter temperature was maintained by enclosing the filter in a hot box capable of maintaining the temperature at 248 °F ±25 °F. This temperature was monitored by use of a thermocouple in the hot box.

Pitot Tube - A type S pitot tube attached to the probe was used to monitor the stack gas velocity. Since the pitot tube meets all the dimensional criteria set forth in Method 2 of 40 CFR 60, a coefficient of 0.84 has been used.

Filter Holder - A borosilicate glass type filter holder with frit support was used.

Condenser - Four impingers connected in series, with ground glass leak-free fittings were used as the condenser. The first, third and fourth impingers were of the Greenburg-Smith design, modified by replacing the tip with a 1/2" glass tube extending to about 1/2" from the bottom of the flask. The second impinger was of the Greenburg-Smith design with the standard tip.

Metering System - A vacuum gauge, micromanometer, inclined manometer, leak-free pump, calibrated thermocouples and a calibrated dry gas meter were the basic components used to meter the dry gas through the system.



Osceola Farms - Boiler #2  
Particulate Emissions Test Report

4.0 SAMPLING TRAIN AND ANALYTICAL TEST PROCEDURES (cont.)

Gas Density Determination - An ORSAT type combustion analyzer, capable of measuring CO<sub>2</sub>, O<sub>2</sub> and CO was used to determine the molecular weight of the flue gas. An integrated proportional sample was taken at each of the traverse points in order to assure that the total test span was covered. The ORSAT analysis was conducted immediately following each test run.

2. SAMPLING AND ANALYTICAL PROCEDURES

All sampling and analytical procedures were conducted in strict accordance with the methods prescribed in Methods 1 through 5 of the Code of Federal Regulations as found in 40 CFR 60 as amended. The following is the sequence of events that occur both prior to and during the actual stack test.

Traverse Points - The traverse points were calculated in accordance with Method 1 and the probe was marked accordingly.

Static Pressure - The static pressure was checked and recorded.

Preliminary Traverse - A preliminary traverse was conducted. Readings included the pressure drops and stack gas temperatures.

Nomograph - Once all of the above information had been obtained, the nomograph was set up for the actual test to correlate the isokinetic relationships.

Barometric Pressure - Barometric pressure was obtained by use of an aneroid barometer at the test site.

Sampling Train Set-Up

- (a) The pre-weighed filter was placed in the filter holder and visually checked.
- (b) 100 ml of water was placed in the first two impingers.
- (c) Approximately 200 grams of silica gel was placed in the fourth impinger. (Exact weights were logged on the field data sheets).
- (d) Crushed ice was placed around the impingers.
- (e) Once assembly of the entire train was completed, the probe and heater box were turned on.

Pre-test Leak Check - Once the heater box was at the desired temperature for testing, the system was leak checked at 15 inches of vacuum. A leakage rate of less than 0.02 CFM had to be achieved before testing commenced.

Final Check - Once everything was ready to go, the plant was checked to assure that it was running at desired capacity.

Osceola Farms - Boiler #2  
Particulate Emissions Test Report

4.0 SAMPLING TRAIN AND ANALYTICAL TEST PROCEDURES (cont.)

Sampling - Isokinetic sampling as described in Method 5 then took place.

Post-test Leak Check - Upon completion of each test run, the system was leak checked at the highest vacuum recorded during that run. All leak checks were less than 0.02 CFM and considered acceptable.

Sample Recovery - Because of the importance of proper sample recovery procedures, details of the sample recovery can be found in the Quality Control Procedures Section of this report.

Isokinetics - Once all sample recovery was completed and the amount of moisture collected had been determined, calculations were conducted to determine the percent isokinetics of the test run.

Operating Data Sheets - All pertinent operating data were logged throughout the testing period by plant personnel.

Osceola Farms - Boiler #2  
Particulate Emissions Test Report

5.0 QUALITY CONTROL PROCEDURES

The following is a description of the procedures used for maintaining the integrity of samples collected, including the chain of custody and quality control assurance of filters and acetone wash.

Pre-test preparation consisted of the filters being desiccated at  $68 \pm 10$  F at ambient pressure for at least twenty four (24) hours. At intervals of at least six (6) hours, the filters were re-weighed until a constant weight was achieved  $\pm 0.5$  mg change from the previous weighing. These pre-marked filters were then put into petri dishes and sealed. All filters used during testing were put into a carrying case for transport to the job site. A list of the filters and tare weights was available prior to testing.

After each test run, the filter and any particles which may have adhered to the filter holder gasket were carefully removed from the filter holder and placed into its identified petri dish container. This container was then labeled with the run number and date.

Taking care to see that particulate on the outside of the probe or other exterior surface did not get into the sample, particulate matter from the probe liner, nozzle, probe fittings, and front half of the filter holder were acetone washed into a sample container. This container was then sealed. The run number, date, and a mark indicating the level of the acetone wash in the bottle was recorded on the bottle.

Both the petri dish containing the filter and the bottle containing the acetone wash were transported to Eastmount Engineering's laboratory.

Once at the laboratory, each filter was weighed and then put back into its individual container. The container was then placed in a desiccator for at least twenty four (24) hours and then weighed. At intervals of at least six (6) hours, the filters were re-weighed until a constant weight was achieved  $\pm 0.5$  mg change from the previous weighing.

The levels marked on the bottles containing the acetone wash were checked to confirm that no leakage occurred during transport. The contents were then transferred into a pre-tared beaker and evaporated to dryness. Once this had been accomplished, the beaker was placed in a desiccator for at least twenty four (24) hours and then weighed. At intervals of at least six (6) hours, the beaker was re-weighed until a constant weight of  $\pm 0.5$  mg change from the previous weighing was achieved.

All calculations were conducted in strict accordance with 40 CFR 60 (See Calculation Sheets in report).

Osceola Farms - Boiler #2  
Particulate Emissions Test Report

APPENDIX I  
COMPUTER INPUT SHEETS

INPUT DATA SHEET

---

PLANT: OSCEOLA  
 LOCATION: UNIT 2

RUN #: 2-1  
 DATE : 02-07-91

		TRAV PT	VEL HEAD	SQ ROOT	DELTA H	DRYGAS IN	DRYGAS OUT	STACK TEMP
Ds N (FT)	5.0							
Ds S (FT)	5.0							
Dn (IN)	.250	NA1	.31	.56	.78	85	82	157
		2	.36	.60	.90	89	83	157
FILTER#	3712	3	.42	.65	1.05	90	83	157
		4	.50	.71	1.25	91	83	158
PIT COEFF	.84	5	.68	.82	1.70	92	83	158
		6	1.10	1.05	2.75	94	84	157
IMP-1 (INT)	100	7	.95	.97	2.38	96	84	156
		8	.85	.92	2.13	97	85	158
IMP-2 (INT)	100	9	.75	.87	1.88	99	85	157
		10	.72	.85	1.80	99	86	156
IMP-3 (INT)	0							
		NB1	.45	.67	1.13	94	85	155
IMP-4 (INT)	500.0	2	.45	.67	1.13	95	86	154
		3	.47	.69	1.18	95	86	155
IMP-1 (FIN)	368	4	.55	.74	1.38	96	86	157
		5	.85	.92	2.13	97	87	157
IMP-2 (FIN)	142	6	1.30	1.14	3.25	98	87	156
		7	1.00	1.00	2.50	100	87	157
IMP-3 (FIN)	2	8	.95	.97	2.34	100	88	157
		9	.82	.91	2.05	100	88	157
IMP-4 (FIN)	513.5	10	.80	.89	1.25	100	88	156
% CO2	12.4	SA1	.45	.67	1.13	91	87	155
		2	.45	.67	1.13	93	87	153
% O2	7.3	3	.50	.71	1.25	95	87	154
		4	.52	.72	1.30	98	88	156
% CO	0	5	.75	.87	1.88	96	88	154
		6	1.40	1.18	3.50	96	88	153
P BAR	29.96	7	1.10	1.05	2.75	99	88	153
		8	.90	.95	2.25	100	88	154
P STK	.10	9	.75	.87	1.88	101	88	153
		10	.72	.85	1.80	100	88	153
NO. PTS	40							
		SB1	.34	.58	.85	91	87	153
TEST LNGTH	60	2	.38	.62	.95	93	87	152
		3	.44	.66	1.10	94	88	153
END METER	652.715	4	.48	.69	1.20	95	88	155
		5	.63	.79	1.58	95	88	154
INT METER	612.927	6	.95	.97	2.38	96	88	154
		7	.85	.92	2.13	98	88	154
BEGIN TIME:	12:45	8	.77	.88	1.93	99	89	153
		9	.75	.87	1.86	99	89	154
END TIME:	14:00	10	.75	.87	1.86	100	89	153
AVERAGE			.70	.82	1.74	95.9	86.6	155.1

INPUT DATA SHEET

---

PLANT: OSCEOLA  
 LOCATION: UNIT 2

RUN #: 2-2  
 DATE : 02-07-91

		TRAV PT	VEL HEAD	SQ ROOT	DELTA H	DRYGAS IN	DRYGAS OUT	STACK TEMP
Ds N (FT)	5.0							
Ds S (FT)	5.0							
Dn (IN)	.250	NA1	.30	.55	.75	81	82	149
		2	.36	.60	.90	84	82	150
FILTER#	3710	3	.44	.66	1.10	85	82	149
		4	.52	.72	1.30	86	82	151
PIT COEFF	.84	5	.72	.85	1.80	87	82	151
		6	.95	.97	2.38	89	82	152
IMP-1 (INT)	100	7	.85	.92	2.13	91	83	152
		8	.78	.88	1.95	92	83	154
IMP-2 (INT)	100	9	.75	.87	1.88	92	83	155
		10	.72	.85	1.80	93	83	153
IMP-3 (INT)	0							
		NB1	.45	.67	1.13	85	82	147
IMP-4 (INT)	500.0	2	.53	.73	1.33	88	82	150
		3	.55	.74	1.38	90	83	151
IMP-1 (FIN)	358	4	.62	.79	1.55	90	83	153
		5	.78	.88	1.95	91	83	154
IMP-2 (FIN)	134	6	1.50	1.22	3.75	92	83	151
		7	1.10	1.05	2.75	95	83	156
IMP-3 (FIN)	4	8	.95	.97	2.38	95	83	156
		9	.78	.88	1.95	95	84	154
IMP-4 (FIN)	511.9	10	.78	.88	1.95	94	84	153
% CO2	12.1	SA1	.30	.55	.75	88	83	154
		2	.37	.61	.93	89	83	155
% O2	7.6	3	.40	.63	1.00	89	83	154
		4	.48	.69	1.20	90	83	155
% CO	0	5	.75	.87	1.86	90	84	154
		6	1.00	1.00	2.50	92	84	154
P BAR	29.98	7	.94	.97	2.35	93	84	156
		8	.82	.91	2.05	93	84	157
P STK	.10	9	.71	.84	1.78	93	84	157
		10	.65	.81	1.63	92	84	157
NO. PTS	40							
		SB1	.30	.55	.75	86	83	153
TEST LNGTH	60	2	.35	.59	.88	88	83	153
		3	.41	.64	1.03	89	83	154
END METER	691.780	4	.45	.67	1.13	90	83	154
		5	.60	.77	1.50	90	84	154
INT METER	653.000	6	.75	.87	1.86	91	84	151
		7	.82	.91	2.05	91	84	154
BEGIN TIME:	15:00	8	.75	.87	1.86	92	84	156
		9	.68	.82	1.70	92	84	156
END TIME:	16:15	10	.68	.82	1.63	93	84	156
AVERAGE			.67	.80	1.66	90.2	83.2	153.4

INPUT DATA SHEET

---

PLANT: OSCEOLA  
 LOCATION: UNIT 2

RUN #: 2-3  
 DATE : 02-07-91

		TRAV	VEL	SQ	DELTA	DRYGAS	DRYGAS	STACK
		PT	HEAD	ROOT	H	IN	OUT	TEMP
Ds N (FT)	5.0							
Ds S (FT)	5.0							
Dn (IN)	.250	NA1	.32	.57	.80	80	79	154
		2	.35	.59	.88	82	79	156
FILTER#	3709	3	.45	.67	1.13	83	80	155
		4	.55	.74	1.38	84	80	155
PIT COEFF	.84	5	.72	.85	1.80	86	80	154
		6	.95	.97	2.38	88	80	153
IMP-1 (INT)	100	7	.95	.97	2.38	89	80	153
		8	.85	.92	2.13	90	80	153
IMP-2 (INT)	100	9	.78	.88	1.95	90	80	153
		10	.75	.87	1.88	91	80	153
IMP-3 (INT)	0							
		NB1	.43	.66	1.08	86	80	154
IMP-4 (INT)	500.0	2	.47	.69	1.18	88	81	155
		3	.54	.73	1.35	88	81	154
IMP-1 (FIN)	324	4	.60	.77	1.50	89	81	154
		5	.75	.87	1.88	91	82	156
IMP-2 (FIN)	138	6	1.70	1.30	4.25	93	82	153
		7	1.10	1.05	2.75	94	82	155
IMP-3 (FIN)	2	8	.94	.97	2.35	94	82	155
		9	.78	.88	1.95	94	82	156
IMP-4 (FIN)	512.0	10	.75	.87	1.88	94	82	156
% CO2	12.1	SA1	.35	.59	.88	87	82	156
		2	.40	.63	1.00	89	82	154
% O2	7.6	3	.45	.67	1.13	90	82	154
		4	.50	.71	1.25	90	83	155
% CO	0	5	.70	.84	1.75	90	83	154
		6	.92	.96	2.30	91	83	154
P BAR	29.98	7	.90	.95	2.25	92	83	155
		8	.82	.91	2.05	93	83	154
P STK	.10	9	.70	.84	1.75	93	84	157
		10	.67	.82	1.68	93	84	155
NO. PTS	40							
		SB1	.30	.55	.75	86	82	155
TEST LNGTH	53	2	.35	.59	.88	88	82	156
		3	.41	.64	1.03	88	82	155
END METER	725.451	4	.44	.66	1.10	88	82	153
		5	.50	.71	1.25	89	83	154
INT METER	692.083							
BEGIN TIME:	16:50							
END TIME:	17:50							
AVERAGE			.66	.80	1.66	89.2	81.5	154.5

Osceola Farms - Boiler #2  
Particulate Emissions Test Report

APPENDIX II  
ISOKINETIC CALCULATION SHEETS



ISOKINETIC CALCULATION SHEET  
-----

PLANT: OSCEOLA  
LOCATION: UNIT 2

RUN #: 2-1  
DATE : 02-07-91

TS ( ` F) = 155.1	% CO2 = 12.4	VM (CF) = 39.788
TS ( ` R) = 615.1	% O2 = 7.3	DELTA H (ABS) = 30.13
TM ( ` F) = 91.3	% CO = 0	PS (ABS) = 30.01
TM ( ` R) = 551.3	% N2 = 80.3	SQRT DELTA P = .824723
VI (TOT) = 325.5	CP = .84	AREA NOZZLE = .000341

Y = .9863

VM STD =	17.64	$\frac{(VM) (Y) (DELTA H ABS)}{(TM)}$	= 37.83 DSCF
VW STD =	.04707 (VI TOT)	=	15.32 CF
BWO =	$\frac{VW STD}{VW STD + VM STD}$	=	.288
BWO =	MOISTURE FROM STEAM TABLES		= .286
VI TOT =	ADJUSTED TO SATURATION VOLUME=		321.7 ML
1-BWO =	1 - BWO		= .714
Md (DRY) =	$\begin{aligned} &.44 (\% CO2) \\ &+.32 (\% O2) \\ &+.28 (\% CO) \\ &+.28 (\% N2) \\ &----- \end{aligned}$	=	30.27 LBS/LB MOLE
Ms (WET) =	$\begin{aligned} &MD (1-BWO) \\ &+ 18 (BWO) \\ &----- \end{aligned}$	=	26.76 LBS/LB MOLE
G =	SQRT (TS / · PS / MS)		= .88
VS =	85.49 (CP) (G) (SQRT DELTA P)		= 51.8 FPS
H =	0.002669 (VI TOT)		= .86
J =	(DELTA H ABS) (VM) (Y) / (TM)		= 2.14
K =	(H) + (J)		= 3.00
% ISO =	$\frac{(TS) (K) (1.667)}{(TIME) (VS) (PS) (AN)}$	=	96.8

ISOKINETIC CALCULATION SHEET

---

PLANT: OSCEOLA  
 LOCATION: UNIT 2

RUN #: 2-2  
 DATE : 02-07-91

TS ( `F)=	153.4	% CO2=	12.1	VM (CF)	=	38.780	
TS ( `R)=	613.4	% O2=	7.6	DELTA H (ABS)=		30.10	
TM ( `F)=	86.7	% CO=	0	PS (ABS)	=	29.99	
TM ( `R)=	546.7	% N2=	80.3	SQRT DELTA P	=	.802094	
VI (TOT)=	307.9	CP=	.84	AREA NOZZLE	=	.000341	
						Y =	.9863
VM STD	=	17.64	(VM) (Y) (DELTA H ABS)	-----	=	37.15 DSCF	
				(TM)			
VW STD	=	.04707	(VI TOT)	=		14.49 CF	
BWO	=	VW STD		=		.281	
		VW STD + VM STD					
BWO	=	MOISTURE FROM STEAM TABLES		=		.274	
VI TOT	=	ADJUSTED TO SATURATION VOLUME=		=		298.5 ML	
1-BWO	=	1 - BWO		=		.726	
Md (DRY)	=	.44	(% CO2)				
		.32	(% O2)				
		.28	(% CO)	=		30.24 LBS/LB	
		.28	(% N2)	-----		MOLE	
Ms (WET)	=	MD (1-BWO)					
		+ 18 (BWO)		=		26.88 LBS/LB	
		-----				MOLE	
G	=	SQRT (TS / PS / MS)		=		.87	
VS	=	85.49 (CP) (G) (SQRT DELTA P)		=		50.2 FPS	
H	=	0.002669 (VI TOT)		=		.80	
J	=	(DELTA H ABS) (VM) (Y) / (TM)		=		2.11	
K	=	(H) + (J)		=		2.90	
% ISO	=	(TS) (K) (1.667)		-----	=	96.3	
		(TIME) (VS) (PS) (AN)					

ISOKINETIC CALCULATION SHEET

---

PLANT: OSCEOLA  
 LOCATION: UNIT 2

RUN #: 2-3  
 DATE: 02-07-91

Avg = 154

Avg = 7.5

TS (°F) = 154.5	% CO2 = 12.1	VM (CF) = 33.368
TS (°R) = 614.5	% O2 = 7.6	DELTA H (ABS) = 30.10
TM (°F) = 85.3	% CO = 0	PS (ABS) = 29.99
TM (°R) = 545.3	% N2 = 80.3	SQRT DELTA P = .796693
VI (TOT) = 276.0	CP = .84	AREA NOZZLE = .000341

---

		Y = .9863
VM STD = 17.64	(VM) (Y) (DELTA H ABS) ----- (TM)	= 32.04 DSCF
VW STD = .04707	(VI TOT)	= 12.99 CF
BWO =	$\frac{VW\ STD}{VW\ STD + VM\ STD}$	= .288
BWO =	MOISTURE FROM STEAM TABLES	= .282
VI TOT =	ADJUSTED TO SATURATION VOLUME =	267.2 ML
1-BWO =	1 - BWO	= .718
Md (DRY) =	.44 (% CO2) +.32 (% O2) +.28 (% CO) +.28 (% N2) -----	= 30.24 LBS/LB MOLE
Ms (WET) =	MD (1-BWO) + 18 (BWO) -----	= 26.79 LBS/LB MOLE
G =	SQRT (TS / PS / MS)	= .87
VS =	85.49 (CP) (G) (SQRT DELTA P)	= 50.0 FPS
H =	0.002669 (VI TOT)	= .71
J =	(DELTA H ABS) (VM) (Y) / (TM)	= 1.82
K =	(H) + (J)	= 2.53
% ISO =	$\frac{(TS) (K) (1.667)}{(TIME) (VS) (PS) (AN)}$	= 95.6

Osceola Farms - Boiler #2  
Particulate Emissions Test Report

APPENDIX III  
ENTHALPY CALCULATION SHEETS

ENTHALPY CALCULATION SHEET  
-----

PLANT : OSCEOLA  
LOCATION: UNIT 2

RUN #: 2-1  
DATE : 02-07-91

	STEAM PRESSURE	STEAM TEMPERATURE	FEED WATER TEMPERATURE
	210	520	220
	225		
	240		
	215		
	200		
	225		
AVERAGE	219.2 PSIG	520.0	220.0
P ABS =	233.9 PSIA		
ENTHALPY @	550 'F AND	235 PSIA =	1292.9
ENTHALPY @	500 'F AND	235 PSIA =	1266.2
ENTHALPY @	520.0 'F AND	235 PSIA =	1276.9
ENTHALPY OF FEED WATER =		188.1	
AVERAGE ENTHALPY =		1088.7	BTU/LB OF STEAM

ENTHALPY CALCULATION SHEET  
-----

PLANT : OSCEOLA  
LOCATION: UNIT 2

RUN #: 2-2  
DATE : 02-07-91

	STEAM PRESSURE	STEAM TEMPERATURE	FEED WATER TEMPERATURE
	225	520	220
	240		
	220		
	215		
	210		
	230		
AVERAGE	223.3 PSIG	520.0	220.0
P ABS =	238.0 PSIA		
ENTHALPY @	550 'F AND	240 PSIA =	1292.5
ENTHALPY @	500 'F AND	240 PSIA =	1265.7
ENTHALPY @	520.0 'F AND	240 PSIA =	1276.4
ENTHALPY OF FEED WATER =		188.1	
AVERAGE ENTHALPY =		1088.3	BTU/LB OF STEAM

ENTHALPY CALCULATION SHEET  
-----

PLANT : OSCEOLA  
LOCATION: UNIT 2

RUN #: 2-3  
DATE : 02-07-91

	STEAM PRESSURE	STEAM TEMPERATURE	FEED WATER TEMPERATURE
	220	520	220
	220		
	225		
	220		
	220		
	220		
AVERAGE	220.8 PSIG	520.0	220.0
P ABS =	235.5 PSIA		
ENTHALPY @	550 'F AND	235 PSIA =	1292.9
ENTHALPY @	500 'F AND	235 PSIA =	1266.2
ENTHALPY @	520.0 'F AND	235 PSIA =	1276.9
ENTHALPY OF FEED WATER =		188.1	
AVERAGE ENTHALPY =		1088.7	BTU/LB OF STEAM

Osceola Farms - Boiler #2  
Particulate Emissions Test Report

APPENDIX IV  
HEAT INPUT CALCULATION SHEETS



HEAT INPUT CALCULATION SHEET  
-----

PLANT: OSCEOLA  
LOCATION: UNIT 2

RUN #: 2-1  
DATE: 02-07-91

<u>STEAM INTEGRATOR READINGS</u>	<u>TIME</u>	<u>INTEGRATOR FACTOR</u>
END	386064	14: 00
BEGIN	385955	12: 45
NET	----- 109	----- 75
		1600
		<u>LBS/HR STEAM</u>
139520 LBS/HR STEAM / 55% EFF. =		253673
253673 LBS/HR STEAM X 1089 BTU/LB =		276.2
		139520 MINS =
		EQUIV.
		BTU(e6)/HR

<u>OIL INTEGRATOR READINGS</u>	<u>TIME</u>	<u>GALS/HR</u>
END	0	14: 00
BEGIN	0	12: 45
NET	----- 0	----- 75
		0 GPH
0 GPH X 150,000 BTU/GAL (EST) =		0
		BTU(e6)/HR

ALLOWABLE EMISSIONS

BAGASSE	276.2	-	0	X	.2	=	55.2	LBS/HR
OIL			0	X	.1	=	.0	LBS/HR
TOTAL						=	55.2	LBS/HR

HEAT INPUT CALCULATION SHEET

PLANT: OSCEOLA  
 LOCATION: UNIT 2

RUN #: 2-2  
 DATE: 02-07-91

	<u>STEAM INTEGRATOR READINGS</u>	<u>TIME</u>	<u>INTEGRATOR FACTOR</u>
END	386254	16: 15	1600
BEGIN	<u>386146</u>	<u>15: 00</u>	<u>LBS/HR STEAM</u>
NET	108	X 1600 / 75	MINS = 138240
138240	LBS/HR STEAM	/ 55% EFF. =	251345 EQUIV.
251345	LBS/HR STEAM	X 1088 BTU/LB =	273.5 BTU(e6)/HR

	<u>OIL INTEGRATOR READINGS</u>	<u>TIME</u>	<u>GALS/HR</u>
END	0	16: 15	
BEGIN	<u>0</u>	<u>15: 00</u>	
NET	0	GALLONS 75	MINS = 0 GPH
0	GPH	X 150,000 BTU/GAL (EST) =	0 BTU(e6)/HR

ALLOWABLE EMISSIONS

BAGASSE	273.5	-	0	X	.2	=	54.7	LBS/HR
OIL			0	X	.1	=	.0	LBS/HR
TOTAL						=	54.7	LBS/HR

HEAT INPUT CALCULATION SHEET

PLANT: OSCEOLA  
 LOCATION: UNIT 2

RUN #: 2-3  
 DATE: 02-07-91

	STEAM INTEGRATOR READINGS	TIME	INTEGRATOR FACTOR
END	386391	17: 50	1600
BEGIN	386303	16: 50	LBS/HR STEAM
NET	<div style="border-top: 1px dashed black; display: inline-block; width: 50px;">88</div>	X 1600 / 60 MINS =	140800

140800 LBS/HR STEAM / 55% EFF. = 256000 EQUIV.

256000 LBS/HR STEAM X 1089 BTU/LB = 278.7 BTU(e6)/HR

	OIL INTEGRATOR READINGS	TIME	GALS/HR
END	0	17: 50	
BEGIN	0	16: 50	
NET	<div style="border-top: 1px dashed black; display: inline-block; width: 50px;">0</div>	GALLONS 60 MINS =	0 GPH

0 GPH X 150,000 BTU/GAL (EST) = 0 BTU(e6)/HR

ALLOWABLE EMISSIONS

BAGASSE	278.7	-	0	X	.2	=	55.7	LBS/HR
OIL			0	X	.1	=	.0	LBS/HR
TOTAL						=	55.7	LBS/HR

Osceola Farms - Boiler #2  
Particulate Emissions Test Report

APPENDIX V  
EMISSION CALCULATION SHEETS

EMISSION CALCULATION SHEET

PLANT: OSCEOLA  
 LOCATION: UNIT 2

RUN #: 2-1  
 DATE: 02-07-91

	<u>FILTER</u>	<u>BEAKER</u>	<u>BLANKS</u>	
			<u>FILTER</u>	<u>ACETONE</u>
NO. :	3712	211	3611	209
FINAL:	.8397	79.1368	.6264	76.3019
TARE :	.6316	79.1323	.6264	76.3009
NET :	<u>.2081</u>	<u>.0045</u>	<u>.0000</u>	<u>.0010/200ML</u>

---

			VOLUME OF RINSE 340	
WEIGHT =	212.60			
RESIDUE =	- 1.70			
Mn =	210.90 Mg	AS =	39.3	SQ FT
Qs =	3600(1-BWO) (VS) (AS) (17.64) (PS)/(TS)		=	4503229 DSCFH
CS =	(2.205 X 10 <sup>-6</sup> ) (Mn) / (VM STD)		=	1.229e-5 LBS/SCF
CS' =	0.0154 (Mn) / (VM STD)		=	.09 GRAINS /SCF
PMR =	(QS) (CS)		=	55.35 LBS/HR
LOAD=	MILLIONS OF BTU / HOUR INPUT		=	276.2 BTU e10 / HR
CS =	LBS / MILLION BTu		=	.200 LBS/ BTu e6

EMISSION CALCULATION SHEET

PLANT: OSCEOLA  
 LOCATION: UNIT 2

RUN #: 2-2  
 DATE: 02-07-91

	FILTER	BEAKER	BLANKS	
	-----	-----	FILTER	ACETONE
	-----	-----	-----	-----
NO. :	3710	212	3611	209
FINAL:	.8274	77.1807	.6264	76.3019
TARE :	.6349	77.1766	.6264	76.3009
NET :	.1925	.0041	.0000	.0010/200ML

---

			VOLUME OF RINSE	415
WEIGHT =	196.60			
RESIDUE =	- 2.08			
Mn =	194.53 Mg	AS =	39.3	SQ FT
Qs =	3600(1-BWO) (VS) (AS) (17.64) (PS) / (TS)	=	4445045	DSCFH
CS =	(2.205 X 10 <sup>-6</sup> ) (Mn) / (VM STD)	=	1.154e-5	LBS/SCF
CS' =	0.0154 (Mn) / (VM STD)	=	.08	GRAINS /SCF
PMR =	(QS) (CS)	=	51.32	LBS/HR
LOAD=	MILLIONS OF BTU / HOUR INPUT	=	273.5	BTU e10 / HR
CS =	LBS / MILLION BTu	=	.188	LBS/ BTu e6

EMISSION CALCULATION SHEET

PLANT: OSCEOLA  
 LOCATION: UNIT 2

RUN #: 2-3  
 DATE: 02-07-91

	SAMPLES		BLANKS	
	<u>FILTER</u>	<u>BEAKER</u>	<u>FILTER</u>	<u>ACETONE</u>
NO. :	3709	213	3611	209
FINAL:	.8086	78.0204	.6264	76.3019
TARE :	.6315	78.0124	.6264	76.3009
NET :	<u>.1771</u>	<u>.0080</u>	<u>.0000</u>	<u>.0010/200ML</u>

VOLUME OF RINSE 370

WEIGHT = 185.10  
 RESIDUE = - 1.85

Mn = 183.25 Mg AS = 39.3 SQ FT

Qs = 3600(1-BWO)(VS)(AS)(17.64)(PS)/(TS) = 4373008 DSCFH

Avg = 4,440,427

CS = (2.205 X 10<sup>-6</sup>)(Mn) / (VM STD) = 1.261e-5 LBS/SCF

CS' = 0.0154 (Mn) / (VM STD) = .09 GRAINS /SCF

PMR = (QS) (CS) = 55.14 LBS/HR

LOAD = MILLIONS OF BTU / HOUR INPUT = 278.7 BTU e10 / HR

CS = LBS / MILLION BTu = .198 LBS/ BTu e6

Avg = 276.1

Osceola Farms - Boiler #2  
Particulate Emissions Test Report

APPENDIX VI  
NOMENCLATURE SHEETS



Osceola Farms - Boiler #2  
Particulate Emissions Test Report

NOMENCLATURE SHEET

PARTICULATE EMISSION TEST

Ar	Acetone residue - result of Blank evaporation.
AREA NOZZLE	Area of the nozzle in square feet.
AS	Area of the stack in square feet.
BDL	Below detectable limits
BWO	The amount of moisture in the flue gas.
% CO	Percent of carbon monoxide in the flue gas.
% CO2	Percent of carbon dioxide in the flue gas.
Cp	Pitot tube coefficient.
CS	The concentration in the stack in pounds per standard cubic foot.
Cs'	The concentration in the stack in grains per standard cubic foot.
DELTA H	The meter orifice differential.
DELTA H(ABS)	The meter orifice differential, absolute conditions in inches of mercury.
Dn (IN)	Diameter of the nozzle in inches.
DRY GAS IN	Temperature of the dry gas meter inlet degrees Farenheight.
DRY GAS OUT	Temperature of the dry gas meter outlet degrees Farenheight.
Ds (FT)	Diameter of the stack in feet.
E	The emission rate in pounds per million Btu derived by using F-Factor.
E (Heat Input)	The emission rate in pounds per million Btu derived by use of calculated heat input.
END METER	The dry gas meter reading at the end of the test.
F factor	The theoretical amount of air in dry standard cubic feet (DSCF) needed to combust a million Btu's worth of fuel.

Osceola Farms - Boiler #2  
Particulate Emissions Test Report

NOMENCLATURE (cont'd)

Filter Catch	The amount of particulate captured on the filter during testing.
INT METER	The dry gas meter reading at the beginning of the test.
Md (DRY)	The dry molecular weight of the flue gas in pounds per pound mole.
MN	The amount of particulate collected by washing the nozzle, probe, and front half of the glassware, reported in milligrams.
MN'	The milligrams of particulate collected minus the blank.
Ms (WET)	Wet or actual molecular weight of the flue gas in pounds per pound mole.
% N2	The percent of nitrogen in the flue gas.
NO PTS	Number of traverse points.
% O2	Percent of oxygen in the flue gas.
P BAR	Barometric pressure at test location.
P STK	Static pressure of the stack in inches of water.
PMR	The emission rate in pounds per hour.
PS (ABS)	Absolute pressure conditions in the stack in inches of mercury.
Qs	The volumetric flow rate of the flue gas in dry standard cubic feet per hour.
SQ ROOT	The square root of each velocity head measurement.
SQRT DELTA P	The average of the square roots of the measured pressure drops.
Stack Temp or TS (°F)	The temperature of the stack in degrees Fahrenheit.
TS (°R)	The temperature of the stack in degrees Rankine.
T (Hot Box)	Temperature around the filter box, degrees Fahrenheit.
TM (°F)	Average temperature of the dry gas meter in degrees Fahrenheit.

Osceola Farms - Boiler #2  
Particulate Emissions Test Report

NOMENCLATURE (cont'd)

TM (°R)	Average temperature of the dry gas meter in degrees Rankine.
VEL HEAD	The pressure drop measured across the pitot tubes.
VI (TOT)	The amount of water collected in the impingers in milliliters.
VM (CF)	The volume sampled through the dry gas meter in cubic feet.
VM STD	Volume sampled through the dry gas meter corrected to standard conditions.
VS	Velocity of the stack gas in feet per second.
VW STD	The amount of moisture collected, converted to standard cubic feet.
Y	Meter box calibration factor.
o	Sampling time in minutes.

Osceola Farms - Boiler #2  
Particulate Emissions Test Report

APPENDIX VII

FIELD DATA SHEETS - UNIT OPERATING CONDITIONS







Osceola Farms - Boiler #2  
Particulate Emissions Test Report

APPENDIX VIII

FIELD DATA SHEETS - STACK TESTING



FIELD DATA SHEET  
GENERAL INFORMATION

Plant:	<u>OSCEOLA</u>	Run #:	<u>C2-1</u>
Location:	<u>UNIT 2</u>	Date:	<u>7 FEB 91</u>
Ds (ft):	<u>N 5.0</u> <u>S 5.0</u>	No. Points:	<u>40</u>
Dn (in):	<u>.250</u>	Test Length:	<u>60</u>
Filter #:	<u>3712</u>	End Meter Reading:	<u>652.75</u>
Cp:	<u>.84</u>	Int Meter Reading:	<u>612.927</u>
P bar:	<u>29.96</u>	Begin Time:	<u>12:45</u>
P stack:	<u>.10</u>	End Time:	<u>14:00</u>
IMP-1 (INT)	<u>368 100</u>	IMP-1 (FINAL)	<u>368</u>
IMP-2 (INT)	<u>142 100</u>	IMP-2 (FINAL)	<u>142</u>
IMP-3 (INT)	<u>2 0</u>	IMP-3 (FINAL)	<u>2</u>
IMP-4 (INT)	<u>513.5 500.0g</u>	IMP-4 (FINAL)	<u>513.5</u>

	TEST 1	TEST 2	TEST 3
% CO2	<u>12.4</u>	_____	_____
% O2	<u>7.3</u>	_____	_____
% CO	<u>0</u>	_____	_____

Project Director: <u>SJ MERCADANTE</u>	Field Laboratory: <u>B. GIBSON</u>
Meter Box Operator: <u>R. VALDEZ</u>	Chain of Custody: <u>SJ. MERCADANTE</u>
Probe Operator: <u>J. JARDIN</u>	Plant Coordinator: <u>P. FARINAS</u>
Orsat Analyst: <u>SJ. MERCADANTE</u>	Agency Rep: <u>K. TUCKER</u>

Comments: \_\_\_\_\_

TRAVERSE DATA SHEET

Page 1 of 3

Sampling time per point: 1.5

Plant: OSCEOLA

Run #: RUN 2-1

Location: # 2

Date: 2-7-91

612.927

Trav. No.	Delta P	Delta H	Meter Reading	DGM In	DGM Out	Hot Box	Impg Temp	Stack Temp	Vac
NORTH A 1	.31	.78	613.65	85	82	256	<del>256</del> <sup>68</sup>	157	2.5
2	.36	.90	614.43	89	83	257	<del>257</del> <sup>69</sup>	157	3.0
3	.42	1.05	615.25	90	83	259	68	157	3.0
02 4	.50	1.25	616.10	91	83	255	68	158	3.3
5	.68	1.70	617.04	92	83	261	69	158	4.0
7.8% 6	1.10	2.75	618.23	94	84	265	69	157	6.0
7.2% 7	.95	2.38	619.45	96	84	268	69	156	6.0
8	.85	2.13	620.61	97	85	269	66	158	5.5
9	.75	1.88	621.73	99	85	270	64	157	5.0
7.8% 10	.72	1.80	622.79	99	86	267	63	156	5.0
NORTH B 1	.45	1.13	<del>623.42</del>	94	85	255	66	155	3.5
18 2	.45	1.13	624.42	95	86	252	64	154	3.5
3	.47	1.18	625.25	95	86	252	64	155	4.0
21 4	.55	1.38	626.25	96	86	250	65	157	4.5
5	.85	2.13	627.21	97	87	249	68	157	6.0
24 6	1.30	3.25	628.45	98	87	250	68	156	8.0

Relationship: 2.5  
 Box #: 3 V: 9863 Delta H: 1.90  
 Start Time: 12:45 End Time: \_\_\_\_\_  
 Pre Leak Ck: DEAD CFM @ 15 "Hg  
 Mid Leak Ck: \_\_\_\_\_ CFM @ \_\_\_\_\_ "Hg (Vol: \_\_\_\_\_)  
 Post Leak Ck: DEAD CFM @ 11 "Hg  
 Pitot Leak Ck: DEAD @ 6 "H2O  
 Box Oper: RJ Probe Oper: J

TRAVERSE DATA SHEET

Page 2 of 3

Sampling time per point: 1.5 MIN

Plant: OSCEOLA

Run #: RUN 2-1

Location: #2

Date: 2-7-91

	Trav. No.	Delta P	Delta H	Meter Reading	DGM In	DGM Out	Hot Box	Impg Temp	Stack Temp	Vac
NORTH (CONT)	B 7	1.00	2.50	629.74	100	87	251	66	157	7.5
	8	.95	2.34	630.92	100	88	252	65	157	7.3
	9	.82	2.05	<del>631.80</del>	100	88	254	64	157	7.0
	10	.80	1.25	633.60	100	88	252	66	156	5.0
SOUTH A 6.6%	1	.45	1.13	633.82	91	87	255	64	155	4.5
	2	.45	1.13	634.63	93	87	256	65	153	4.5
	3	.50	1.25	MISS	95	87	256	65	154	5.0
	4	.52	1.30	636.28	98	88	257	65	156	5.0
	5	.75	1.88	MISS	96	88	258	67	154	6.0
	6	1.40	3.50	638.60	96	88	258	66	153	11.0
	7	1.10	2.75	639.92	99	88	258	62	153	10.0
	8	.90	2.25	641.25	100	88	253	62	154	9.0
	9	.75	1.88	642.24	101	88	253	63	153	7.5
	10	.72	1.80	643.31	100	88	254	65	153	7.3

Relationship: 2.5  
 Box #: 3 Y: 9863 Delta H@: 1.90  
 Start Time: \_\_\_\_\_ End Time: \_\_\_\_\_  
 Pre Leak Ck: \_\_\_\_\_ CFM @ \_\_\_\_\_ "Hg  
 Mid Leak Ck: \_\_\_\_\_ CFM @ \_\_\_\_\_ "Hg (Vol: \_\_\_\_\_)  
 Post Leak Ck: \_\_\_\_\_ CFM @ \_\_\_\_\_ "Hg  
 Pitot Leak Ck: \_\_\_\_\_ @ \_\_\_\_\_ "H2O  
 Box Oper: RJ Probe Oper: JT



FIELD DATA SHEET  
GENERAL INFORMATION

Plant: <u>OSCEOLA</u>	Run #: <u>C2-2</u>
Location: <u>UNIT 2</u>	Date: <u>7 FEB 91</u>
Ds (ft): <u>N 5.0 S 5.0</u>	No. Points: <u>40</u>
Dn (in): <u>.250</u>	Test Length: <u>4.0 min</u>
Filter #: <u>3710</u>	End Meter Reading: <u>691.780</u>
Cp: <u>.84</u>	Int Meter Reading: <u>653.000</u>
P bar: <u>29.98</u>	Begin Time: <u>15:00</u>
P stack: <u>.10</u>	End Time: <u>16:15</u>

IMP-1 (INT) <u>100 mL</u>	IMP-1 (FINAL) <u>358</u>
IMP-2 (INT) <u>100 mL</u>	IMP-2 (FINAL) <u>134</u>
IMP-3 (INT) <u>0 mL</u>	IMP-3 (FINAL) <u>4</u>
IMP-4 (INT) <u>500.0g</u>	IMP-4 (FINAL) <u>511.9</u>

	TEST 1	TEST 2	TEST 3
% CO2	<u>12.1</u>	_____	_____
% O2	<u>7.6</u>	_____	_____
% CO	<u>0</u>	_____	_____

Project Director: <u>S.J. MERLAONTE</u>	Field Laboratory: <u>B. GIBSON</u>
Meter Box Operator: <u>R. VALDEZ</u>	Chain of Custody: <u>R. VALDEZ</u>
Probe Operator: <u>J. JARDIN</u>	Plant Coordinator: <u>P. FARINAS</u>
Orsat Analyst: <u>S.J. MERLAONTE</u>	Agency Rep: <u>K. TUCKER</u>

Comments:

TRANSVERSE DATA SHEET

Page 1 of 3

Sampling time per point: 1.5 min

Plant: OSCEOLA

Run #: RUN 2-2

Location: #2

Date: 2-7-91

Trav. No.	Delta P	Delta H	Meter Reading	DGM In	DGM Out	Hot Box	Impg Temp	Stack Temp	Vac
NORTH A1	.30	.75	653.68	81	82	237	69	149	3.0
(3) 2	.36	.90	654.44	84	82	238	66	150	3.5
3	.44	1.10	655.24	85	82	240	64	149	3.8
8.3% (4)	.52	1.30	656.08	86	82	243	63	151	4.0
5	.72	1.80	657.07	87	82	248	63	151	5.0
8.5% (6)	.95	2.38	658.18	89	82	252	61	152	6.0
7	.85	2.13	659.28	91	83	257	62	152	6.0
8.4% (8)	.78	1.95	660.38	92	83	259	62	154	5.5
9	.75	1.88	661.45	92	83	263	63	155	5.5
(15) 10	.72	1.80	662.51	93	83	265	63	153	5.5
8.8% NORTH B4	.45	1.13	663.33	85	82	263	67	147	4.0
8.4% (3) 2	.53	1.33	664.20	88	82	265	66	150	4.5
3	.55	1.38	665.10	90	83	265	68	151	5.0
(4) 4	.62	1.55	666.04	90	83	265	67	153	5.0
5	.78	1.95	667.05	91	83	265	66	154	6.0

Relationship: 2.5  
 Box #: 3 Y: .9863 Delta H@: 1.90  
 Start Time: 15:00 End Time: \_\_\_\_\_  
 Pre Leak Ck: LEAD CFM @ 15 "Hg  
 Mid Leak Ck: \_\_\_\_\_ CFM @ \_\_\_\_\_ "Hg (Vol: \_\_\_\_\_)  
 Post Leak Ck: \_\_\_\_\_ CFM @ \_\_\_\_\_ "Hg  
 Pitot Leak Ck: \_\_\_\_\_ @ \_\_\_\_\_ "H2O  
 Box Oper: PV Probe Oper: JJ

FILTER #  
3710

TRAVERSE DATA SHEET

Page 2 of 3

Sampling time per point: 1.5 min

Plant: OSCEOLA

Run #: RUN 2-2

Location: #2

Date: 2-7-91

Trav. No.	Delta P	Delta H	Meter Reading	DGM In	DGM Out	Hot Box	Impg Temp	Stack Temp	Vac
NORTH B 6	1.50	3.75	668.35	92	83	265	64	151	12.0
(CONT) 7	1.1	2.75	669.70	95	83	264	63	156	8.0
8.0% 8	.95	2.38	670.97	95	83	264	64	156	5.0
8.0% 9	.78	1.95	672.10	95	84	264	64	154	4.5
10	.78	1.95	673.19	94	84	263	67	153	4.5
SOUTH A 1	.30	.75	673.93	88	83	259	68	154	3.0
6.0% 2	.37	.93	674.66	89	83	260	66	155	3.5
3	.40	1.00	675.47	89	83	260	64	154	3.5
4	.48	1.20	676.30	90	83	261	61	155	4.0
5	.75	1.86	677.20	90	84	261	59	154	5.0
6	1.00	2.50	678.35	92	84	261	59	154	6.0
7	.94	2.35	679.52	93	84	261	59	156	5.5
8	.82	2.05	680.65	93	84	263	61	157	5.5
9	.71	1.78	681.70	93	84	264	61	157	5.0
10	.65	1.63	682.69	92	84	265	60	157	5.0

Relationship: 2.5  
 Box #: 3 Y: .9863 Delta H@: 1.90  
 Start Time: \_\_\_\_\_ End Time: \_\_\_\_\_  
 Pre Leak Ck: \_\_\_\_\_ CFM @ \_\_\_\_\_ "Hg  
 Mid Leak Ck: \_\_\_\_\_ CFM @ \_\_\_\_\_ "Hg (Vol: \_\_\_\_\_)  
 Post Leak Ck: \_\_\_\_\_ CFM @ \_\_\_\_\_ "Hg  
 Pitot Leak Ck: \_\_\_\_\_ @ \_\_\_\_\_ "H2O  
 Box Oper: RJ Probe Oper: JJ

TRAVERSE DATA SHEET

Page 3 of 3

Sampling time per point: 1.5 min

Plant: OSCEOLA

Run #: RUN 2-2

Location: STACK

Date: 2-7-91

Trav. No.	Delta P	Delta H	Meter Reading	DGM In	DGM Out	Hot Box	Impg Temp	Stack Temp	Vac
SOUTH#B 1	.30	.75	683.38	86	83	260	66	153	3.5
(3) 2	.35	.88	584.12	88	83	260	66	153	4.0
<u>6.6%</u> 3	.41	1.03	684.90	89	83	260	66	154	4.5
(6) 4	.45	1.13	685.73	90	83	260	67	154	4.5
5	.60	1.50	686.60	90	84	256	68	154	5.0
<u>6.5%</u> (7) 6	.75	1.86	687.55	91	84	257	68	151	5.5
7	.82	2.05	688.61	91	84	257	68	154	6.0
<u>6.8</u> (12) 8	.75	1.86	689.66	92	84	256	66	156	6.0
9	.68	1.70	690.68	92	84	254	66	156	5.5
(15) 10	.65	1.63	691.780	93	84	253	67	156	5.5

Relationship: 2.5  
 Box #: 3 Y: 9883 Delta H@: 1.90  
 Start Time: \_\_\_\_\_ End Time: \_\_\_\_\_  
 Pre Leak Ck: \_\_\_\_\_ CFM @ \_\_\_\_\_ "Hg  
 Mid Leak Ck: \_\_\_\_\_ CFM @ \_\_\_\_\_ "Hg (Vol: \_\_\_\_\_)  
 Post Leak Ck: READ CFM @ 12 "Hg  
 Pitot Leak Ck: \_\_\_\_\_ @ \_\_\_\_\_ "H2O  
 Box Oper: RV Probe Oper: JJ



FIELD DATA SHEET  
GENERAL INFORMATION

Plant:	<u>OSCEOLA FARMS</u>	Run #:	<u>C2-3</u>
Location:	<u>UNIT 2</u>	Date:	<u>7 FEB 91</u>
Ds (ft):	<u>N 5.0 S 5.0</u>	No. Points:	<u>40</u>
Dn (in):	<u>.250</u>	Test Length:	<u>53 min *</u>
Filter #:	<u>3709</u>	End Meter Reading:	<u>725.451</u>
Cp:	<u>.24</u>	Int Meter Reading:	<u>692.083</u>
P bar:	<u>29.98</u>	Begin Time:	<u>16:50</u>
P stack:	<u>.10</u>	End Time:	<u>17:50</u>

IMP-1 (INT)	<u>100 mL</u>	IMP-1 (FINAL)	<u>324</u>
IMP-2 (INT)	<u>100 mL</u>	IMP-2 (FINAL)	<u>138</u>
IMP-3 (INT)	<u>0 mL</u>	IMP-3 (FINAL)	<u>2</u>
IMP-4 (INT)	<u>500.0 g</u>	IMP-4 (FINAL)	<u>512.0</u>

	TEST 1	TEST 2	TEST 3
% CO2	<u>12.1</u>	_____	_____
% O2	<u>7.6</u>	_____	_____
% CO	<u>0</u>	_____	_____

Project Director:	<u>S.J. MERCADANTE</u>	Field Laboratory:	<u>B. GIBSON</u>
Meter Box Operator:	<u>R. VALDEZ</u>	Chain of Custody:	<u>R. VALDEZ</u>
Probe Operator:	<u>J. JARDIN</u>	Plant Coordinator:	<u>P. FARINAS</u>
Orsat Analyst:	<u>S.J. MERCADANTE</u>	Agency Rep:	<u>K. TUCKER</u>

Comments: \* TEST CUT SHORT AT 53 MIN BECAUSE THE MILL WENT DOWN

TRAVERSE DATA SHEET

Page 1 of 3

Sampling time per point: 1.5 min

Plant: OSCEOLA

Run #: RVN 2-3

Location: #2

Date: 2-7-91

692.083

Trav. No.	Delta P	Delta H	Meter Reading	DGM In	DGM Out	Hot Box	Impg Temp	Stack Temp	Vac
North A 1	.32	.80	692.82	80	79	240	68	154	2.5
③ 2	.35	.88	693.55	82	79	235	68	156	2.8
3	.45	1.13	694.77	83	80	243	68	155	3.0
8% ④ 4	.55	1.38	695.24	84	80	256	69	155	3.5
5	.72	1.80	696.23	86	80	264	67	154	4.0
8% ⑤ 6	.95	2.38	697.36	88	80	252	65	153	5.0
7	.95	2.38	698.50	89	80	249	65	153	5.0
7.8% ② 8	.85	2.13	699.62	90	80	244	66	153	5.0
9	.78	1.95	700.71	90	80	243	66	153	5.0
8.6% ⑩ 10	.75	1.88	701.76	91	80	242	66	153	5.0
North B 1	.43	1.08	702.59	86	80	235	67	154	3.5
③ 2	.47	1.18	<del>MISSA</del>	88	81	238	67	155	3.5
④ 3	.54	1.35	704.28	88	81	240	66	154	4.0
⑥ 4	.60	1.50	705.17	89	81	242	66	154	4.5
5	.75	1.88	706.07	91	82	250	66	156	4.5

Relationship: 2.5  
 Box #: 3 v: 9863 Delta H@: 1.9  
 Start Time: 16:50 End Time: \_\_\_\_\_  
 Pre Leak Ck: DEAD CFM @ 15 "Hg  
 Mid Leak Ck: \_\_\_\_\_ CFM @ \_\_\_\_\_ "Hg (Vol: \_\_\_\_\_)  
 Post Leak Ck: \_\_\_\_\_ CFM @ \_\_\_\_\_ "Hg  
 Pitot Leak Ck: DEAD @ 6" "H<sub>2</sub>O  
 Box Oper: RV Probe Oper: J

FILTER #

TRAVERSE DATA SHEET

Page 2 of 3

Sampling time per point: 1.5 min

Plant: OSCEOLA

Run #: RUN 2-3

Location: #2

Date: 2-7-91

	Trav. No.	Delta P	Delta H	Meter Reading	DGM In	DGM Out	Hot Box	Impg Temp	Stack Temp	Vac
7.2%	⑨ 6	1.70	4.25	missed	93	82	257	66	153	11.0
	7	1.10	2.75	708.72	94	82	264	67	155	8.5
7.2%	⑩ 8	.94	2.35	709.94	94	82	265	67	155	7.3
	9	.78	1.95	711.04	94	82	266	68	156	7.0
	⑪ 10	.75	1.88	712.11	94	82	265	68	156	6.5
7.0%	South A 1	.35	.88	712.84	87	82	244	68	156	4.0
	③ 2	.40	1.00	713.62	89	82	243	66	154	4.5
6.4%	3	.45	1.13	714.47	90	82	243	65	154	4.8
	④ 4	.50	1.25	715.30	90	83	243	64	155	5.0
	5	.70	1.75	716.23	90	83	243	63	154	6.0
7.5%	⑥ 6	.92	2.30	missed	91	83	241	61	154	7.5
	7	.90	2.25	718.45	92	83	239	59	155	7.5
	⑦ 8	.82	2.05	719.54	93	83	240	59	154	7.5
	9	.70	1.75	720.60	93	84	242	59	157	7.0
	⑧ 10	.67	1.68	721.617	93	84	243	60	155	7.0

Relationship: 2.5  
 Box #: 3 Y: .9863 Delta H@: 1.9  
 Start Time: \_\_\_\_\_ End Time: \_\_\_\_\_  
 Pre Leak Ck: DEAD CFM @ 15 "Hg  
 Mid Leak Ck: \_\_\_\_\_ CFM @ \_\_\_\_\_ "Hg (Vol: \_\_\_\_\_)  
 Post Leak Ck: DEAD CFM @ 11 "Hg  
 Pitot Leak Ck: DEAD @ 6 "H2O  
 Box Oper: RV Probe Oper: JL



Osceola Farms - Boiler #2  
Particulate Emissions Test Report

APPENDIX IX

EQUIPMENT CALIBRATION SHEETS

POST  
METER BOX CALIBRATION SHEET  
-----

BOX #: 3  
PRES BAR: 30.04

DATE: 2-11-91  
VACUUM: 15IN HG

RUN #	VOLUME WET	VOLUME DRY	DELTA H	DELTA H /13.6	PRES BAR (ABS)	TIME (MINS)
1	10.00	10.198	1.40	.103	30.14	16.22
2	10.00	10.336	1.40	.103	30.14	16.24
3	10.00	10.406	1.40	.103	30.14	16.26

RUN #	TEMP WET (°F)	TEMP DRY INLET	TEMP DRY OUT	TEMP DRY (AVG)	Y	DELTA H @
1	66.0	85.3	74.0	79.7	1.003	1.99
2	66.0	90.7	79.3	85.0	.9990	1.98
3	66.0	93.3	83.0	88.2	.9981	1.97
AVERAGE					1.000	1.98

PRE CAL Y = .9863      % DIFFERENCE = 1.36 %  
ALLOWABLE = 5.00 %

FORMULAS:

Y=

DELTA H @=

$$\frac{(V_w)(P_b)(T_d)}{(V_d)(P_b \text{ ABS})(T_w)} \times \frac{0.0317 (\text{DELTA H})}{(P_b)(T_d)} \times \left[ \frac{(T_w)(\text{TIME})}{(V_w)} \right]^2$$

CALIBRATION BY:

JIM JARDIN  
-----