

Note: This is a reference cited in *AP 42, Compilation of Air Pollutant Emission Factors, Volume I Stationary Point and Area Sources*. AP42 is located on the EPA web site at [www.epa.gov/ttn/chief/ap42/](http://www.epa.gov/ttn/chief/ap42/)


The file name refers to the reference number, the AP42 chapter and section. The file name "ref02\_c01s02.pdf" would mean the reference is from AP42 chapter 1 section 2. The reference may be from a previous version of the section and no longer cited. The primary source should always be checked.

**AP-42 Section Number:** 1.8

**Reference Number:** 59

**Title:** Okeelanta Corporation Particulate  
Emissions Test Report Boiler #10

January 1991



# Eastmount Engineering

Environmental Consultants — Air Quality Specialists

OKEELANTA CORPORATION  
COMPLIANCE PARTICULATE EMISSIONS TEST REPORT  
BOILER #10

PREPARED FOR:

Okeelanta Corporation  
Okeelanta Sugar Division  
South Bay, Florida 33493

CONCERNING:

Particulate Emissions Testing  
Okeelanta Corporation  
Boiler #10  
South Bay Florida Facility  
January 29 & 30, 1991

PREPARED BY:

Sean MacKay  
Project Director  
Eastmount Engineering, Inc.  
420 Main Street  
Walpole, MA 02081

  
Sean MacKay  
Project Director

28 FEB 91

Date

## TABLE OF CONTENTS

- 1.0 COMPENDIUM
- 2.0 STACK SCHEMATIC
- 3.0 TRAVERSE POINT LOCATION & SAMPLING TIME PER POINT
- 4.0 SAMPLING TRAIN AND ANALYTICAL TEST PROCEDURES
- 5.0 QUALITY CONTROL PROCEDURES

## APPENDIX

- I COMPUTER INPUT SHEETS
- II ISOKINETIC CALCULATION SHEETS
- III ENTHALPY CALCULATION SHEETS
- IV HEAT INPUT CALCULATION SHEETS
- V EMISSION CALCULATION SHEETS
- VI NOMENCLATURE SHEETS
- VII FIELD DATA SHEETS - UNIT OPERATING CONDITIONS
- VIII FIELD DATA SHEETS - STACK TESTING
- IX EQUIPMENT CALIBRATION SHEETS

Okeelanta Corporation - Boiler #10  
 Particulate Emissions Test Report

1.0 COMPENDIUM

Eastmount Engineering Inc., conducted a Compliance Particulate Emissions Test Program on Unit #10 at Okeelanta Corporation's South Bay, Florida facility on January 29 and 30, 1991. The test program consisted of a series of three EPA Method 5 test runs. A series of four Method 5 tests were performed on the December 18 and 19, 1990. Results of this December testing lead Eastmount to believe that the steam production was actually higher than the steam production shown on the chart. As a result, Ernesto Alfonso of Okeelanta Corporation performed a complete loop calibration of the steam flow and measurement system. A 6.75 % error was found and corrected. Eastmount then re-tested Unit #10 on January 29 and 30, 1991. A full description of the calibration on the flow measurement system can be found in Appendix IX of this report. Results of the December, 1990 testing are available upon request.

All testing was conducted in strict accordance with the Environmental Protection Agency's Reference Methods 1 through 5 as found in the Federal Register (40 CFR 60) as amended and were consistent with the State of Florida Department of Environmental Regulation's guidelines.

The purpose of this test was to determine compliance with the rules of the Department of Environmental Regulation (DER), Chapter 17-2.600 Air Pollution, Section 2.05 Prohibitive Acts, Subsection 6, Stationary Sources, Table II, Emission Limiting Standards.

During testing the boiler was burning bagasse as fuel. Boiler No. 10 is rated at 125,000 pounds of steam per hour. Results of the test program indicate Boiler No. 10 to be in compliance with the Florida DER emission standards. The following table summarizes the emission results, emission standards and boiler operating conditions.

RUN#	DATE	EMISSION RATE		ALLOWABLE		LOAD #/HR	% OF 125 KPH
		#/MMBtu	#/HR	#MMBtu	#/HR		
1	01-29-91	.194	37.03	.200	38.10	93171	74.5%
2	01-30-91	.183	37.60	.200	41.15	101100	80.9%
3	01-30-91	.192	37.43	.200	39.08	96000	76.8%
3	RUN AVG.	.190	37.35	.200	39.44	96757	77.4%

1.0 COMPENDIUM (cont.)


Sean MacKay, Project Director, was in charge of and responsible for all stack testing, conducted all calculations and maintained chain of custody of all samples. Brian Gibson operated the meter box and performed the field laboratory aspects of the program. Mark Wescott located the probe at the proper traverse point locations and assisted where required. Mr. Kenneth Tucker and Mr. Sherrel Culliver of the Florida Department of Environmental Regulation observed the stack testing and boiler operations. Mr. Alberto Padrone was the boiler room superintendent. Mr. George Devane was responsible for boiler operation and acquisition of all pertinent process data.

2.0 STACK SCHEMATIC

OKEELANTA CORPORATION  
 UNIT # 10  
 SOUTH BAY, FLORIDA FACILITY

The following is a schematic of the stack which services Boiler #10 at Okeelanta Corporation's South Bay, Florida facility.

Defined are the sampling port locations, interior stack dimensions and distances from the ports to the nearest upstream and downstream interferences.




DISTANCE UPSTREAM FROM FLOW DISTURBANCE (A)	4'
DISTANCE DOWNSTREAM FROM FLOW DISTURBANCE (B)	16'
DIAMETER OF PORT SLEEVE (C)	4"
LENGTH OF PORT SLEEVE (D)	3.5"
NUMBER OF PORTS	2
INTERNAL DIAMETER OF STACK AT SAMPLING PORTS	7.5'

Drawing not to scale

3.0 NUMBER OF TRAVERSE POINTS AND SAMPLING TIME PER POINT

OKEELANTA CORPORATION  
 UNIT # 10  
 SOUTH BAY, FLORIDA FACILITY



Minimum number of traverse points for particulate traverses.

Distance A = 4' or 0.5 diameters.

Distance B = 16' or 2.1 diameters.

In accordance with Method 1, 24 traverse points are needed.

In order to sample for a minimum of one hour and draw at least 30 cubic feet, each traverse point was sampled for 2.5 minutes.

Okeelanta Corporation - Boiler #10  
Particulate Emissions Test Report

3.0 NUMBER OF TRAVERSE POINTS AND SAMPLING TIME PER POINT

OKEELANTA CORPORATION  
UNIT # 10  
SOUTH BAY, FLORIDA FACILITY

DIAMETER OF STACK: 7.5 FEET  
PORT SLEEVE LENGTH: 3 INCHES

TRAVERSE POINT	DISTANCE % OF DIAMETER	DISTANCE (INCHES)	PROBE MARK (INCHES)
1	2.1	1.9	5.4
2	6.7	6.0	9.5
3	11.8	10.6	14.1
4	17.7	15.9	19.4
5	25.0	22.5	26.0
6	35.6	32.0	35.5
7	64.4	57.9	61.5
8	75.0	67.5	71.0
9	82.3	74.1	77.6
10	88.2	79.4	82.9
11	93.3	84.0	87.5
12	97.9	88.1	91.6

#### 4.0 SAMPLING TRAIN AND ANALYTICAL TEST PROCEDURES

The following is a description of the sampling train and specifications of particulate collection media used in the tests.

##### 1. EMISSION SAMPLING EQUIPMENT

The specific train used during this test is one manufactured by Research Appliance Company (RAC). The design specifications of this train meets all the requirements of Environmental Protection Agency's Method 5 as found in the Federal Regulations under Section 40 CFR 60 as amended. The following is a description of the individual pieces of equipment used:

Nozzle - The nozzle was of seamless stainless steel tubing construction of the button hook design. A range of sizes suitable for isokinetic sampling was available. All nozzles were calibrated before testing. A nozzle calibration sheet may be found in the calibration section of this report.

Probe - An 10 foot steel probe with a stainless steel liner was used.

Heating System - The filter temperature was maintained by enclosing the filter in a hot box capable of maintaining the temperature at 248 °F  $\pm$ 25 °F. This temperature was monitored by use of a thermocouple in the hot box.

Pitot Tube - A type S pitot tube attached to the probe was used to monitor the stack gas velocity. Since the pitot tube meets all the dimensional criteria set forth in Method 2 of 40 CFR 60, a coefficient of 0.84 has been used.

Filter Holder - A borosilicate glass type filter holder with frit support was used.

Condenser - Four impingers connected in series, with ground glass leak-free fittings were used as the condenser. The first, third and fourth impingers were of the Greenburg-Smith design, modified by replacing the tip with a 1/2" glass tube extending to about 1/2" from the bottom of the flask. The second impinger was of the Greenburg-Smith design with the standard tip.

Metering System - A vacuum gauge, micromanometer, inclined manometer, leak-free pump, calibrated thermocouples and a calibrated dry gas meter were the basic components used to meter the dry gas through the system.

#### 4.0 SAMPLING TRAIN AND ANALYTICAL TEST PROCEDURES (cont.)

Gas Density Determination - An ORSAT type combustion analyzer, capable of measuring CO<sub>2</sub>, O<sub>2</sub> and CO was used to determine the molecular weight of the flue gas. An integrated proportional sample was taken at each of the traverse points in order to assure that the total test span was covered. The ORSAT analysis was conducted immediately following each test run.

#### 2. SAMPLING AND ANALYTICAL PROCEDURES

All sampling and analytical procedures were conducted in strict accordance with the methods prescribed in Methods 1 through 5 of the Code of Federal Regulations as found in 40 CFR 60 as amended. The following is the sequence of events that occur both prior to and during the actual stack test.

Traverse Points - The traverse points were calculated in accordance with Method 1 and the probe was marked accordingly.

Static Pressure - The static pressure was checked and recorded.

Preliminary Traverse - A preliminary traverse was conducted. Readings included the pressure drops and stack gas temperatures.

Nomograph - Once all of the above information had been obtained, the nomograph was set up for the actual test to correlate the isokinetic relationships.

Barometric Pressure - Barometric pressure was obtained by use of an aneroid barometer at the test site.

##### Sampling Train Set-Up

- (a) The pre-weighed filter was placed in the filter holder and visually checked.
- (b) 100 ml of water was placed in the first two impingers.
- (c) Approximately 200 grams of silica gel was placed in the fourth impinger. (Exact weights were logged on the field data sheets).
- (d) Crushed ice was placed around the impingers.
- (e) Once assembly of the entire train was completed, the probe and heater box were turned on.

Pre-test Leak Check - Once the heater box was at the desired temperature for testing, the system was leak checked at 15 inches of vacuum. A leakage rate of less than 0.02 CFM had to be achieved before testing commenced.

Final Check - Once everything was ready to go, the plant was checked to assure that it was running at desired capacity.

4.0 SAMPLING TRAIN AND ANALYTICAL TEST PROCEDURES (cont.)

Sampling - Isokinetic sampling as described in Method 5 then took place.

Post-test Leak Check - Upon completion of each test run, the system was leak checked at the highest vacuum recorded during that run. All leak checks were less than 0.02 CFM and considered acceptable.

Sample Recovery - Because of the importance of proper sample recovery procedures, details of the sample recovery can be found in the Quality Control Procedures Section of this report.

Isokinetics - Once all sample recovery was completed and the amount of moisture collected had been determined, calculations were conducted to determine the percent isokinetics of the test run.

Operating Data Sheets - All pertinent operating data were logged throughout the testing period by plant personnel.

## 5.0 QUALITY CONTROL PROCEDURES

The following is a description of the procedures used for maintaining the integrity of samples collected, including the chain of custody and quality control assurance of filters and acetone wash.

Pre-test preparation consisted of the filters being desiccated at  $68 \pm 10$  °F at ambient pressure for at least twenty four (24) hours. At intervals of at least six (6) hours, the filters were re-weighed until a constant weight was achieved  $\pm 0.5$  mg change from the previous weighing. These pre-marked filters were then put into petri dishes and sealed. All filters used during testing were put into a carrying case for transport to the job site. A list of the filters and tare weights was available prior to testing.

After each test run, the filter and any particles which may have adhered to the filter holder gasket were carefully removed from the filter holder and placed into its identified petri dish container. This container was then labeled with the run number and date.

Taking care to see that particulate on the outside of the probe or other exterior surface did not get into the sample, particulate matter from the probe liner, nozzle, probe fittings, and front half of the filter holder were acetone washed into a sample container. This container was then sealed. The run number, date, and a mark indicating the level of the acetone wash in the bottle was recorded on the bottle.

Both the petri dish containing the filter and the bottle containing the acetone wash were transported to Eastmount Engineering's laboratory.

Once at the laboratory, each filter was weighed and then put back into its individual container. The container was then placed in a desiccator for at least twenty four (24) hours and then weighed. At intervals of at least six (6) hours, the filters were re-weighed until a constant weight was achieved  $\pm 0.5$  mg change from the previous weighing.

The levels marked on the bottles containing the acetone wash were checked to confirm that no leakage occurred during transport. The contents were then transferred into a pre-tared beaker and evaporated to dryness. Once this had been accomplished, the beaker was placed in a desiccator for at least twenty four (24) hours and then weighed. At intervals of at least six (6) hours, the beaker was re-weighed until a constant weight of  $\pm 0.5$  mg change from the previous weighing was achieved.

All calculations were conducted in strict accordance with 40 CFR 60 (See Calculation Sheets in report).

APPENDIX I

COMPUTER INPUT SHEETS

INPUT DATA SHEET

---

PLANT: OKEELANTA  
 LOCATION: UNIT 10

RUN #: C 10R-1  
 DATE : 01-29-91

Ds (FT) 7.5

Dn (IN) .250

FILTER#	3614	TRAV PT	VEL HEAD	SQ ROOT	DELTA H	DRYGAS IN	DRYGAS OUT	STACK TEMP
PIT COEFF	.84	A1	.80	.89	2.48	81	79	140
IMP-1 (INT)	100	2	.71	.84	2.20	82	79	139
		3	.56	.75	1.74	84	80	139
		4	.40	.63	1.24	85	80	140
IMP-2 (INT)	100	5	.21	.46	.65	85	80	140
		6	.11	.33	.34	85	81	139
IMP-3 (INT)	0	7	.27	.52	.84	86	81	140
		8	.54	.73	1.67	87	82	140
IMP-4 (INT)	500.0	9	.65	.81	2.02	90	82	140
		10	.77	.88	2.39	91	83	139
IMP-1 (FIN)	254	11	.83	.91	2.57	92	83	140
		12	.90	.95	2.79	93	84	139
IMP-2 (FIN)	116	B1	.77	.88	2.39	91	85	140
		2	.75	.87	2.33	92	85	140
IMP-3 (FIN)	2	3	.62	.79	1.92	93	86	140
		4	.47	.69	1.46	93	86	139
IMP-4 (FIN)	516.0	5	.33	.57	1.02	93	86	139
		6	.21	.46	.65	92	86	140
% CO2	10.3	7	.14	.37	.43	91	87	141
% O2	9.9	8	.23	.48	.71	90	86	140
		9	.45	.67	1.39	92	87	138
% CO	0	10	.66	.81	2.05	92	87	139
		11	.92	.96	2.85	93	88	138
P BAR	30.08	12	1.02	1.01	3.16	96	88	140
P STK	.20							
NO. PTS	24							
TEST LNGTH	60							
END METER	525.848							
	.235							
INT METER	486.800							
BEGIN TIME:	14:30							
END TIME:	15:40							
AVERAGE			.56	.72	1.72	89.5	83.8	139.5

INPUT DATA SHEET

---

PLANT: OKEELANTA  
 LOCATION: UNIT 10

RUN #: C 10R-2  
 DATE : 01-30-91

Ds (FT)	7.5							
Dn (IN)	.250							
FILTER#	3613	TRAV	VEL	SQ	DELTA	DRYGAS	DRYGAS	STACK
PIT COEFF	.84	PT	HEAD	ROOT	H	IN	OUT	TEMP
IMP-1 (INT)	100	A1	.80	.89	2.48	76	75	141
		2	.85	.92	2.64	78	75	140
		3	.60	.77	1.86	82	76	140
IMP-2 (INT)	100	4	.42	.65	1.30	83	77	140
		5	.21	.46	.65	83	78	141
IMP-3 (INT)	0	6	.10	.32	.31	82	78	140
		7	.26	.51	.81	83	78	141
IMP-4 (INT)	500.0	8	.53	.73	1.64	84	79	140
		9	.65	.81	2.02	86	79	143
IMP-1 (FIN)	258	10	.76	.87	2.36	87	80	140
		11	.81	.90	2.51	89	81	141
IMP-2 (FIN)	116	12	.87	.93	2.70	90	82	141
		B1	.67	.82	2.08	82	82	139
IMP-3 (FIN)	1	2	.70	.84	2.17	82	84	140
		3	.60	.77	1.86	82	84	138
IMP-4 (FIN)	514.9	4	.45	.67	1.40	83	86	139
		5	.34	.58	1.05	83	86	141
% CO2	10.1	6	.23	.48	.71	83	87	141
		7	.12	.35	.37	83	86	142
% O2	10.1	8	.20	.45	.62	83	87	141
		9	.37	.61	1.15	83	86	141
% CO	0	10	.70	.84	2.17	83	85	141
		11	.87	.93	2.70	84	88	143
P BAR	30.08	12	1.00	1.00	3.10	84	91	141
P STK	.20							
NO. PTS	24							
TEST LNGTH	60							
END METER	569.222							
	.274							
INT METER	530.800							
BEGIN TIME:	09:30							
END TIME:	11:20							
AVERAGE			.55	.71	1.69	83.3	82.1	140.6

INPUT DATA SHEET

---

PLANT: OKEELANTA  
 LOCATION: UNIT 10

RUN #: C 10R-3  
 DATE : 01-30-91

Ds (FT)	7.5							
Dn (IN)	.250							
FILTER#	3615	TRAV	VEL	SQ	DELTA	DRYGAS	DRYGAS	STACK
PIT COEFF	.84	PT	HEAD	ROOT	H	IN	OUT	TEMP
IMP-1 (INT)	100	A1	.83	.91	2.57	83	83	140
		2	.78	.88	2.42	83	87	141
		3	.59	.77	1.83	83	88	142
IMP-2 (INT)	100	4	.38	.62	1.18	83	89	140
		5	.24	.49	.74	84	89	143
IMP-3 (INT)	0	6	.11	.33	.34	84	88	144
		7	.28	.53	.87	84	89	143
IMP-4 (INT)	500.0	8	.52	.72	1.61	85	90	143
		9	.70	.84	2.17	85	91	144
IMP-1 (FIN)	274	10	.83	.91	2.57	86	93	144
		11	.90	.95	2.79	87	95	143
IMP-2 (FIN)	116	12	.93	.96	2.88	88	96	143
		B1	.72	.85	2.23	88	92	143
IMP-3 (FIN)	2	2	.75	.87	2.32	89	94	141
		3	.64	.80	1.98	89	95	141
IMP-4 (FIN)	516.5	4	.43	.66	1.33	89	96	142
		5	.32	.57	.99	89	95	142
% CO2	10.4	6	.21	.46	.65	89	94	141
		7	.14	.37	.43	90	94	142
% O2	9.8	8	.25	.50	.77	90	94	142
		9	.38	.62	1.18	90	95	142
% CO	0	10	.63	.79	1.95	91	97	141
		11	.86	.93	2.67	91	98	143
P BAR	30.06	12	.97	.98	3.01	91	100	143
P STK	.20							
NO. PTS	24							
TEST LNGTH	60							
END METER	608.511							
	.22							
INT METER	569.488							
BEGIN TIME:	12:20							
END TIME:	13:30							
AVERAGE			.56	.72	1.73	87.1	92.6	142.2

APPENDIX II

ISOKINETIC CALCULATION SHEETS

ISOKINETIC CALCULATION SHEET

---

PLANT: OKEELANTA  
 LOCATION: UNIT 10

RUN #: C 10R-1  
 DATE : 01-29-91

TS (`F)= 139.5	% CO2= 10.3	VM (CF) = 38.813
TS (`R)= 599.5	% O2= 9.9	DELTA H (ABS)= 30.21
TM (`F)= 86.7	% CO= 0	PS (ABS) = 30.09
TM (`R)= 546.7	% N2= 79.8	SQRT DELTA P = .719206
VI(TOT)= 188.0	CP= .84	AREA NOZZLE = .000341

---

	Y = 1.001
VM STD = 17.64	$\frac{(VM)(Y)(DELTA H ABS)}{(TM)} = 37.87$ DSCF
VW STD = .04707 (VI TOT)	= 8.85 CF
BWO = $\frac{VW STD}{VW STD + VM STD}$	= .189
BWO = MOISTURE FROM STEAM TABLES	= .193
VI TOT = ADJUSTED TO SATURATION VOLUME=	N/A ML
1-BWO = 1 - BWO	= .811
Md (DRY) = .44 (% CO2) +.32 (% O2) +.28 (% CO) +.28 (% N2)	= 30.04 LBS/LB MOLE
Ms (WET) = MD (1-BWO) + 18 (BWO)	= 27.76 LBS/LB MOLE
G = SQRT (TS / PS / MS)	= .85
VS = 85.49(CP)(G)(SQRT DELTA P)	= 43.8 FPS
H = 0.002669 (VI TOT)	= .50
J = (DELTA H ABS)(VM)(Y) / (TM)	= 2.15
K = (H) + (J)	= 2.65
% ISO = $\frac{(TS) (K) (1.667)}{(TIME) (VS) (PS) (AN)}$	= 98.3

ISOKINETIC CALCULATION SHEET  
-----

PLANT: OKEELANTA  
LOCATION: UNIT 10

RUN #: C 10R-2  
DATE : 01-30-91

TS (`F)= 140.6	% CO2= 10.1	VM (CF) =	38.148
TS (`R)= 600.6	% O2= 10.1	DELTA H (ABS)=	30.20
TM (`F)= 82.7	% CO= 0	PS (ABS) =	30.09
TM (`R)= 542.7	% N2= 79.8	SQRT DELTA P =	.712366
VI(TOT)= 189.9	CP= .84	AREA NOZZLE =	.000341

		Y =	1.001
VM STD =	17.64	$\frac{(VM)(Y)(DELTA H ABS)}{(TM)}$	= 37.49 DSCF
VW STD =	.04707	(VI TOT)	= 8.94 CF
BWO =	$\frac{VW STD}{VW STD + VM STD}$		= .193
BWO =	MOISTURE FROM STEAM TABLES		= .198
VI TOT =	ADJUSTED TO SATURATION VOLUME=		N/A ML
1-BWO =	1 - BWO		= .807
Md (DRY) =	.44 (% CO2) +.32 (% O2) +.28 (% CO) +.28 (% N2)		= 30.02 LBS/LB MOLE
Ms (WET) =	MD (1-BWO) + 18 (BWO)		= 27.71 LBS/LB MOLE
G =	SQRT (TS / PS / MS)		= .85
VS =	85.49(CP)(G)(SQRT DELTA P)		= 43.4 FPS
H =	0.002669 (VI TOT)		= .51
J =	(DELTA H ABS)(VM)(Y) / (TM)		= 2.13
K =	(H) + (J)		= 2.63
% ISO =	$\frac{(TS) (K) (1.667)}{(TIME) (VS) (PS) (AN)}$		= 98.6

ISOKINETIC CALCULATION SHEET

---

PLANT: OKEELANTA  
 LOCATION: UNIT 10

RUN #: C 10R-3  
 DATE : 01-30-91

*Avg = 14.1*

*Avg = 9.9*

TS (°F) =	142.2	% CO2 =	10.4	VM (CF) =	38.803
TS (°R) =	602.2	% O2 =	9.8	DELTA H (ABS) =	30.19
TM (°F) =	89.9	% CO =	0	PS (ABS) =	30.07
TM (°R) =	549.9	% N2 =	79.8	SQRT DELTA P =	.720924
VI (TOT) =	208.5	CP =	.84	AREA NOZZLE =	.000341

---

		Y =	1.001
VM STD =	17.64	$\frac{(VM)(Y)(DELTA H ABS)}{(TM)}$	37.62 DSCF
VW STD =	.04707 (VI TOT)		9.81 CF
BWO =	$\frac{VW STD}{VW STD + VM STD}$		.207
BWO =	MOISTURE FROM STEAM TABLES		.207
VI TOT =	ADJUSTED TO SATURATION VOLUME =		208.4 ML
1-BWO =	1 - BWO		.793
Md (DRY) =	.44 (% CO2) +.32 (% O2) +.28 (% CO) +.28 (% N2)	$\frac{\text{---}}{\text{---}}$	30.06 LBS/LB MOLE
Ms (WET) =	MD (1-BWO) + 18 (BWO)	$\frac{\text{---}}{\text{---}}$	27.56 LBS/LB MOLE
G =	SQRT (TS / PS / MS)		.85
VS =	85.49(CP)(G)(SQRT DELTA P)		44.1 FPS
H =	0.002669 (VI TOT)		.56
J =	(DELTA H ABS)(VM)(Y) / (TM)		2.13
K =	(H) + (J)		2.69
% ISO =	$\frac{(TS)(K)(1.667)}{(TIME)(VS)(PS)(AN)}$		99.4

APPENDIX III

ENTHALPY CALCULATION SHEETS

ENTHALPY CALCULATION SHEET  
-----

PLANT : OKEELANTA  
LOCATION: UNIT 10

RUN #: C 10R-1  
DATE : 01-29-91

	STEAM PRESSURE	STEAM TEMPERATURE	FEED WATER TEMPERATURE
	350	680	260
	355	680	
	340	680	
	335	680	
	340	680	
	345	680	
 AVERAGE	 344.2 PSIG	 680.0	 260.0
 P ABS =	 358.9 PSIA		
 ENTHALPY @	 700 'F AND	 360 PSIA =	 1364.1
ENTHALPY @	600 'F AND	360 PSIA =	1309.9
ENTHALPY @	680.0 'F AND	360 PSIA =	1353.3
 ENTHALPY OF FEED WATER =		 228.65	
 AVERAGE ENTHALPY =		 1124.6	 BTU/LB OF STEAM

ENTHALPY CALCULATION SHEET  
-----

PLANT : OKEELANTA  
LOCATION: UNIT 10

RUN #: C 10R-2  
DATE : 01-30-91

	STEAM PRESSURE	STEAM TEMPERATURE	FEED WATER TEMPERATURE
	340	660	260
	340	670	
	350	680	
	340	670	
	350	680	
	330	660	
	350	670	
	350	670	
	340	670	
AVERAGE	343.3 PSIG	670.0	260.0
P ABS =	358.0 PSIA		
ENTHALPY @	700 'F AND	360 PSIA =	1364.1
ENTHALPY @	600 'F AND	360 PSIA =	1309.9
ENTHALPY @	670.0 'F AND	360 PSIA =	1347.8
ENTHALPY OF FEED WATER =		228.65	
AVERAGE ENTHALPY =		1119.2	BTU/LB OF STEAM

ENTHALPY CALCULATION SHEET  
-----

PLANT : OKEELANTA  
LOCATION: UNIT 10

RUN #: C 10R-3  
DATE : 01-30-91

	STEAM PRESSURE	STEAM TEMPERATURE	FEED WATER TEMPERATURE
	355	670	260
	350	670	
	345	670	
	355	670	
	355	680	
	350	670	
AVERAGE	351.7 PSIG	671.7	260.0
P ABS =	366.4 PSIA		
ENTHALPY @	700 'F AND	370 PSIA =	1363.6
ENTHALPY @	600 'F AND	370 PSIA =	1309.1
ENTHALPY @	671.7 'F AND	370 PSIA =	1348.2
ENTHALPY OF FEED WATER =		228.65	
AVERAGE ENTHALPY =		1119.5	BTU/LB OF STEAM

APPENDIX IV

HEAT INPUT CALCULATION SHEETS

HEAT INPUT CALCULATION SHEET  
-----

PLANT: OKEELANTA  
LOCATION: UNIT 10

RUN #: C 10R-1  
DATE: 01-29-91

STEAM INTEGRATOR READINGS	TIME	INTEGRATOR FACTOR
-----		-----
END	508097	15: 40
BEGIN	507010	14: 30
NET	1087	X 100 / 70 MINS =
		93171
93171 LBS/HR STEAM / 55% EFF. = 169403 EQUIV.		
169403 LBS/HR STEAM X 1125 BTU/LB = 190.5 BTU(e6)/HR		

OIL INTEGRATOR READINGS	TIME	GALS/HR
-----		-----
END	0	14: 40
BEGIN	0	13: 30
NET	0	GALLONS 70 MINS = 0 GPH
0 GPH X 150,000 BTU/GAL (EST) = 0 BTU(e6)/HR		

ALLOWABLE EMISSIONS  
-----

BAGASSE	190.5	-	0	X	.2	=	38.1	LBS/HR
OIL			0	X	.1	=	0	LBS/HR
TOTAL						=	38.1	LBS/HR

HEAT INPUT CALCULATION SHEET

-----

PLANT: OKEELANTA  
 LOCATION: UNIT 10

RUN #: C 10R-2  
 DATE: 01-30-91

STEAM INTEGRATOR READINGS	TIME	INTEGRATOR FACTOR
-----	----	-----
525800 526143 526552	10:30 10:50 11:20	100
524822 525945 526380	9:30 10:40 11:10	LBS/HR STEAM
978 198 172	X 100 / 80 MINS	= 101100
101100 LBS/HR STEAM / 55% EFF.	=	183818 EQUIV.
183818 LBS/HR STEAM X 1119 BTU/LB	=	205.7 BTU(e6)/HR

OIL INTEGRATOR READINGS	TIME	GALS/HR
-----	----	-----
END 0	14:40	
BEGIN 0	13:30	
NET 0	GALLONS 80	MINS = 0 GPH
0 GPH X 150,000 BTU/GAL (EST)	=	0 BTU(e6)/HR

ALLOWABLE EMISSIONS

-----

BAGASSE	205.7	-	0	X	.2	=	41.1 LBS/HR
OIL			0	X	.1	=	.0 LBS/HR
TOTAL						=	41.1 LBS/HR

HEAT INPUT CALCULATION SHEET

-----

PLANT: OKEELANTA  
 LOCATION: UNIT 10

RUN #: C 10R-3  
 DATE: 01-30-91

	STEAM INTEGRATOR READINGS	TIME	INTEGRATOR FACTOR
	-----	----	-----
END	528541	13: 30	100
BEGIN	527421	12: 20	LBS/HR STEAM
NET	----- 1120	----- / 70	----- 96000
	X 100	MINS =	
96000	LBS/HR STEAM /	55% EFF. =	174545 EQUIV.
174545	LBS/HR STEAM X	1120 BTU/LB =	195.4 BTU(e6)/HR

	OIL INTEGRATOR READINGS	TIME	GALS/HR
	-----	----	-----
END	0	14: 40	
BEGIN	0	13: 30	
NET	----- 0	----- 70	----- GPH
	GALLONS	MINS =	0
0 GPH	X 150,000	BTU/GAL (EST) =	0 BTU(e6)/HR

ALLOWABLE EMISSIONS

-----

BAGASSE	195.4	-	0	X	.2	=	39.1	LBS/HR
OIL			0	X	.1	=	.0	LBS/HR
TOTAL						=	39.1	LBS/HR

APPENDIX V  
EMISSION CALCULATION SHEETS

EMISSION CALCULATION SHEET  
-----

PLANT: OKEELANTA  
LOCATION: UNIT 10

RUN #: C 10R-1  
DATE: 01-29-91

	SAMPLES		BLANKS	
	FILTER	BEAKER	FILTER	ACETONE
	-----	-----	-----	-----
NO. :	3614	200	3611	211
FINAL:	.7324	78.4936	.6265	79.1329
TARE :	.6138	78.4846	.6264	79.1327
	-----	-----	-----	-----
NET :	.1186	.0090	.0001	.0002/200ML

---

				VOLUME OF RINSE	265
WEIGHT =	127.60				
RESIDUE =	- .27				
Mn =	127.34 Mg	AS =	44.2	SQ FT	
Qs =	3600(1-BWO)(VS)(AS)(17.64)(PS)/(TS)		=	4994189	DSCFH
CS =	(2.205 X 10 <sup>-6</sup> ) (Mn) / (VM STD)		=	7.414e-6	LBS/SCF
CS' =	0.0154 (Mn) / (VM STD)		=	.05	GRAINS / SCF
PMR =	(QS) (CS)		=	37.03	LBS/HR
LOAD=	MILLIONS OF BTU / HOUR INPUT		=	190.5	BTU e6 / HR
CS =	LBS / MILLION BTu		=	.194	LBS / BTu e6
ALLOWABLE			=	38.10	LBS/HR
			=	.200	LBS / BTu e6

EMISSION CALCULATION SHEET  
-----

PLANT: OKEELANTA  
LOCATION: UNIT 10

RUN #: C 10R-2  
DATE: 01-30-91

	SAMPLES		BLANKS	
	FILTER -----	BEAKER -----	FILTER -----	ACETONE -----
NO. :	3613	205	3611	211
FINAL:	.7341	75.8671	.6265	79.1329
TARE :	.6114	75.8598	.6264	79.1327
NET :	.1227	.0073	.0001	.0002/200ML

---

		VOLUME OF RINSE		290
WEIGHT =	130.00			
RESIDUE =	.29			
Mn =	129.71 Mg	AS =	44.2	SQ FT
Qs =	3600(1-BWO)(VS)(AS)(17.64)(PS)/(TS)		=	4928368 DSCFH
CS =	(2.205 X 10 <sup>-6</sup> ) (Mn) / (VM STD)		=	7.628e-6 LBS/SCF
CS' =	0.0154 (Mn) / (VM STD)		=	.05 GRAINS / SCF
PMR =	(QS) (CS)		=	37.60 LBS/HR
LOAD=	MILLIONS OF BTU / HOUR INPUT		=	205.7 BTU e6 / HR
CS =	LBS / MILLION BTu		=	.183 LBS / BTu e6
ALLOWABLE			=	41.15 LBS/HR
			=	.200 LBS / BTu e6

EMISSION CALCULATION SHEET  
-----

PLANT: OKEELANTA  
LOCATION: UNIT 10

RUN #: C 10R-3  
DATE: 01-30-91

	SAMPLES		BLANKS	
	FILTER -----	BEAKER -----	FILTER -----	ACETONE -----
NO. :	3615	209	3611	211
FINAL:	.7387	76.3050	.6265	79.1329
TARE :	.6124	76.3009	.6264	79.1327
NET :	.1263	.0041	.0001	.0002/200ML

---

VOLUME OF RINSE 185

WEIGHT = 130.40  
RESIDUE = - .19

Mn = 130.22 Mg                      AS = 44.2 SQ FT

Qs =  $3600(1-BWO)(VS)(AS)(17.64)(PS)/(TS)$  = 4903763 DSCFH  
*Aug = 4,942,107*

CS =  $(2.205 \times 10^{-6})(Mn) / (VM \text{ STD})$  =  $7.633e-6$  LBS/SCF

CS' =  $0.0154 (Mn) / (VM \text{ STD})$  = .05 GRAINS / SCF

PMR = (QS) (CS) = 37.43 LBS/HR

LOAD= MILLIONS OF BTU / HOUR INPUT = 195.4 BTU e6 / HR  
*Aug = 147.2*

CS = LBS / MILLION BTU = .192 LBS / BTu e6

ALLOWABLE = 39.08 LBS/HR  
= .200 LBS / BTu e6

APPENDIX VI

NOMENCLATURE SHEETS

Okeelanta Corporation - Boiler #10  
Particulate Emissions Test Report

NOMENCLATURE SHEET

PARTICULATE EMISSION TEST

Ar	Acetone residue - result of Blank evaporation.
AREA NOZZLE	Area of the nozzle in square feet.
AS	Area of the stack in square feet.
BDL	Below detectable limits
BWO	The amount of moisture in the flue gas.
% CO	Percent of carbon monoxide in the flue gas.
% CO2	Percent of carbon dioxide in the flue gas.
Cp	Pitot tube coefficient.
CS	The concentration in the stack in pounds per standard cubic foot.
Cs'	The concentration in the stack in grains per standard cubic foot.
DELTA H	The meter orifice differential.
DELTA H(ABS)	The meter orifice differential, absolute conditions in inches of mercury.
Dn (IN)	Diameter of the nozzle in inches.
DRY GAS IN	Temperature of the dry gas meter inlet degrees Farenheight.
DRY GAS OUT	Temperature of the dry gas meter outlet degrees Farenheight.
Ds (FT)	Diameter of the stack in feet.
E	The emission rate in pounds per million Btu derived by using F-Factor.
E (Heat Input)	The emission rate in pounds per million Btu derived by use of calculated heat input.
END METER	The dry gas meter reading at the end of the test.
F factor	The theoretical amount of air in dry standard cubic feet (DSCF) needed to combust a million Btu's worth of fuel.

NOMENCLATURE (cont'd)

Filter Catch	The amount of particulate captured on the filter during testing.
INT METER	The dry gas meter reading at the beginning of the test.
Md (DRY)	The dry molecular weight of the flue gas in pounds per pound mole.
MN	The amount of particulate collected by washing the nozzle, probe, and front half of the glassware, reported in milligrams.
MN'	The milligrams of particulate collected minus the blank.
Ms (WET)	Wet or actual molecular weight of the flue gas in pounds per pound mole.
% N2	The percent of nitrogen in the flue gas.
NO PTS	Number of traverse points.
% O2	Percent of oxygen in the flue gas.
P BAR	Barometric pressure at test location.
P STK	Static pressure of the stack in inches of water.
PMR	The emission rate in pounds per hour.
PS (ABS)	Absolute pressure conditions in the stack in inches of mercury.
Qs	The volumetric flow rate of the flue gas in dry standard cubic feet per hour.
SQ ROOT	The square root of each velocity head measurement.
SQRT DELTA P	The average of the square roots of the measured pressure drops.
Stack Temp or TS (°F)	The temperature of the stack in degrees Fahrenheit.
TS (°R)	The temperature of the stack in degrees Rankine.
T (Hot Box)	Temperature around the filter box, degrees Fahrenheit.
TM (°F)	Average temperature of the dry gas meter in degrees Fahrenheit.

Okeelanta Corporation - Boiler #10  
Particulate Emissions Test Report

NOMENCLATURE (cont'd)

TM (°R)	Average temperature of the dry gas meter in degrees Rankine.
VEL HEAD	The pressure drop measured across the pitot tubes.
VI (TOT)	The amount of water collected in the impingers in milliliters.
VM (CF)	The volume sampled through the dry gas meter in cubic feet.
VM STD	Volume sampled through the dry gas meter corrected to standard conditions.
VS	Velocity of the stack gas in feet per second.
VW STD	The amount of moisture collected, converted to standard cubic feet.
Y	Meter box calibration factor.
o	Sampling time in minutes.

APPENDIX VII

FIELD DATA SHEETS - UNIT OPERATING CONDITIONS





CAPACITY 125,000  
 INT. FACTOR 100  
 RUN # 10R-2

BOILER # 10

EVOLUTION COMPLIANCE TESTING  
 DATE: 7-30-97  
 TESTED BY: East Coast Eng

TIME	STEAM INTERGRATOR	OIL METER		STEAM PRESS.	TEMP.	CHART READING LBS/HR.	FEED WATER PRESS.	TEMP.	BOILER PRESSURE DROP				
		NORTH	SOUTH						OVERFIRE AIR PRESS.	AIR HEATER OUT	UNDERGRATE AIR PRESS.	WIND BOX PRESSURE	FURNACE PRESSURE
9:30	524822	1133540	107768	340	660	97,500	630	260		3.0	3.1	3.0	3.0
9:45	525058			340	670	100,000	650	"		1.4	1.4	1.4	1.4
10:00	525296			350	680	96,000	650	"		-1.0	1.0	1.5	1.0
10:15	525562		NONE	340	670	102,000	630	"		15.5	17.5	15.5	15.0
10:30	525800	1133540	107768	350	680	97,500	650	"					
10:40	525945	1133540	107768	330	660	90,000	620	"					
10:50	526143		NONE	350	670	90,000	640	"					
11:00	526380	1133540	107768	350	670	100,000	640	"					
11:20	526552	1133540	107768	340	670	90,000	640	"					

TEST RESULTS		COMMENTS:	
OIL USED	NONE	"A"	"B"
TOTAL TEST TIME	80	80	80
INTERGRATOR TIME	1348		
INTERGRATOR STEAM...	107,100 P.P.H.		
CHART AVERAGE	863,000 TOTAL		
I.D. FAN TURBINE	98,888 P.P.H.		
STACK TEMPERATURE	4800 °F		
GRATE TEMPERATURE	140 °F		
SCRUBBER WATER	EST 1000 G.P.M.		


Intergrator 928  
 1st stop 198  
 2nd stop 172  
 1348

- (1) Mill speed 80
- (2) using no oil burner
- (3) "A" Mill stop 10:30 (5 min)
- (4) Hot box short out (25 min)
- (5) "A" Mill stop 10:50 (5 min)

Allowed =  
 Actual =

PLANT READINGS BY *Ray DeWitt*  
 % OF CAPACITY





7 AM  
8 AM  
9 AM  
10 AM  
11 AM  
NOON  
1 PM  
2 PM  
3 PM  
4 PM  
5 PM

FISCHER & PORTER CO.  
WASHINGTON, D.C. 20001  
JAN 30 1968

100  
90  
80  
70  
60  
50  
40  
30  
20  
10  
0  
10  
20  
30  
40  
50  
60  
70  
80  
90  
100

WIND  
TEMP  
PRESS  
HUMIDITY  
SEA LEVEL  
SURFACE  
100  
90  
80  
70  
60  
50  
40  
30  
20  
10  
0  
10  
20  
30  
40  
50  
60  
70  
80  
90  
100

100  
90  
80  
70  
60  
50  
40  
30  
20  
10  
0  
10  
20  
30  
40  
50  
60  
70  
80  
90  
100

100  
90  
80  
70  
60  
50  
40  
30  
20  
10  
0  
10  
20  
30  
40  
50  
60  
70  
80  
90  
100

APPENDIX VIII

FIELD DATA SHEETS - STACK TESTING

FIELD DATA SHEET

GENERAL INFORMATION

Plant:	<u>OKEE/ANTA</u>	Run #:	<u>COMP 10R-1</u>
Location:	<u>UNIT 10</u>	Date:	<u>29 JAN 91</u>
Ds (ft):	<u>7.5</u>	No. Points:	<u>24</u>
Dn (in):	<u>.250</u>	Test Length:	<u>60 MIN</u>
Filter #:	<u>3614</u>	End Meter Reading:	<u>525.848</u>
Cp:	<u>.84</u>	Int Meter Reading:	<u>486.800</u>
P bar:	<u>30.08</u>	Begin Time:	<u>1430</u>
P stack:	<u>+ .2</u>	End Time:	<u>1540</u>

IMP-1 (INT)	<u>100 <math>\mu</math>L</u>	IMP-1 (FINAL)	<u>254</u>
IMP-2 (INT)	<u>100 ML</u>	IMP-2 (FINAL)	<u>116</u>
IMP-3 (INT)	<u>0 ML</u>	IMP-3 (FINAL)	<u>2</u>
IMP-4 (INT)	<u>500.0g</u>	IMP-4 (FINAL)	<u>515.0g</u>

	TEST 1	TEST 2	TEST 3
% CO <sub>2</sub>	<u>11.3</u>	_____	_____
% O <sub>2</sub>	<u>9.9</u>	_____	_____
% CO	<u>0</u>	_____	_____

Project Director:	<u>S. MacKay</u>	Field Laboratory:	<u>B. GIBSON</u>
Meter Box Operator:	<u>S. MacKay</u>	Chain of Custody:	<u>S. MacKay</u>
Probe Operator:	<u>M. Wescott</u>	Plant Coordinator:	<u>G. DEVANE</u>
Orsat Analyst:	<u>S. MacKay</u>	Agency Rep:	<u>C. CULLIVER</u>

Comments:

TRAVERSE DATA SHEET

Page 12 of 2

Sampling time per point: 2.5

Plant: OKFELANTA

Run #: COMP 10R-1

Location: UNIT 10

Date: 29 JAN 91

Trav. No.	Delta P	Delta H	Meter Reading	DGM In	DGM Out	Hot Box	Impg Temp	Stack Temp	Vac
<u>02</u>			<u>486.800</u>						
<u>A1</u>	<u>.80</u>	<u>2.48</u>	<u>489.87</u>	<u>81</u>	<u>79</u>	<u>249</u>	<u>62</u>	<u>140</u>	<u>2</u>
<u>9.7</u>									
<u>2</u>	<u>.71</u>	<u>2.20</u>	<u>491.06</u>	<u>82</u>	<u>79</u>	<u>262</u>	<u>61</u>	<u>139</u>	<u>2</u>
<u>3</u>	<u>.56</u>	<u>1.74</u>	<u>492.83</u>	<u>84</u>	<u>80</u>	<u>267</u>	<u>61</u>	<u>139</u>	<u>1</u>
<u>10.0</u>									
<u>4</u>	<u>.40</u>	<u>1.24</u>	<u>494.24</u>	<u>85</u>	<u>80</u>	<u>253</u>	<u>62</u>	<u>140</u>	<u>1</u>
<u>5</u>	<u>.21</u>	<u>.65</u>	<u>495.33</u>	<u>85</u>	<u>80</u>	<u>250</u>	<u>63</u>	<u>140</u>	<u>1</u>
<u>10.3</u>									
<u>6</u>	<u>.11</u>	<u>.34</u>	<u>496.08</u>	<u>85</u>	<u>81</u>	<u>259</u>	<u>64</u>	<u>139</u>	<u>1</u>
<u>7</u>	<u>.27</u>	<u>.84</u>	<u>497.17</u>	<u>86</u>	<u>81</u>	<u>263</u>	<u>62</u>	<u>140</u>	<u>1</u>
<u>8</u>	<u>.54</u>	<u>1.67</u>	<u>498.81</u>	<u>87</u>	<u>82</u>	<u>260</u>	<u>60</u>	<u>140</u>	<u>2</u>
<u>9</u>	<u>.65</u>	<u>2.02</u>	<u>500.60</u>	<u>90</u>	<u>82</u>	<u>264</u>	<u>59</u>	<u>140</u>	<u>2</u>
<u>10.3</u>									
<u>10</u>	<u>.77</u>	<u>2.39</u>	<u>502.51</u>	<u>91</u>	<u>83</u>	<u>261</u>	<u>60</u>	<u>139</u>	<u>3</u>
<u>11</u>	<u>.83</u>	<u>2.57</u>	<u>504.55</u>	<u>92</u>	<u>83</u>	<u>260</u>	<u>61</u>	<u>140</u>	<u>3</u>
<u>9.8</u>									
<u>12</u>	<u>.90</u>	<u>2.79</u>	<u>506.604</u>	<u>93</u>	<u>84</u>	<u>256</u>	<u>61</u>	<u>139</u>	<u>4</u>

Relationship: 3.1  
 Box #: 4 Y: 1.001 Delta H@: 2.03  
 Start Time: 1430 End Time: \_\_\_\_\_  
 Pre Leak CK: 0 CFM @ 15 "Hg  
 Mid Leak CK: \_\_\_\_\_ CFM @ \_\_\_\_\_ "Hg (Vol: \_\_\_\_\_)  
 Post Leak CK: \_\_\_\_\_ CFM @ \_\_\_\_\_ "Hg  
 Pitot Leak CK: 9000 @ 5 "H2O  
 Box Oper: SM Probe Oper: MW

TRAVERSE DATA SHEET

Page 2 of 2

Sampling time per point: 2.5

Plant: OKEELANTA

Run #: COMP 10R-1

Location: UNIT 10

Date: 29 JAN 91

	Trav. No.	Delta P	Delta H	Meter Reading	DGM In	DGM Out	Hot Box	Impg Temp	Stack Temp	Vac
				<del>506.839</del>						
9.9	B1	.77	2.39	508.78	91	85	245	63	140	3
	2	.75	2.33	510.68	92	85	252	61	140	3
	3	.62	1.92	512.54	93	86	251	62	140	2
10.1	4	.47	1.46	514.07	93	86	258	64	139	2
	5	.33	1.02	515.38	93	86	260	64	139	1
10.0	6	.21	.65	516.40	92	86	265	60	140	1
	7	.14	.43	517.25	91	87	262	59	141	1
	8	.23	.71	518.30	90	86	251	59	140	1
	9	.45	1.39	519.82	92	87	262	57	138	2
10.3	10	.66	2.05	521.59	92	87	266	57	139	3
	11	.92	2.85	523.67	93	88	252	56	138	5
9.9	12	1.02	3.16	525.848	96	88	242	56	140	6

Relationship: 3,1  
 Box #: \_\_\_\_\_ Y: \_\_\_\_\_ Delta H@: \_\_\_\_\_  
 Start Time: \_\_\_\_\_ End Time: \_\_\_\_\_  
 Pre Leak CK: \_\_\_\_\_ CFM @ \_\_\_\_\_ "Hg  
 Mid Leak CK: \_\_\_\_\_ CFM @ \_\_\_\_\_ "Hg (Vol: \_\_\_\_\_)  
 Post Leak CK: \_\_\_\_\_ CFM @ \_\_\_\_\_ "Hg  
 Pitot Leak CK: \_\_\_\_\_ @ \_\_\_\_\_ "H2O  
 Box Oper: \_\_\_\_\_ Probe Oper: \_\_\_\_\_

FIELD DATA SHEET

GENERAL INFORMATION

Plant: OKEE/ANTA Run #: COMP 10R-2  
Location: UNIT 10 Date: 30 JAN 91  
Ds (ft): 7.5 FT No. Points: 24  
Dn (in): .250 Test Length: 60 MIN  
Filter #: 3613 End Meter Reading: 569.222  
Cp: .84 Int Meter Reading: 530.800  
P bar: 30.08 Begin Time: 09:30  
P stack: .2 End Time: 11.20

IMP-1 (INT) 100 ML IMP-1 (FINAL) 258  
IMP-2 (INT) 100 ML IMP-2 (FINAL) 116  
IMP-3 (INT) 0 ML IMP-3 (FINAL) 1  
IMP-4 (INT) 500.0g IMP-4 (FINAL) BC-A-114-9514.9

	TEST 1	TEST 2	TEST 3
% CO2	<u>10.1</u>	_____	_____
% O2	<u>10.1</u>	_____	_____
% CO	<u>0</u>	_____	_____

Project Director: SEAN MACKAY Field Laboratory: GIBSON/MACKAY  
Meter Box Operator: BRIAN GIBSON Chain of Custody: S. Mac Kay  
Probe Operator: M. WESCOTT Plant Coordinator: G. DEJANE  
Orsat Analyst: S. MACKAY Agency Rep: C. CULLIVER

Comments: A' mill STOPPED TWICE DURING TESTING

TRAVERSE DATA SHEET

Page 2 of 2

Sampling time per point: 2.5

Plant: OKEELANTA

Run #: Comp 10R-2

Location: Unit 10

Date: 30 Jan 91

Trav. No.	Delta P	Delta H	Meter Reading	DGM In	DGM Out	Hot Box	Impg Temp	Stack Temp	Vac
10.0 B 1	.67	2.08	550.548	82	82	240	68	139	2
2	.70	2.17	554.3	82	84	245	60	140	2
10.7 3	.60	1.86	556.1	82	84	243	64	138	2
4	.45	1.40	557.6	83	86	248	63	139	1
10.5 5	.34	1.05	559.0	83	86	271	64	141	1
6	.23	0.71	560.1	83	87	248	65	141	1
10.0 7	.12	0.37	560.9	83	86	271	66	142	1
8	.20	.62	561.8	83	87	245	67	141	1
10.5 9	.37	1.15	563.2	83	86	241	67	141	2
10	.70	2.17	565.0	83	85	246	63	141	3
9.7 11	.87	2.70	567.6	84	88	260	63	143	5
12	1.0	3.1	569.222	84	91	261	65	141	5
10.23%									

Relationship: 3.1  
 Box #: 4 Y: 1.001 Delta H@: 2.03  
 Start Time: 1025 End Time: 1055  
 Pre Leak Ck: N/A CFM @ N/A "Hg  
 Mid Leak Ck: 0 CFM @ .15 "Hg (Vol: N/A)  
 Post Leak CK: 0 CFM @ 5 "Hg  
 Pitot Leak CK: 0 @ 0 "H2O  
 Box Oper: Gibson Probe Oper: Wescott

1110 start  
 T+ 4.18 stop      Restart 1040      T+20.23 stop

TRAVERSE DATA SHEET

Page 1 of 2

Sampling time per point: 2.5

Plant: OKEE LANTA

Run #: COMP 10R - 2

Location: UNIT 10

Date: 30 JAN 91

Trav. No.	Delta P	Delta H	Meter Reading	DGM In	DGM Out	Hot Box	Impg Temp	Stack Temp	Vac
			530.800						Ø
10.5	A1	.80	532.9	76	75	265	68	141	2
	2	.85	534.9	78	75	267	67	140	2
10.0	3	.60	536.6	82	76	269	68	140	2
	4	.42	538.2	83	77	267	68	140	1
10.1	5	.21	539.2	83	78	266	67	141	1
	6	.10	540.0	82	78	261	68	140	1
10.4	7	.26	541.0	83	78	255	67	141	1
	8	.53	542.5	84	79	260	66	140	1
9.6	9	.65	544.3	86	79	268	60	143	1.5
	10	.76	546.2	87	80	269	58	140	2
9.5	11	.81	548.2	89	81	267	60	141	3
	12	.87	550.274	90	82	262	61	141	3
10.0%									
19.47	cu ft								

Relationship: 3.1  
 Box #: 4 Y: 1.001 Delta H@: 2.03  
 Start Time: 0930 End Time: \_\_\_\_\_  
 Pre Leak Ck: Ø CFM @ 16 "Hg  
 Mid Leak Ck: Ø CFM @ 4 "Hg (Vol: \_\_\_\_\_)  
 Post Leak CK: N/A CFM @ N/A "Hg  
 Pitot Leak CK: OK @ 7.5 "H2O  
 Box Oper: Gibson Probe Oper: Wescott

FIELD DATA SHEET

GENERAL INFORMATION

Plant:	<u>OKEE/ANTA</u>	Run #:	<u>Comp 10R-3</u>
Location:	<u>UNIT 10</u>	Date:	<u>31 JAN 91</u>
Ds (ft):	<u>7.5</u>	No. Points:	<u>24</u>
Dn (in):	<u>.250</u>	Test Length:	<u>60 min</u>
Filter #:	<u>3615</u>	End Meter Reading:	<u>608.511</u>
Cp:	<u>.84</u>	Int Meter Reading:	<u>569.488</u>
P bar:	<u>30.06</u>	Begin Time:	<u>12:20</u>
P stack:	<u>.2</u>	End Time:	<u>13:36</u>
IMP-1 (INT)	<u>100 mL</u>	IMP-1 (FINAL)	<u>274</u>
IMP-2 (INT)	<u>100 mL</u>	IMP-2 (FINAL)	<u>116</u>
IMP-3 (INT)	<u>0 mL</u>	IMP-3 (FINAL)	<u>2</u>
IMP-4 (INT)	<u>500.0 g</u>	IMP-4 (FINAL)	<u>516.5</u>

	TEST 1	TEST 2	TEST 3
% CO2	<u>10.4</u>	_____	_____
% O2	<u>9.8</u>	_____	_____
% CO	<u>0</u>	_____	_____

Project Director:	<u>S. MacKay</u>	Field Laboratory:	<u>S. MacKay / Gibson</u>
Meter Box Operator:	<u>B. Gibson</u>	Chain of Custody:	<u>MacKay</u>
Probe Operator:	<u>M. Wescott</u>	Plant Coordinator:	<u>G. Devane</u>
Orsat Analyst:	<u>S. MacKay</u>	Agency Rep:	<u>C. Culliver</u>

Comments:

TRAVERSE DATA SHEET

Page 1 of 2

Sampling time per point: 2.5

Plant: Okeelanta

Run #: CR-3

Location: Unit 10

Date: 30 Jan 91

Trav. No.	Delta P	Delta H	569.488 Meter Reading 567.488	DGM In	DGM Out	Hot Box	Impg Temp	Stack Temp	Vac	
10.2	A 1	.83	2.57	571.6	83	83	240	68	140	2
	2	.78	2.42	573.5	83	87	256	68	141	2
10.0	3	.59	1.83	575.4	83	88	252	67	142	1
	4	.38	1.18	576.9	83	89	252	67	140	1
9.5	5	.24	0.74	577.5	84	89	249	68	143	1
	6	.11	.34	578.6	84	88	261	66	144	1
10.0	7	.28	.87	579.7	84	89	268	66	143	1
	8	.52	1.61	581.3	85	90	270	64	143	1
9.5	9	.70	2.17	583.2	85	91	243	64	144	2
	10	.83	2.57	585.2	86	93	268	63	144	2
10.4	11	.90	2.79	587.3	87	95	268	64	143	3
	12	.93	2.88	589.4	88	96	240	64	143	3

Relationship: 3.1  
 Box #: 4 Y: 1.001 Delta H@: 2.03  
 Start Time: 1230 End Time: \_\_\_\_\_  
 Pre Leak CK: 0 CFM @ 15"Hg  
 Mid Leak CK: 0 CFM @ 5"Hg (Vol: \_\_\_\_\_)  
 Post Leak CK: N/A CFM @ N/A"Hg  
 Pitot Leak CK: \_\_\_\_\_ @ \_\_\_\_\_"H2O  
 Box Oper: Gibson Probe Oper: Wescott

289.594



APPENDIX IX

EQUIPMENT CALIBRATION SHEETS

# OKEELANTA CORPORATION

6 MILES SOUTH OF SOUTH BAY  
POST OFFICE BOX 88  
SOUTH BAY, FLORIDA 33493

TELEPHONE: (407) 996-9072

TELEX: 803444

Eastmount Engineering Inc.  
Environmental Engineers

February 06, 1991

S. Joseph Mercadante President

Subject: Okeelanta Sugar Corporation  
Boiler Unit 10, 150,000 lbs/hr

In recent days while testing for compliance; you found some discrepancies between your test, and the steam production shown in the chart.

Following that day, we proceeded to a complete loop calibration of the steam flow and measurement, based on the attached spec. sheet.

Before re-calibration: Overall span was 142" H<sub>2</sub>O


On a 0 to 100% chart showed:

D/P cell trans in H <sub>2</sub> O:	0	68"	103"	120"	137"
Chart in %:	0	50	75	87.5	93
Eng. Units in ;bs/h:		75,000	108,500	126,750	145,000
After Correction:	0	68"	103"	120"	137"
		75,000	112,500	131,250	150,000

LBS/HR errors at chart's	75%=	4,000 lbs/hr
	87.5=	4,500 lbs/hr
	100 =	5,000 lbs/hr

Total Average= 4,500 lbs/hr

Error in % = 6.75

  
Ernesto Alfonso  
Instrument Department Head

EA/jh



ORIFICE PLATE NUMBER \_\_\_\_\_  
 TRANSMITTER NUMBER \_\_\_\_\_  
 SERVICE BOILER N<sup>o</sup> 10 & 11

COMPUTED BY JIM  
 DATE Jan. 8/80

		Engr	Metr	
0.	Unit system? 0=English; 1=Metric; 2=SI	0.0		
1.	Service? 0=Liquid; 1=Gas, steam	1.0		
2.	Tap type? 1=Fl; 2=Rad; 3=VC; 4=Cor; 5=Pipe.	1.0		
3.	Computed? 4=ΔP; 5=W; 6=d.	4.0		
4.	Meter differential - maximum ΔP	in.WC		137 Dry
5.	Flowrate W	lb/h		150,000.0000
6.	Orifice hole diameter d	in.		8.1165
7.	Pipe inside diameter D	in.		11.7500
8.	Fluid flowing density ρ <sub>f</sub>	lb/ft <sup>3</sup>		1/1.6040
9.	Fluid flowing viscosity μ	cP		0.0260
10.	Fluid specific heat ratio (1) k	-		1.3000
11.	Absolute upstream pressure (1) P <sub>1</sub>	psia		389.7 (350)
12.	Fluid flowing temperature T	°		650
13.	Thermal expansion coefficient x 10 <sup>6</sup> (2) α	°C <sup>-1</sup>		
14.	Drain/Venthole diameter (3) d <sub>h</sub>	in.		
15.	Temperature correction coefficient F <sub>T</sub>			1.0130
16.	Drain/Vent hole correction coefficient F <sub>h</sub>			
17.	Reynold's number correction coefficient F <sub>c</sub>			
18.	β ratio within 0.15 ≤ β ≤ 0.75 limits? 0=Y; 1=N			
19.	For compressible fluids: ΔP ≤ 25% P <sub>1</sub> ? 0=Y; 1=N			
20.	Orifice flow coefficient Kβ <sup>2</sup> -s			0.3270
21.	β ratio = d/D β			0.6908
22.	Gas expansion factor (4) Y <sub>1</sub>			0.9980
23.	Pipe Reynold's number at 100% of W R <sub>D</sub>			> 3 x 10 <sup>6</sup>
24.				
25.	Upstream - Downstream / SCHEDULE	21.17 - 9.00 /		SCH. 3
26.	Straightening Vanes			Yes

Notes: (1). Not required for liquids: enter 0.

(2) If unknown: enter 0; program assumes 17 for 316 SS.

POST  
METER BOX CALIBRATION SHEET  
-----

BOX #: 4  
PRES BAR: 30.02

DATE: 2-11-91  
VACUUM: 10IN HG

RUN #	VOLUME WET	VOLUME DRY	DELTA H	DELTA H /13.6	PRES BAR (ABS)	TIME (MINS)
1	10.00	10.089	1.95	.143	30.16	13.39
2	10.00	10.353	1.95	.143	30.16	13.73
3	10.00	10.333	1.95	.143	30.16	13.73

RUN #	TEMP WET (°F)	TEMP DRY INLET	TEMP DRY OUT	TEMP DRY (AVG)	Y	DELTA H @
1	65.0	85.7	80.0	82.8	1.020	1.87
2	65.0	87.7	81.7	84.7	.9973	1.96
3	65.0	88.7	82.3	85.5	1.001	1.96
AVERAGE					1.006	1.93

PRE CAL Y = 1.0010      % DIFFERENCE = .50 %  
ALLOWABLE = 5.00 %

FORMULAS:

Y=

DELTA H @=

$$\frac{(V w) (P b) (T d)}{(V d) (P b \text{ ABS}) (T w)} \quad 0.0317 \frac{(\text{DELTA H})}{(P b) (T d)} \quad * \quad \left[ \frac{(T w) (TIME)^2}{(V w)} \right]$$

S. MacKAY

CALIBRATION BY:

METER BOX CALIBRATION SHEET

BOX NUMBER: 4  
 PRESS BAR : 30.04

DATE: 10 SEPT 1990  
 DUE: 10 MAR 1991

RUN #	VOLUME WET	VOLUME DRY	DELTA H	DELTA H /13.6	PRES BAR (ABS)	TIME (MINS)
1	5	5.037	.50	.0368	30.08	13.80
2	5	5.043	1.00	.0735	30.11	9.55
3	10	10.190	1.50	.1103	30.15	15.34
4	10	10.273	2.00	.1471	30.19	13.46
5	10	10.330	3.00	.2206	30.26	11.69
6	10	10.400	4.00	.2941	30.33	9.64

RUN #	TEMP WET (°F)	TEMP DRY INLET	TEMP DRY OUT	TEMP DRY (AVG)	Y	DELTA H
1	69.3	82.3	77.3	79.8	1.011	2.09
2	69.7	83.7	78.3	81.0	1.010	2.00
3	70.0	86.7	80.3	83.5	1.003	1.93
4	70.0	89.3	82.7	86.0	.9979	1.97
5	69.3	91.7	83.3	87.5	.9940	2.21
6	69.0	94.7	85.3	90.0	.9900	1.99
AVERAGE					1.001	2.03

MAX % DEVIATION 1.10  
 ALLOWABLE % DEV 2.00

FORMULAS:

$$Y = \frac{(V_w)(P_b)(T_d)}{(V_d)(P_b \text{ ABS})(T_w)}$$

$$\text{DELTA H } \theta = \frac{0.0317 (\text{DELTA H})}{(P_b)(T_d)} * \left[ \frac{(T_w)(\text{TIME})^2}{(V_w)} \right]$$

CALIBRATION BY:

*From Computer Disc*  
 SCOTT LAWTON  
 BCLH  
 13-Feb-90

THERMOCOUPLE CALIBRATION SHEET  
-----

SET #: METER BOX #4 - IN

DATE: 9/11/85

STANDARD ('F)	THERMOCOUPLE ('F)	% DIFFERENCE
32	27	1.02
63	57	1.15
204	201	.45
	MAXIMUM	1.15
	ALLOWABLE	1.50

SET #: METER BOX #4 - OUT

DATE: 9/11/85

STANDARD ('F)	THERMOCOUPLE ('F)	% DIFFERENCE
32	27	1.02
63	57	1.15
204	202	.30
	MAXIMUM	1.15
	ALLOWABLE	1.50

CALIBRATION BY:

C. LODI  
\_\_\_\_\_

# CARL POE CO., INC.

99 REINERMAN ST. • HOUSTON, TEXAS 77007 • 713-861-3816

February 19, 1990

Eastmount Engineering  
420 Main  
Walpole, MA 02081

Dear Sirs:


This is to certify that your AL-19 American Wet Test Meter, serial no. P-468, has been calibrated with an American five foot bell prover, serial no. 2260. It is traceable to the Bureau of Standards, reference no. 106870, PI-TAPE.

Test Results are as follows:

<u>FLOW RATE</u>	<u>% OF ERROR</u>
60 CFH	+0.3%
30 CFH	0.0%
15 CFH	0.0%

Sincerely,

CARL POE CO., INC.



Carl W. Poe  
CWP/mp

**THERMOCOUPLE CALIBRATION SHEET**

---

SET #: 8'-1

DATE: 10-25-85

REFERENCE MERCURY/GLASS

STANDARD ('F)	THERMOCOUPLE ('F)	ABSOLUTE OF % DEVIATION
74	72	.37
210	205	.75
400	409	1.05
	<b>MAXIMUM DEVIATION</b>	<b>1.05</b>
	<b>ALLOWABLE</b>	<b>1.50</b>

SET #: 8.5'-1

DATE: 11-15-85

STANDARD ('F)	THERMOCOUPLE ('F)	ABSOLUTE OF % DEVIATION
66	63	.57
170	170	0
211.5	215	.52
	<b>MAXIMUM DEVIATION</b>	<b>.57</b>
	<b>ALLOWABLE</b>	<b>1.50</b>

**G. ZWILLING**

CALIBRATION BY: \_\_\_\_\_

NOZZLE CALIBRATION SHEET

PROJECT NAME: OKEE/ANTA

PROJECT NUMBER: 90 102

POINT#	NOZZLE# <sup>A/4-1</sup>	NOZZLE # <sup>1/4-2</sup>	NOZZLE#	NOZZLE #
1	<u>.305</u>	<u>.256</u>	_____	_____
2	<u>.305</u>	<u>.258</u>	_____	_____
3	<u>.305</u>	<u>.257</u>	_____	_____
AVG.	<u>.305</u>	<u>.257</u>	_____	_____

SEAN MacFARLANE  
CALIBRATED BY:

3 DEC 90  
DATE:

NOZZLE CALIBRATION SHEET

PROJECT NAME: OKEELENTA

PROJECT NUMBER: 90-102

POINT#	NOZZLE# <u>5/16-3</u>	NOZZLE # <u>5/16-14</u>	NOZZLE# <u>1/4-3</u>	NOZZLE # <u>1/4-1</u>
1	<u>.316</u>	<u>.313</u>	<u>.251</u>	<u>.250</u>
2	<u>.314</u>	<u>.312</u>	<u>.249</u>	<u>.251</u>
3	<u>.315</u>	<u>.311</u>	<u>.250</u>	<u>.251</u>
AVG.	<u>.315</u>	<u>.312</u>	<u>.250</u>	<u>.251</u>

SEAN MCKAY  
CALIBRATED BY:

3 DEC 90  
DATE:

47

DATE 04/24/91

FLORIDA DEPARTMENT OF ENVIRONMENTAL REGULATION  
PARTICULATE STACK TEST VERIFICATION  
DER METHOD 5

FACILITY NAME: OKEELANTA

APIS #

COMPANY CONDUCTING TEST: EASTMOUNT

TEST DATE 1 29 91

SOURCE DESCRIPTION: BOILER 10

STACK TEST DATA SUMMATION

		RUN1	RUN2	RUN3
1.H2O	(VOL.MEAS.),ML	188	189.9	208.5
2.H2O	(MASS MEAS.),GM	0	0	0
3.M'N	PARTICULATE WEIGHT, GM	.1273	.1297	.1302
4.V'M	VOLUME METERED,CF	38.813	38.148	38.803
5.Y	DRY GAS MTR. CALIB.FCTR.	1.001	1.001	1.001
6.RDP	AVG SQR D.P-SAMPLING	.72	.71	.72
7.DH	AVG DELTA H,IN.H2O	1.72	1.69	1.73
8.T'M	AVG MTR. TEMP,DEG.F	86.7	82.7	89.9
9.T'S	AVG STACK TEMP,DEG.F	139.5	140.6	142.2
10.P'SG	STACK PRESS,'HG(GAUGE)	.2	.2	.2
11.P'B	BAROMETRIC PRESS,'HG	30.08	30.08	30.06
13.D'N	ACTUAL NOZZLE DIAM,IN	.25	.25	.25
14.T	ACTUAL SAMPLE TIME,MIN	60	60	60
15.C'P	PITOT TUBE COEFFICIENT	.84	.84	.84
23.S/T	VALUE: SAMPLE PTS/TOT PTS	1	1	1

RUN	VOLUME SAMPLED' DSCF	MOISTURE CONTENT PERCENT	STACK VEL FPS	FLOW RATE DSCF/H	PERCENT ISO-KINETIC	ACTUAL EMISS LB/HR	ACTUAL EMISS LB/MBTU	ALLOW EMISS LB/MBTU
1	37.87	18.94	43.69	5,020,845	97.80	37.21	0.189	0.200
2	37.49	19.25	43.15	4,930,964	98.60	37.60	0.191	0.200
3	37.61	20.57	43.96	4,924,664	99.05	37.58	0.191	0.200
MEAN	37.66	19.59	43.60	4,958,824	98.48	37.46	0.190	0.200

SUMMARY

GENERAL:

REVIEWED BY AS  
ACTUAL A 'S = 44.2 SQ FT  
LAMINAR FLOW ASSUMED (<10 DEG YAW) (OR <20 DER)  
ACTUAL EMISS BASED ON HEAT INPUT = 196.966 MBTU/HR  
ALL REQUIRED LEAK TESTS ACCEPTABLE  
ASSUMED M 'D=30.0 (COMBUSTION GASES)

COMMENT.....

RUN 1 :

ACTUAL A 'N = .0003409 SQ FT  
P 'S = 30.28 IN HG

COMMENT.....

RUN 2 :

ACTUAL A 'N = .0003409 SQ FT  
P 'S = 30.28 IN HG

COMMENT.....

RUN 3 :

ACTUAL A 'N = .0003409 SQ FT  
P 'S = 30.26 IN HG  
OVERSATURATED CONDITIONS: SATURATION MOISTURE ASSUMED/GIVEN PG.1

COMMENT.....

OKEELANTA CORPORATION

8 MILES SOUTH OF SOUTH BAY  
POST OFFICE BOX 88  
SOUTH BAY, FLORIDA 33493

TELEPHONE: (407) 998-9072

TELEX: 803444

March 9, 1991

Palm Beach County Health Dept.  
Division of Environmental Service  
901 Evernia Street  
P.O. Box 29  
West Palm Beach, FL 33402

Attn: Mr. Randall Miller

Ref: Emission Test Reports

Dear Mr. Miller,

Please find attached the remaining of the emission test reports for boilers 10, 12, 14 and 15. The test reports for boilers 4, 5, 6 and 11 were previously mailed to you on February 27, 1991.

Please let me know if you need further information.

Sincerely,



P. A. Carreño  
Director of Mill &  
Refinery Operations

xc: Arthur Kirstein, III  
Frank Fernandez  
Roger King  
Pedro Alvarez  
David Knowls, Ft. Myers DER W/attachments

RECEIVED

MAR 13 1991

Division of Environmental Engineering  
PALM BEACH COUNTY  
HEALTH DEPARTMENT

442

Boiler #10  
Okeelanta

1-29-91

INPUT SHEET - REV:09/13/83 - PAGE 2 OF 2

ENTER THE FOLLOWING:

	RUN1	RUN2	RUN3
1. H2O COLLECTED (ONLY VOL. MEASURED), ML:	.....	.....	.....
2. H2O COLLECTED (WEIGHED PART ONLY), GM:	188.0	189.9	208.5
3. M'N PARTICULATE WEIGHT, GM:	127.3	129.7	130.2
4. V'M VOLUME METERED, CF:	38.813	38.803	38.803
5. Y DRY GAS METER CAL FACTOR:	1.001	1.001	1.001
6. RDP AVG SQR DELTA P (WHEN SAMPLING):	.72	.71	.72
7. DH AVG DELTA H, IN H2O:	1.72	1.69	1.73
8. T'M AVG METER TEMP, DEG F:	86.7	82.7	89.9
9. T'S AVG STACK TEMP, DEG F:	139.5	140.6	142.2
10. P'S* STACK PRESS, *IN ..... (40):	.20	.20	.20
11. P'B BAROMETRIC PRESS, IN HG:	30.08	30.08	30.06
12. D'N ACTUAL NOZZLE DIAMETER, IN.:	.250	.250	.250
14. T ACTUAL SAMPLE TIME, MIN:	60	60	60
15. C'P PITOT TUBE COEFFICIENT:	.84	.84	.84
OPTION ENTRIES:	190.5	205	195.4
17. ORSAT/FYRITE - %CO2:	.....	.....	.....
18. ORSAT/FYRITE - %O2:	.....	.....	.....
20. ORSAT/FYRITE (FOR C'S @ 50% E.A.) - %CO:	.....	.....	.....
19. SPECIFIC M'D ENTRIES:	.....	.....	.....
23. CYCLONIC (10-20 DEG) - AVG COS(YAW):	.....	.....	.....
26. CYC. (>20) - AVG(SQR D.P X COS(YAW)):	.....	.....	.....
24. PROCESS WT SOURCE - T/HR:	.....	.....	.....
22. LB/TON REGULATED - T/HR:	.....	.....	.....
27. LB/* REGULATED (* AS DEFINED) - */HR:	.....	.....	.....
29. LAM&CYC (?0) - VAL(SAMPLE PTS/TOT PTS):	.....	.....	.....

196.966