

Note: This is a reference cited in *AP 42, Compilation of Air Pollutant Emission Factors, Volume I Stationary Point and Area Sources*. AP42 is located on the EPA web site at www.epa.gov/ttn/chief/ap42/


The file name refers to the reference number, the AP42 chapter and section. The file name "ref02_c01s02.pdf" would mean the reference is from AP42 chapter 1 section 2. The reference may be from a previous version of the section and no longer cited. The primary source should always be checked.

AP-42 Section Number: 1.8

Reference Number: 62

Title: Okeelanta Corporation Particulate
Emissions Test Reprot Boiler #12

January 1991



Eastmount Engineering

Environmental Consultants — Air Quality Specialists

OKEELANTA CORPORATION
COMPLIANCE PARTICULATE EMISSIONS TEST REPORT
BOILER #12

PREPARED FOR:

Okeelanta Corporation
Okeelanta Sugar Division
South Bay, Florida 33493

CONCERNING:

Particulate Emissions Testing
Okeelanta Corporation
Boiler #12
South Bay Florida Facility
January 31 & February 1, 1991

PREPARED BY:

Sean MacKay
Project Director
Eastmount Engineering, Inc.
420 Main Street
Walpole, MA 02081

Sean MacKay
Sean MacKay
Project Director

28 FEB 91

Date

TABLE OF CONTENTS

- 1.0 COMPENDIUM
- 2.0 STACK SCHEMATIC
- 3.0 TRAVERSE POINT LOCATION & SAMPLING TIME PER POINT
- 4.0 SAMPLING TRAIN AND ANALYTICAL TEST PROCEDURES
- 5.0 QUALITY CONTROL PROCEDURES

APPENDIX

- I COMPUTER INPUT SHEETS
- II ISOKINETIC CALCULATION SHEETS
- III ENTHALPY CALCULATION SHEETS
- IV HEAT INPUT CALCULATION SHEETS
- V EMISSION CALCULATION SHEETS
- VI NOMENCLATURE SHEETS
- VII FIELD DATA SHEETS - UNIT OPERATING CONDITIONS
- VIII FIELD DATA SHEETS - STACK TESTING
- IX EQUIPMENT CALIBRATION SHEETS

Okeelanta Corporation - Boiler #12
Particulate Emissions Test Report

1.0 COMPENDIUM

Eastmount Engineering Inc., conducted a Compliance Particulate Emissions Test Program on Unit #12 at Okeelanta Corporation's South Bay, Florida facility on January 31 and February 1, 1991. The test program consisted of a series of three EPA Method 5 test runs.

All testing was conducted in strict accordance with the Environmental Protection Agency's Reference Methods 1 through 5 as found in the Federal Register (40 CFR 60) as amended and were consistent with the State of Florida Department of Environmental Regulation's guidelines.

The purpose of this test was to determine compliance with the rules of the Department of Environmental Regulation (DER), Chapter 17-2.600 Air Pollution, Section 2.05 Prohibitive Acts, Subsection 6, Stationary Sources, Table II, Emission Limiting Standards.

During testing the boiler was burning bagasse and oil as fuel. Boiler No. 12 is rated at 150,000 pounds of steam per hour. Results of the test program indicate Boiler No. 12 to be in compliance with the Florida DER emission standards. The following table summarizes the emission results, emission standards and boiler operating conditions.

RUN#	DATE	EMISSION RATE		ALLOWABLE		LOAD #/HR	% OF 150 KPH
		#/MMBtu	/HR	#MMBtu	/HR		
1	01-31-91	.164	42.58	.185	48.16	127938	85.3%
2	01-31-91	.137	34.04	.187	46.49	122480	81.7%
3	02-01-91	.158	40.38	.185	47.32	126086	84.1%
3 RUN AVG.		.153	39.00	.186	47.32	125501	83.7%


Sean MacKay, Project Director, was in charge of and responsible for all stack testing, conducted all calculations and maintained chain of custody of all samples. Mark Wescott operated the meter box and performed the field laboratory aspects of the program. Brian Gibson located the probe at the proper traverse point locations and assisted where required. Mr. Sherrel Culliver of the Florida Department of Environmental Regulation observed the stack testing and boiler operations. Mr. Alberto Padrone was the boiler room superintendent. Mr. George Devane was responsible for boiler operation and acquisition of all pertinent process data.

2.0 STACK SCHEMATIC

OKEELANTA CORPORATION
UNIT # 12
SOUTH BAY, FLORIDA FACILITY

The following is a schematic of the stack which services Boiler #12 at Okeelanta Corporation's South Bay, Florida facility.

Defined are the sampling port locations, interior stack dimensions and distances from the ports to the nearest upstream and downstream interferences.




DISTANCE UPSTREAM FROM FLOW DISTURBANCE (A)	4'
DISTANCE DOWNSTREAM FROM FLOW DISTURBANCE (B)	16'
DIAMETER OF PORT SLEEVE (C)	4"
LENGTH OF PORT SLEEVE (D)	3.5"
NUMBER OF PORTS	2
INTERNAL DIAMETER OF STACK AT SAMPLING PORTS	7.5'

Drawing not to scale

Okeelanta Corporation - Boiler #12
 Particulate Emissions Test Report

3.0 NUMBER OF TRAVERSE POINTS AND SAMPLING TIME PER POINT

OKEELANTA CORPORATION
 UNIT # 12
 SOUTH BAY, FLORIDA FACILITY



Minimum number of traverse points for particulate traverses.

Distance A = 4' or 0.5 diameters.

Distance B = 16' or 2.1 diameters.

In accordance with Method 1, 24 traverse points are needed.

In order to sample for a minimum of one hour and draw at least 30 cubic feet, each traverse point was sampled for 2.5 minutes.

Okeelanta Corporation - Boiler #12
Particulate Emissions Test Report

3.0 NUMBER OF TRAVERSE POINTS AND SAMPLING TIME PER POINT

OKEELANTA CORPORATION
UNIT # 12
SOUTH BAY, FLORIDA FACILITY

DIAMETER OF STACK: 7.5 FEET
PORT SLEEVE LENGTH: 3 INCHES

TRAVERSE POINT	DISTANCE % OF DIAMETER	DISTANCE (INCHES)	PROBE MARK (INCHES)
1	2.1	1.9	5.4
2	6.7	6.0	9.5
3	11.8	10.6	14.1
4	17.7	15.9	19.4
5	25.0	22.5	26.0
6	35.6	32.0	35.5
7	64.4	57.9	61.5
8	75.0	67.5	71.0
9	82.3	74.1	77.6
10	88.2	79.4	82.9
11	93.3	84.0	87.5
12	97.9	88.1	91.6

4.0 SAMPLING TRAIN AND ANALYTICAL TEST PROCEDURES

The following is a description of the sampling train and specifications of particulate collection media used in the tests.

1. EMISSION SAMPLING EQUIPMENT

The specific train used during this test is one manufactured by Research Appliance Company (RAC). The design specifications of this train meets all the requirements of Environmental Protection Agency's Method 5 as found in the Federal Regulations under Section 40 CFR 60 as amended. The following is a description of the individual pieces of equipment used:

Nozzle - The nozzle was of seamless stainless steel tubing construction of the button hook design. A range of sizes suitable for isokinetic sampling was available. All nozzles were calibrated before testing. A nozzle calibration sheet may be found in the calibration section of this report.

Probe - An 10 foot steel probe with a stainless steel liner was used.

Heating System - The filter temperature was maintained by enclosing the filter in a hot box capable of maintaining the temperature at $248 \text{ } ^\circ\text{F} \pm 25 \text{ } ^\circ\text{F}$. This temperature was monitored by use of a thermocouple in the hot box.

Pitot Tube - A type S pitot tube attached to the probe was used to monitor the stack gas velocity. Since the pitot tube meets all the dimensional criteria set forth in Method 2 of 40 CFR 60, a coefficient of 0.84 has been used.

Filter Holder - A borosilicate glass type filter holder with frit support was used.

Condenser - Four impingers connected in series, with ground glass leak-free fittings were used as the condenser. The first, third and fourth impingers were of the Greenburg-Smith design, modified by replacing the tip with a 1/2" glass tube extending to about 1/2" from the bottom of the flask. The second impinger was of the Greenburg-Smith design with the standard tip.

Metering System - A vacuum gauge, micromanometer, inclined manometer, leak-free pump, calibrated thermocouples and a calibrated dry gas meter were the basic components used to meter the dry gas through the system.

4.0 SAMPLING TRAIN AND ANALYTICAL TEST PROCEDURES (cont.)

Gas Density Determination - An ORSAT type combustion analyzer, capable of measuring CO₂, O₂ and CO was used to determine the molecular weight of the flue gas. An integrated proportional sample was taken at each of the traverse points in order to assure that the total test span was covered. The ORSAT analysis was conducted immediately following each test run.

2. SAMPLING AND ANALYTICAL PROCEDURES

All sampling and analytical procedures were conducted in strict accordance with the methods prescribed in Methods 1 through 5 of the Code of Federal Regulations as found in 40 CFR 60 as amended. The following is the sequence of events that occur both prior to and during the actual stack test.

Traverse Points - The traverse points were calculated in accordance with Method 1 and the probe was marked accordingly.

Static Pressure - The static pressure was checked and recorded.

Preliminary Traverse - A preliminary traverse was conducted. Readings included the pressure drops and stack gas temperatures.

Nomograph - Once all of the above information had been obtained, the nomograph was set up for the actual test to correlate the isokinetic relationships.

Barometric Pressure - Barometric pressure was obtained by use of an aneroid barometer at the test site.

Sampling Train Set-Up

- (a) The pre-weighed filter was placed in the filter holder and visually checked.
- (b) 100 ml of water was placed in the first two impingers.
- (c) Approximately 200 grams of silica gel was placed in the fourth impinger. (Exact weights were logged on the field data sheets).
- (d) Crushed ice was placed around the impingers.
- (e) Once assembly of the entire train was completed, the probe and heater box were turned on.

Pre-test Leak Check - Once the heater box was at the desired temperature for testing, the system was leak checked at 15 inches of vacuum. A leakage rate of less than 0.02 CFM had to be achieved before testing commenced.

Final Check - Once everything was ready to go, the plant was checked to assure that it was running at desired capacity.

4.0 SAMPLING TRAIN AND ANALYTICAL TEST PROCEDURES (cont.)

Sampling - Isokinetic sampling as described in Method 5 then took place.

Post-test Leak Check - Upon completion of each test run, the system was leak checked at the highest vacuum recorded during that run. All leak checks were less than 0.02 CFM and considered acceptable.

Sample Recovery - Because of the importance of proper sample recovery procedures, details of the sample recovery can be found in the Quality Control Procedures Section of this report.

Isokinetics - Once all sample recovery was completed and the amount of moisture collected had been determined, calculations were conducted to determine the percent isokinetics of the test run.

Operating Data Sheets - All pertinent operating data were logged throughout the testing period by plant personnel.

5.0 QUALITY CONTROL PROCEDURES

The following is a description of the procedures used for maintaining the integrity of samples collected, including the chain of custody and quality control assurance of filters and acetone wash.

Pre-test preparation consisted of the filters being desiccated at 68 ± 10 °F at ambient pressure for at least twenty four (24) hours. At intervals of at least six (6) hours, the filters were re-weighed until a constant weight was achieved ± 0.5 mg change from the previous weighing. These pre-marked filters were then put into petri dishes and sealed. All filters used during testing were put into a carrying case for transport to the job site. A list of the filters and tare weights was available prior to testing.

After each test run, the filter and any particles which may have adhered to the filter holder gasket were carefully removed from the filter holder and placed into its identified petri dish container. This container was then labeled with the run number and date.

Taking care to see that particulate on the outside of the probe or other exterior surface did not get into the sample, particulate matter from the probe liner, nozzle, probe fittings, and front half of the filter holder were acetone washed into a sample container. This container was then sealed. The run number, date, and a mark indicating the level of the acetone wash in the bottle was recorded on the bottle.

Both the petri dish containing the filter and the bottle containing the acetone wash were transported to Eastmount Engineering's laboratory.

Once at the laboratory, each filter was weighed and then put back into its individual container. The container was then placed in a desiccator for at least twenty four (24) hours and then weighed. At intervals of at least six (6) hours, the filters were re-weighed until a constant weight was achieved ± 0.5 mg change from the previous weighing.

The levels marked on the bottles containing the acetone wash were checked to confirm that no leakage occurred during transport. The contents were then transferred into a pre-tared beaker and evaporated to dryness. Once this had been accomplished, the beaker was placed in a desiccator for at least twenty four (24) hours and then weighed. At intervals of at least six (6) hours, the beaker was re-weighed until a constant weight of ± 0.5 mg change from the previous weighing was achieved.

All calculations were conducted in strict accordance with 40 CFR 60 (See Calculation Sheets in report).

Okeelanta Corporation - Boiler #12
Particulate Emissions Test Report

APPENDIX I

COMPUTER INPUT SHEETS

INPUT DATA SHEET

PLANT: OKEELANTA
 LOCATION: UNIT 12

RUN #: COMP-1
 DATE : 01-31-91

Ds (FT) 7.5

Dn (IN) .305

FILTER#	3760	TRAV PT	VEL HEAD	SQ ROOT	DELTA H	DRYGAS IN	DRYGAS OUT	STACK TEMP
PIT COEFF	.84	A1	.18	.42	1.24	80	79	138
IMP-1 (INT)	100	2	.24	.49	1.66	79	79	138
		3	.25	.50	1.72	83	79	139
IMP-2 (INT)	100	4	.27	.52	1.86	85	80	139
		5	.26	.51	1.80	86	80	139
IMP-3 (INT)	0	6	.23	.48	1.59	87	81	139
		7	.23	.48	1.59	87	82	139
IMP-4 (INT)	500.0	8	.24	.49	1.66	89	83	138
		9	.24	.49	1.66	89	83	140
IMP-1 (FIN)	254	10	.24	.49	1.66	90	84	138
		11	.24	.49	1.66	91	84	139
IMP-2 (FIN)	120	12	.25	.50	1.72	91	85	137
		B1	.22	.47	1.52	90	86	138
IMP-3 (FIN)	2	2	.24	.49	1.66	90	86	137
		3	.26	.51	1.80	92	87	138
IMP-4 (FIN)	512.0	4	.27	.52	1.86	93	87	139
		5	.26	.51	1.80	94	88	137
% CO2	12.2	6	.24	.49	1.66	94	88	139
		7	.25	.50	1.73	95	89	140
% O2	8.0	8	.26	.51	1.80	95	89	140
		9	.28	.53	1.93	96	90	139
% CO	0	10	.28	.53	1.93	97	90	140
		11	.27	.52	1.56	97	92	139
P BAR	30.06	12	.26	.51	1.80	97	91	139
P STK	.15							
NO. PTS	24							
TEST LNGTH	60							
END METER	687.772							
	.190							
INT METER	647.427							
BEGIN TIME:	11:30							
END TIME:	12:35							
AVERAGE			.25	.50	1.70	90.3	85.1	138.7

INPUT DATA SHEET

PLANT: OKEELANTA
 LOCATION: UNIT 12

RUN #: COMP-2
 DATE : 01-31-91

Ds (FT)	7.5							
Dn (IN)	.305							
FILTER#	3761	TRAV	VEL	SQ	DELTA	DRYGAS	DRYGAS	STACK
PIT COEFF	.84	PT	HEAD	ROOT	H	IN	OUT	TEMP
		A1	.20	.45	1.40	85	83	138
IMP-1 (INT)	100	2	.22	.47	1.54	86	84	140
		3	.26	.51	1.82	87	84	140
IMP-2 (INT)	100	4	.27	.52	1.90	88	84	140
		5	.26	.51	1.82	90	86	139
IMP-3 (INT)	0	6	.23	.48	1.61	90	85	140
		7	.22	.47	1.54	91	86	139
IMP-4 (INT)	500.0	8	.23	.48	1.61	92	88	140
		9	.23	.48	1.61	92	86	140
IMP-1 (FIN)	254	10	.24	.49	1.68	92	87	140
		11	.23	.48	1.61	93	87	139
IMP-2 (FIN)	125	12	.23	.48	1.61	92	88	141
		B1	.23	.48	1.61	89	87	141
IMP-3 (FIN)	2	2	.24	.49	1.68	91	88	143
		3	.25	.50	1.75	91	87	144
IMP-4 (FIN)	515.5	4	.26	.51	1.82	92	88	144
		5	.25	.50	1.78	93	88	144
% CO2	12.1	6	.24	.49	1.68	94	89	143
		7	.25	.50	1.75	94	89	143
% O2	8.1	8	.25	.50	1.75	96	90	141
		9	.25	.50	1.75	95	90	143
% CO	0	10	.25	.50	1.75	95	90	142
		11	.25	.50	1.75	95	90	143
P BAR	30.06	12	.26	.51	1.82	96	91	143
P STK	.15							
NO. PTS	24							
TEST LNPTH	60							
END METER	728.351							
	.395							
INT METER	688.150							
BEGIN TIME:	13:45							
END TIME:	15:00							
AVERAGE			.24	.49	1.69	91.6	87.3	141.3

INPUT DATA SHEET

PLANT: OKEELANTA
 LOCATION: UNIT 12

RUN #: COMP-3
 DATE : 02-01-91

Ds (FT)	7.5							
Dn (IN)	.305							
FILTER#	3762	TRAV	VEL	SQ	DELTA	DRYGAS	DRYGAS	STACK
PIT COEFF	.84	PT	HEAD	ROOT	H	IN	OUT	TEMP
		A1	.29	.54	2.03	72	71	139
IMP-1 (INT)	100	2	.31	.56	2.17	73	71	138
		3	.35	.59	2.45	76	72	139
IMP-2 (INT)	100	4	.37	.61	2.59	78	73	139
		5	.35	.59	2.45	79	73	140
IMP-3 (INT)	0	6	.33	.57	2.31	80	73	140
		7	.31	.56	2.17	81	75	138
IMP-4 (INT)	500.0	8	.32	.57	2.24	82	75	138
		9	.32	.57	2.24	83	76	138
IMP-1 (FIN)	270	10	.32	.57	2.24	83	76	140
		11	.30	.55	2.10	84	77	138
IMP-2 (FIN)	125	12	.30	.55	2.10	84	77	140
		B1	.23	.48	1.61	82	79	139
IMP-3 (FIN)	3	2	.29	.54	2.03	84	80	137
		3	.31	.56	2.17	85	80	140
IMP-4 (FIN)	515.2	4	.33	.57	2.31	88	81	140
		5	.33	.57	2.31	88	81	140
% CO2	11.7	6	.30	.55	2.10	89	82	139
		7	.32	.57	2.24	89	82	138
% O2	8.5	8	.35	.59	2.45	90	83	138
		9	.36	.60	2.52	90	83	139
% CO	0	10	.36	.60	2.52	91	84	138
		11	.27	.52	1.89	90	84	139
P BAR	30.10	12	.15	.39	1.05	89	84	139
P STK	.15							
NO. PTS	24							
TEST LNGTH	60							
END METER	774.680							
	.134							
INT METER	729.520							
BEGIN TIME:	11:45							
END TIME:	12:55							
AVERAGE			.31	.56	2.18	83.8	78.0	138.9

ISOKINETIC CALCULATION SHEET

PLANT: OKEELANTA
LOCATION: UNIT 12

RUN #: COMP-2
DATE : 01-31-91

TS (`F)= 141.3	% CO2= 12.1	VM (CF) = 39.806
TS (`R)= 601.3	% O2= 8.1	DELTA H (ABS)= 30.18
TM (`F)= 89.5	% CO= 0	PS (ABS) = 30.07
TM (`R)= 549.5	% N2= 79.8	SQRT DELTA P = .491321
VI(TOT)= 196.5	CP= .84	AREA NOZZLE = .000507

	Y = 1.001
VM STD = 17.64	$\frac{(VM)(Y)(DELTA H ABS)}{(TM)} = 38.61$ DSCF
VW STD = .04707 (VI TOT)	= 9.25 CF
BWO = $\frac{VW STD}{VW STD + VM STD}$	= .193
BWO = MOISTURE FROM STEAM TABLES	= .202
VI TOT = ADJUSTED TO SATURATION VOLUME	= N/A ML
1-BWO = 1 - BWO	= .807
Md (DRY) = .44 (% CO2) +.32 (% O2) +.28 (% CO) +.28 (% N2)	= 30.26 LBS/LB MOLE
Ms (WET) = MD (1-BWO) + 18 (BWO)	= 27.89 LBS/LB MOLE
G = SQRT (TS / PS / MS)	= .85
VS = 85.49(CP)(G)(SQRT DELTA P)	= 29.9 FPS
H = 0.002669 (VI TOT)	= .52
J = (DELTA H ABS)(VM)(Y) / (TM)	= 2.19
K = (H) + (J)	= 2.71
% ISO = $\frac{(TS) (K) (1.667)}{(TIME) (VS) (PS) (AN)}$	= 99.4

ISOKINETIC CALCULATION SHEET

PLANT: OKEELANTA
 LOCATION: UNIT 12

RUN #: COMP-1
 DATE : 01-31-91

TS (`F)= 138.7	% CO2= 12.2	VM (CF) = 40.155
TS (`R)= 598.7	% O2= 8.0	DELTA H (ABS)= 30.19
TM (`F)= 87.7	% CO= 0	PS (ABS) = 30.07
TM (`R)= 547.7	% N2= 79.8	SQRT DELTA P = .497851
VI(TOT)= 188.0	CP= .84	AREA NOZZLE = .000507

		Y = 1.001
VM STD = 17.64	(VM)(Y)(DELTA H ABS) ----- (TM)	= 39.08 DSCF
VW STD = .04707 (VI TOT)		= 8.85 CF
BWO =	VW STD ----- VW STD + VM STD	= .185
BWO =	MOISTURE FROM STEAM TABLES	= .189
VI TOT =	ADJUSTED TO SATURATION VOLUME=	N/A ML
1-BWO =	1 - BWO	= .815
Md (DRY) =	.44 (% CO2) +.32 (% O2) +.28 (% CO) +.28 (% N2) -----	= 30.27 LBS/LB MOLE
Ms (WET) =	MD (1-BWO) + 18 (BWO) -----	= 28.01 LBS/LB MOLE
G =	SQRT (TS / PS / MS)	= .84
VS =	85.49(CP)(G)(SQRT DELTA P)	= 30.1 FPS
H =	0.002669 (VI TOT)	= .50
J =	(DELTA H ABS)(VM)(Y) / (TM)	= 2.22
K =	(H) + (J)	= 2.72
% ISO =	(TS) (K) (1.667) ----- (TIME) (VS) (PS) (AN)	= 98.3

APPENDIX II

ISOKINETIC CALCULATION SHEETS

Okeelanta Corporation - Boiler #12
Particulate Emissions Test Report

APPENDIX III

ENTHALPY CALCULATION SHEETS

ENTHALPY CALCULATION SHEET

PLANT : OKEELANTA
LOCATION: UNIT 12

RUN #: COMP-1
DATE : 01-31-91

	STEAM PRESSURE	STEAM TEMPERATURE	FEED WATER TEMPERATURE
	350	670	260
	340	670	
	340	660	
	360	660	
	340	670	
 AVERAGE	 346.0 PSIG	 666.0	 260.0
 P ABS =	 360.7 PSIA		
 ENTHALPY @	 700 'F AND	 360 PSIA =	 1364.1
ENTHALPY @	600 'F AND	360 PSIA =	1309.9
ENTHALPY @	666.0 'F AND	360 PSIA =	1345.7
 ENTHALPY OF FEED WATER =		 228.65	
AVERAGE ENTHALPY =		1117.0	BTU/LB OF STEAM

ENTHALPY CALCULATION SHEET

PLANT : OKEELANTA
LOCATION: UNIT 12

RUN #: COMP-2
DATE : 01-31-91

	STEAM PRESSURE	STEAM TEMPERATURE	FEED WATER TEMPERATURE
	350	660	260
	340	660	
	350	660	
	350	680	
	350	670	
	350	660	
AVERAGE	348.3 PSIG	665.0	260.0
P ABS =	363.0 PSIA		
ENTHALPY @	700 'F AND	360 PSIA =	1364.1
ENTHALPY @	600 'F AND	360 PSIA =	1309.9
ENTHALPY @	665.0 'F AND	360 PSIA =	1345.1
ENTHALPY OF FEED WATER =		228.65	
AVERAGE ENTHALPY =		1116.5	BTU/LB OF STEAM

ENTHALPY CALCULATION SHEET

PLANT : OKEELANTA
LOCATION: UNIT 12

RUN #: COMP-3
DATE : 02-01-91

	STEAM PRESSURE	STEAM TEMPERATURE	FEED WATER TEMPERATURE
	340	650	260
	350	660	
	340	650	
	360	680	
	350	660	
	340	660	
 AVERAGE	 346.7 PSIG	 660.0	 260.0
 P ABS =	 361.4 PSIA		
 ENTHALPY @	 700 'F AND	 360 PSIA =	 1364.1
ENTHALPY @	600 'F AND	360 PSIA =	1309.9
ENTHALPY @	660.0 'F AND	360 PSIA =	1342.4
 ENTHALPY OF FEED WATER =		 228.65	
AVERAGE ENTHALPY =		1113.8	BTU/LB OF STEAM

APPENDIX IV

HEAT INPUT CALCULATION SHEETS

HEAT INPUT CALCULATION SHEET

PLANT: OKEELANTA
 LOCATION: UNIT 12

RUN #: COMP-1
 DATE: 01-31-91

	STEAM INTEGRATOR READINGS	TIME	INTEGRATOR FACTOR
	-----	----	-----
END	741611	12: 35	100
BEGIN	740225	11: 30	LBS/HR STEAM
	-----	-----	-----
NET	1386	X 100 / 65	MINS = 127938

127938 LBS/HR STEAM / 55% EFF. = 232615 EQUIV.

232615 LBS/HR STEAM X (1117) BTU/LB = (259.8) BTU(e6)/HR

	OIL INTEGRATOR READINGS	TIME	GALS/HR
	-----	----	-----
END	847334	12: 35	
BEGIN	847059	11: 30	
	---	-----	
NET	275	GALLONS 65	MINS = 253.846 GPH

253.8462 GPH X 150,000 BTU/GAL (EST) = (38.077) BTU(e6)/HR

ALLOWABLE EMISSIONS

BAGASSE	<u>259.8</u>	X	<u>38</u>	.	2	=	44.4 LBS/HR
OIL		X	38	.	1	=	3.8 LBS/HR
TOTAL						=	48.2 LBS/HR

HEAT INPUT CALCULATION SHEET

PLANT: OKEELANTA
 LOCATION: UNIT 12

RUN #: COMP-2
 DATE: 01-31-91

	STEAM INTEGRATOR READINGS	TIME	INTEGRATOR FACTOR
	-----	----	-----
END	744575	15: 0	100
BEGIN	743044	13: 45	LBS/HR STEAM
NET	----- 1531	----- / 75	----- = 122480

122480 LBS/HR STEAM / 55% EFF. = 222691 EQUIV.

222691 LBS/HR STEAM X 1116 BTU/LB = 248.6 BTU(e6)/HR

	OIL INTEGRATOR READINGS	TIME	GALS/HR
	-----	----	-----
END	847865	15: 0	
BEGIN	847595	13: 45	
NET	----- 270	----- GALLONS 75	----- MINS = 216 GPH

216 GPH X 150,000 BTU/GAL (EST) = 32.4 BTU(e6)/HR

ALLOWABLE EMISSIONS

BAGASSE	248.6	-	32	X	.2	=	43.2	LBS/HR
OIL			32	X	.1	=	3.2	LBS/HR
TOTAL						=	46.5	LBS/HR

HEAT INPUT CALCULATION SHEET

PLANT: OKEELANTA
 LOCATION: UNIT 12

RUN #: COMP-3
 DATE: 02-01-91

	STEAM INTEGRATOR READINGS		TIME		INTEGRATOR FACTOR
	-----		----		-----
END	767658		12: 55		100
BEGIN	766187		11: 45		LBS/HR STEAM
	-----		-----		-----
NET	1471	X	100	/ 70	MINS = 126086

126086 LBS/HR STEAM / 55% EFF. = 229247 EQUIV.

229247 LBS/HR STEAM X 1114 BTU/LB = 255.3 BTU(e6)/HR

Avg = 254.6

	OIL INTEGRATOR READINGS		TIME		GALS/HR
	-----		----		-----
END	850545		12: 55		
BEGIN	850254		11: 45		
	---		---		
NET	291	GALLONS	70	MINS =	249.429 GPH

Avg = 239.758

249.4286 GPH X 150,000 BTU/GAL (EST) = 37.414 BTU(e6)/HR

Avg = 35.964
Total = 290.53

ALLOWABLE EMISSIONS

BAGASSE	255.3	-	37	X	.2	=	43.6	LBS/HR
OIL			37	X	.1	=	3.7	LBS/HR
TOTAL						=	47.3	LBS/HR

Okeelanta Corporation - Boiler #12
Particulate Emissions Test Report

APPENDIX V

EMISSION CALCULATION SHEETS

EMISSION CALCULATION SHEET

PLANT: OKEELANTA
 LOCATION: UNIT 12

RUN #: COMP-1
 DATE: 01-31-91

	SAMPLES		BLANKS	
	FILTER	BEAKER	FILTER	ACETONE
	-----	-----	-----	-----
NO. :	3760	206	3747	211
FINAL:	.8393	77.9397	.6434	79.1328
TARE :	.6472	77.9138	.6430	79.1327
	-----	-----	-----	-----
NET :	.1921	.0259	.0004	.0001/200ML

			VOLUME OF RINSE 235	
WEIGHT =	218.00			
RESIDUE =	.12			
Mn =	217.88 Mg	AS =	44.2	SQ FT
Qs =	3600(1-BWO)(VS)(AS)(17.64)(PS)/(TS)		=	3463483 DSCFH
CS =	(2.205 X 10 ⁻⁶) (Mn) / (VM STD)		=	1.229e-5 LBS/SCF
CS' =	0.0154 (Mn) / (VM STD)		=	.09 GRAINS / SCF
PMR =	(QS) (CS)		=	42.58 LBS/HR
LOAD =	MILLIONS OF BTU / HOUR INPUT		=	259.8 BTU e6 / HR
CS =	LBS / MILLION BTu		=	.164 LBS / BTu e6
ALLOWABLE			=	48.16 LBS/HR
			=	.185 LBS / BTu e6

EMISSION CALCULATION SHEET

PLANT: OKEELANTA
LOCATION: UNIT 12

RUN #: COMP-2
DATE: 01-31-91

	SAMPLES		BLANKS	
	FILTER	BEAKER	FILTER	ACETONE
	-----	-----	-----	-----
NO. :	3761	212	3747	211
FINAL:	.8052	77.1935	.6434	79.1328
TARE :	.6450	77.1772	.6430	79.1327
	-----	-----	-----	-----
NET :	.1602	.0163	.0004	.0001/200ML

		VOLUME OF RINSE 425	
WEIGHT =	176.50		
RESIDUE =	.21		
Mn =	176.29 Mg	AS =	44.2 SQ FT
Qs =	3600(1-BWO)(VS)(AS)(17.64)(PS)/(TS)		= 3381659 DSCFH
CS =	(2.205 X 10 ⁻⁶) (Mn) / (VM STD)		= 1.007e-5 LBS/SCF
CS' =	0.0154 (Mn) / (VM STD)		= .07 GRAINS / SCF
PMR =	(QS) (CS)		= 34.04 LBS/HR
LOAD=	MILLIONS OF BTU / HOUR INPUT		= 248.6 BTU e6 / HR
CS =	LBS / MILLION BTu		= .137 LBS/ BTu e6
ALLOWABLE			= 46.49 LBS/HR
			= .187 LBS/ BTu e6

EMISSION CALCULATION SHEET

PLANT: OKEELANTA
LOCATION: UNIT 12

RUN #: COMP-3
DATE: 02-01-91

	SAMPLES		BLANKS	
	FILTER	BEAKER	FILTER	ACETONE
	-----	-----	-----	-----
NO. :	3762	213	3747	211
FINAL:	.8379	78.0304	.6434	79.1328
TARE :	.6456	78.0124	.6430	79.1327
	-----	-----	-----	-----
NET :	.1923	.0180	.0004	.0001/200ML

WEIGHT = 210.30
RESIDUE = - .14

VOLUME OF RINSE 280

Mn = 210.16 Mg AS = 44.2 SQ FT

Qs = $3600(1-BWO)(VS)(AS)(17.64)(PS)/(TS)$ = 3876127 DSCFH
Avg = 3,573,756

CS = $(2.205 \times 10^{-6})(Mn) / (VM \text{ STD})$ = 1.042e-5 LBS/SCF

CS' = $0.0154 (Mn) / (VM \text{ STD})$ = .07 GRAINS / SCF

PMR = (QS) (CS) = 40.38 LBS/HR

LOAD = MILLIONS OF BTU / HOUR INPUT = 255.3 BTU e6 / HR

CS = LBS / MILLION BTu = .158 LBS / BTu e6

ALLOWABLE = 47.32 LBS/HR

= .185 LBS / BTu e6

APPENDIX VI

NOMENCLATURE SHEETS

NOMENCLATURE SHEET

PARTICULATE EMISSION TEST

Ar	Acetone residue - result of Blank evaporation.
AREA NOZZLE	Area of the nozzle in square feet.
AS	Area of the stack in square feet.
BDL	Below detectable limits
BWO	The amount of moisture in the flue gas.
% CO	Percent of carbon monoxide in the flue gas.
% CO2	Percent of carbon dioxide in the flue gas.
Cp	Pitot tube coefficient.
CS	The concentration in the stack in pounds per standard cubic foot.
Cs'	The concentration in the stack in grains per standard cubic foot.
DELTA H	The meter orifice differential.
DELTA H(ABS)	The meter orifice differential, absolute conditions in inches of mercury.
Dn (IN)	Diameter of the nozzle in inches.
DRY GAS IN	Temperature of the dry gas meter inlet degrees Farenheight.
DRY GAS OUT	Temperature of the dry gas meter outlet degrees Farenheight.
Ds (FT)	Diameter of the stack in feet.
E	The emission rate in pounds per million Btu derived by using F-Factor.
E (Heat Input)	The emission rate in pounds per million Btu derived by use of calculated heat input.
END METER	The dry gas meter reading at the end of the test.
F factor	The theoretical amount of air in dry standard cubic feet (DSCF) needed to combust a million Btu's worth of fuel.

Okeelanta Corporation - Boiler #12
Particulate Emissions Test Report

NOMENCLATURE (cont'd)

Filter Catch	The amount of particulate captured on the filter during testing.
INT. METER	The dry gas meter reading at the beginning of the test.
Md (DRY)	The dry molecular weight of the flue gas in pounds per pound mole.
MN	The amount of particulate collected by washing the nozzle, probe, and front half of the glassware, reported in milligrams.
MN'	The milligrams of particulate collected minus the blank.
Ms (WET)	Wet or actual molecular weight of the flue gas in pounds per pound mole.
% N2	The percent of nitrogen in the flue gas.
NO PTS	Number of traverse points.
% O2	Percent of oxygen in the flue gas.
P BAR	Barometric pressure at test location.
P STK	Static pressure of the stack in inches of water.
PMR	The emission rate in pounds per hour.
PS (ABS)	Absolute pressure conditions in the stack in inches of mercury.
Qs	The volumetric flow rate of the flue gas in dry standard cubic feet per hour.
SQ ROOT	The square root of each velocity head measurement.
SQRT DELTA P	The average of the square roots of the measured pressure drops.
Stack Temp or TS (°F)	The temperature of the stack in degrees Fahrenheit.
TS (°R)	The temperature of the stack in degrees Rankine.
T (Hot Box)	Temperature around the filter box, degrees Fahrenheit.
TM (°F)	Average temperature of the dry gas meter in degrees Fahrenheit.

NOMENCLATURE (cont'd)

TM (°R)	Average temperature of the dry gas meter in degrees Rankine.
VEL HEAD	The pressure drop measured across the pitot tubes.
VI (TOT)	The amount of water collected in the impingers in milliliters.
VM (CF)	The volume sampled through the dry gas meter in cubic feet.
VM STD	Volume sampled through the dry gas meter corrected to standard conditions.
VS	Velocity of the stack gas in feet per second.
VW STD	The amount of moisture collected, converted to standard cubic feet.
Y	Meter box calibration factor.
o	Sampling time in minutes.

APPENDIX VII

FIELD DATA SHEETS - UNIT OPERATING CONDITIONS

CAPACITY 150,000
INT. FACTOR 100
RUN 1 12-22

BOILER 1 12

POLLUTION COMPLIANCE TESTING
DATE: 1-31-91
TESTED BY: Eastmont Eng

TIME	STEAM INTERGRATOR	OIL METER		STEAM		EXHAUST READING LBS/HR.	FEED WATER		BOILER PRESSURE DROP								
		North	South	PRESS.	TEMP.		PRESS.	TEMP.	OVERFIRE AIR PRESS.	AIR HEATER AIR OUT	UNDERGRATE AIR PRESS.	WIND BOX PRESSURE	FURNACE PRESSURE	BLR. OUTLET PRESSURE	DUST COLLECTOR OUT.	SCRUBBER DIFF.	
1:45	743044	847595	one meter	350	660	125,000	640	260	14	14	14	14	14	14	14	14	14
2:00	743361			340	660	120,000	600	"									
2:15	743669			350	660	125,000	620	"									
2:30	743975			350	680	125,000	650	"									
2:45	744274			350	670	120,000	660	"									
3:00	744575	847865		350	660	120,000	660	"									

BOILER TEMPERATURE	
BOILER OUTLET	200 690 680 680 680
AIR HEATER GAS OUT	410 410 410 410 410
AIR HEATER AIR OUT	590 590 590 590 590
I.D. FAN	400 400 400 400 400
S.H. STEAM TEMP.	660 660 660 660 660

PANEL SETTINGS	
FURNACE PRESSURE	7
F.D. FAN PRESSURE	15
BAGASSE FEED	60%
UNDERGRATE AIR	90%
OVERFIRE AIR	45


TEST RESULTS

OIL USED	270	GALS.
TOTAL TEST TIME	75	MINS.
INTERGRATOR TIME	1531	COUNT
INTERGRATOR STEAM	120,460	P.P.H.
CHART READING	735,000	TOTAL
CHART AVERAGE	182,500	P.P.H.
I.D. FAN TURBINE	4400	RPM
STACK TEMPERATURE	140	°F
GRATE TEMPERATURE	600	°F
SCRUBBER WATER	est 600	G.P.M.

COMMENTS:
 (1) Mill speed 80 80 F.P.M.
 (2) using one oil burner.

Allowed =
 Actual =

PLANT READINGS BY *[Signature]*
 % OF CAPACITY



CAPACITY 150,000
 INT. FACTOR 120
 RUN 1 1A-3

BOILER 1 12

POLLUTION COMPLIANCE TESTING
 DATE: 2-1-97
 TESTED BY: EASTMOUNT ENG

TIME	STEAM INTERGRATOR	OIL METER		STEAM		CLAS. READING LBS/HR.	FEED WATER		BOILER PRESSURE DROP									
		NORTH	SOUTH	PRESS.	TEMP.		PRESS.	TEMP.	OVERFIRE AIR PRESS.	AIR HEATER AIR OUT	UNDERGRATE AIR PRESS.	WIND BOX PRESSURE	FURNACE PRESSURE	BLR. OUTLET PRESSURE	DUST COLLECTOR OUT.	SCRUBBER DIFF.		
11:45 AM	766167	850254	ONS	340	650	122,000	630	260	1.4	1.4	1.4	1.4	1.4	1.4	1.4	1.4	1.4	1.4
12:00 PM	766505		HEATER	350	660	125,000	620	"	1.8	1.9	1.8	1.8	1.8	1.8	1.8	1.8	1.8	1.8
12:15	766825			340	650	128,000	600	"	.40	.50	.50	.50	.50	.50	.50	.50	.50	.50
12:30	767134			360	680	125,000	620	"	2.0	2.3	2.0	2.3	2.3	2.3	2.3	2.3	2.3	2.3
12:45	767450			350	660	125,000	640	"	.60	.60	.60	.60	.60	.60	.60	.60	.60	.60
12:55	767658	850545	X	340	660	125,000	630	"	4.3	4.3	4.3	4.3	4.3	4.3	4.3	4.3	4.3	4.3

BOILER TEMPERATURE

BOILER OUTLET	670	660	660	680	680
AIR HEATER GAS OUT	400	400	400	410	410
AIR HEATER AIR OUT	480	580	580	585	580
I.D. FAN	390	380	380	390	390
S.H. STEAM TEMP.	650	660	650	680	660

PANEL SETTINGS

FURNACE PRESSURE	6.5
F.D. FAN PRESSURE	15
BAGASSE FEED	60%
UNDERGRATE AIR	100%
OVERFIRE AIR	11.5%


TEST RESULTS

OIL USED	297	GALS.
TOTAL TEST TIME	70	MINS.
INTERGRATOR TIME	1471	COUNT
INTERGRATOR STEAM	126,086	P.P.H.
CHART READING	250,000	TOTAL
CHART AVERAGE	125,000	P.P.H.
I.D. FAN TURBINE	4800	RPM
STACK TEMPERATURE	138	°F
GRATE TEMPERATURE	650	°F
SCRUBBER WATER	est 600	G.P.M.

COMMENTS:
 (1) Mill speed 65 "A" "B" 65 F.P.H.
 (2) using oil burner @ 60%

Allowed =
 Actual =

PLANT READINGS BY *Ray Dahn*
 % OF CAPACITY



BAILEY RECORDER

Meter No.

Date

Integrator
Off On

FEB 1 - 1991

BAILEY METER COMPANY
CLEVELAND, OHIO

Chart No.
180F60P30L

Galley # 12-800-190

R-6
B-8
C-12

12-3

START
11:35

761570

Okeelanta Corporation - Boiler #12
Particulate Emissions Test Report

APPENDIX VIII

FIELD DATA SHEETS - STACK TESTING

P

FIELD DATA SHEET
GENERAL INFORMATION

Plant:	<u>OKEE/ANTA</u>	Run #:	<u>COMP-1</u>
Location:	<u>UNIT 12</u>	Date:	<u>31 JAN 91</u>
Ds (ft):	<u>7.5</u>	No. Points:	<u>24</u>
Dn (in):	<u>.305</u>	Test Length:	<u>60</u>
Filter #:	<u>3760</u>	End Meter Reading:	<u>687.772</u>
Cp:	<u>.84</u>	Int Meter Reading:	<u>647.427</u>
P bar:	<u>30.06</u>	Begin Time:	<u>11:30</u>
P stack:	<u>.15</u>	End Time:	<u>12:35</u>

IMP-1 (INT)	<u>100 ml</u>	IMP-1 (FINAL)	<u>254</u>
IMP-2 (INT)	<u>100 ml</u>	IMP-2 (FINAL)	<u>120</u>
IMP-3 (INT)	<u>0 ml</u>	IMP-3 (FINAL)	<u>2</u>
IMP-4 (INT)	<u>500.0g</u>	IMP-4 (FINAL)	<u>512</u>

	TEST 1	TEST 2	TEST 3
% CO2	<u>12.2</u>	_____	_____
% O2	<u>8.0</u>	_____	_____
% CO	<u>0</u>	_____	_____

Project Director:	<u>S. MacKay</u>	Field Laboratory:	<u>MacKay/Wescott</u>
Meter Box Operator:	<u>M. Wescott</u>	Chain of Custody:	<u>S. MacKay</u>
Probe Operator:	<u>R. Gibson</u>	Plant Coordinator:	<u>G. DeJANE</u>
Orsat Analyst:	<u>S. MacKay</u>	Agency Rep:	<u>C. Culliver</u>

Comments:

TRAVERSE DATA SHEET

Page 2 of 2

Sampling time per point: 2.5 min/pt

Plant: O'Keefe Lanta

Run #: Comp-1

Location: Unit # 12

Date: _____

	Trav. No.	Delta P	Delta H	Meter Reading	DGM In	DGM Out	Hot Box	Impg Temp	Stack Temp	Vac
B				667.425						
4.0	1	.22	1.52	668.85	90	86	270	69	138	4.0
8.0	2	.24	1.66	670.495	90	86	270	65	137	4.5
	3	.20	1.80	672.018	92	87	262	67	138	5.0
8.0	4	.27	1.80	673.91	93	87	250	68	139	6.0
	5	.20	1.80	675.635	94	88	257	68	137	6.0
	6	.24	1.66	677.335	94	88	264	67	139	6.0
8.0	7	.25	1.73	679.02	95	89	250	66	140	6.0
	8	.20	1.80	680.715	95	89	255	66	140	6.0
8.0	9	.28	1.93	682.418	96	90	251	66	139	7.0
	10	.25	1.93	684.27	97	90	245	65	140	7.5
8.0	11	.27	1.80	686.03	97	92	243	66	139	7.5
	12	.26	1.80	687.772	97	91	265	66	139	7.5

Relationship: _____
 Box #: _____ Y: _____ Delta H@: _____
 Start Time: _____ End Time: _____
 Pre Leak Ck: _____ CFM @ _____ "Hg
 Mid Leak Ck: _____ CFM @ _____ "Hg (Vol: _____)
 Post Leak Ck: None CFM @ 7.5 "Hg
 Pitot Leak Ck: _____ @ _____ "H2O
 Box Oper: _____ Probe Oper: _____

TRAVERSE DATA SHEET

Page 1 of 2

Sampling time per point: 2.5 min/pt

Plant: Okeelanta

Run #: Comp-1

Location: Unit # 12

Date: 31 JAN 91

Trav. No.	Delta P	Delta H	Meter Reading	5 DGM In	6 DGM Out	1 Hot Box	2 Impg Temp	3 Stack Temp	Vac
			647.427						
A 1	0.18	1.24	649.03	80	79	248	63	138	2.0
2	0.24	1.66	650.64	79	79	253	64	138	2.0
3	0.25	1.72	652.95	83	79	241	66	139	2.5
4	0.27	1.86	654.01	85	80	259	66	139	3.0
6.0 5	0.26	1.80	655.745	86	80	268	65	139	3.0
6	0.23	1.59	657.411	87	81	266	66	139	3.0
7	0.23	1.59	658.88	87	82	251	66	139	3.0
8.0 8	0.24	1.66	660.69	89	83	241	67	138	3.0
9	0.24	1.66	662.335	89	83	244	68	140	3.0
8.0 10	0.24	1.66	663.95	90	84	266	66	138	3.0
11	0.24	1.66	665.71	91	84	270	66	139	4.0
8.0 12	0.25	1.72	667.235	91	85	265	66	137	4.5

Relationship: 6.9
 Box #: 4 Y: 1.001 Delta H@: 2.03
 Start Time: 1130 End Time: _____
 Pre Leak Ck: dead CFM @ 15 "Hg
 Mid Leak Ck: dead CFM @ 4.5 "Hg (Vol: _____)
 Post Leak CK: _____ CFM @ 9.2 "Hg
 Pitot Leak CK: dead @ 9.2 "H2O
 Box Oper: M. Wescoff Probe Oper: B. Gibson

FIELD DATA SHEET
GENERAL INFORMATION

Plant:	<u>OKEE/ANTA</u>	Run #:	<u>COMP-2</u>
Location:	<u>UNIT 12</u>	Date:	<u>31 JAN 91</u>
Ds (ft):	<u>7.5</u>	No. Points:	<u>24</u>
Dn (in):	<u>.305</u>	Test Length:	<u>60 MIN</u>
Filter #:	<u>3761</u>	End Meter Reading:	<u>608.150 728.351</u>
Cp:	<u>.84</u>	Int Meter Reading:	<u>628 638.150</u>
P bar:	<u>30.06</u>	Begin Time:	<u>13:45</u>
P stack:	<u>.15</u>	End Time:	_____

IMP-1 (INT)	<u>100 ML</u>	IMP-1 (FINAL)	<u>254</u>
IMP-2 (INT)	<u>100 ML</u>	IMP-2 (FINAL)	<u>125</u>
IMP-3 (INT)	<u>0 ML</u>	IMP-3 (FINAL)	<u>2</u>
IMP-4 (INT)	<u>500.0 g</u>	IMP-4 (FINAL)	<u>515.05</u>

	TEST 1	TEST 2	TEST 3
% CO2	_____	_____	_____
% O2	_____	_____	_____
% CO	_____	_____	_____

Project Director:	<u>S. MACKAY</u>	Field Laboratory:	<u>Mackay/Wescott</u>
Meter Box Operator:	<u>M. WESCOTT</u>	Chain of Custody:	<u>S. Mackay</u>
Probe Operator:	<u>R. GIBSON</u>	Plant Coordinator:	<u>G. DEVANE</u>
Orsat Analyst:	<u>S. MACKAY</u>	Agency Rep:	<u>C. COLLIVER</u>

Comments:

TRAVERSE DATA SHEET

Page 1 of 2

Sampling time per point: 2.5 min / pt

Plant: Okechanta

Run #: Comp - 2

Location: Unit # 12

Date: 31 Jan 91

Trav. No.	Delta P	Delta H	Meter Reading	DGM In	DGM Out	Hot Box	Impg Temp	Stack Temp	Vac
			688.15						
1	.20	1.40	689.71	85	83	264	68	138	1.0
8.5 2	.22	1.54	691.31	86	84	270	68	140	1.0
3	.20	1.82	693.02	87	84	267	68	140	1.0
8.0 4	.27	1.90	694.765	88	84	257	67	140	1.0
5	.20	1.82	694.49	90	86	255	67	139	1.0
8.5 6	.23	1.81 1.61	698.23	90	85	252	66	140	1.0
7	.22	1.54	699.88	91	86	249	68	139	1.0
8.0 8	.23	1.61	701.52	92	88	260	67	140	1.0
9	.23	1.61	703.145	92	86	269	66	140	1.0
8.0 10	.24	1.68	704.78	92	87	265	66	140	1.0
11	.23	1.61	706.415	93	87	267	59	139	1.5
12	.23	1.61	708.055	92	88	255	58	141	2.0

Relationship: 7.0
 Box #: 4 Y: 1.001 Delta H: 2.03
 Start Time: _____ End Time: _____
 Pre Leak Ck: _____ CFM @ _____ "Hg
 Mid Leak Ck: _____ CFM @ _____ "Hg (Vol: _____)
 Post Leak Ck: _____ CFM @ _____ "Hg
 Pitot Leak Ck: dead @ 5.5 "H2O
 Box Oper: M. W. Scott Probe Oper: B. Gibson

TRAVERSE DATA SHEET

Page 2 of 2

Sampling time per point: 2.5 min/pt

Plant: Coke Plant

Run #: Comp-2

Location: Unit #12

Date: 31 Jan 91

Trav. No.	Delta P	Delta H	Meter Reading	DGM In	DGM Out	Hot Box	Impg Temp	Stack Temp	Vac
			708.75						
1	.23	1.61	709.74	89	87	265	68	141	2.0
8.0 2	.24	1.68	711.385	91	88	270	66	143	2.0
3	.25	1.75	713.085	91	87	259	67	144	2.5
8.0 4	.26	1.82	714.795	92	88	252	67	144	3.0
5	.25	1.75	716.49	93	88	252	64	144	3.0
8.0 6	.24	1.68	718.195	94	89	253	63	143	3.0
7	.25	1.75	719.90	94	89	259	62	143	3.0
8.0 8	.25	1.75	721.59	96	90	264	63	141	3.5
9	.25	1.75	723.27	95	90	268	66	143	3.5
8.0 10	.25	1.75	724.95	95	90	270	66	142	3.5
11	.25	1.75	726.63	95	90	270	67	143	3.5
8.0 12	.26	1.82	728.351	96	91	265	67	143	4.0

Relationship: 2.0
 Box #: 4 Y: 1.001 Delta H@: 2.03
 Start Time: _____ End Time: _____
 Pre Leak Ck: _____ CFM @ _____ "Hg
 Mid Leak Ck: _____ CFM @ 2.0 "Hg (Vol: _____)
 Post Leak Ck: dead CFM @ 4.0 "Hg
 Pitot Leak Ck: _____ @ _____ "H2O
 Box Oper: M. Wescott Probe Oper: B. Gibson

FIELD DATA SHEET
GENERAL INFORMATION

Plant:	<u>OKEEJANTA</u>	Run #:	<u>COMP-3</u>
Location:	<u>UNIT 12</u>	Date:	<u>1 FEB 91</u>
Ds (ft):	<u>7.5</u>	No. Points:	<u>24</u>
Dn (in):	<u>3.05</u>	Test Length:	<u>60 min</u>
Filter #:	<u>3762</u>	End Meter Reading:	<u>774.680</u>
Cp:	<u>.84</u>	Int Meter Reading:	<u>729.520</u>
P bar:	<u>30.10</u>	Begin Time:	<u>11:45</u>
P stack:	<u>1</u>	End Time:	<u>12:55</u>

IMP-1 (INT)	<u>100 mL</u>	IMP-1 (FINAL)	<u>270</u>
IMP-2 (INT)	<u>100 mL</u>	IMP-2 (FINAL)	<u>125</u>
IMP-3 (INT)	<u>0 mL</u>	IMP-3 (FINAL)	<u>3</u>
IMP-4 (INT)	<u>500.0g</u>	IMP-4 (FINAL)	<u>515.2</u>

	TEST 1	TEST 2	TEST 3
% CO2	<u>11.7</u>	_____	_____
% O2	<u>8.5</u>	_____	_____
% CO	<u>0</u>	_____	_____

Project Director:	<u>S. MacKay</u>	Field Laboratory:	<u>S. MacKay/WESTT</u>
Meter Box Operator:	<u>M. Westcott</u>	Chain of Custody:	<u>S. MacKay</u>
Probe Operator:	<u>B. Gibson</u>	Plant Coordinator:	<u>G. Devane</u>
Orsat Analyst:	<u>S. MacKay</u>	Agency Rep:	<u>C. Culliver</u>

Comments:

TRAVERSE DATA SHEET

Page 2 of 2

Sampling time per point: 2.5 min/pt

Plant: Okeechinta

Run #: Camp-3

Location: Unit #12

Date: 1 Feb 91

	Trav. No.	Delta P	Delta H	Meter Reading	DGM In	DGM Out	Hot Box	Impg Temp	Stack Temp	Vac
B				752.496						
3.0	1	.23	1.61	754.12	82	79	266	66	139	1.0
3.5	2	.29	2.32 ^{2.03}	755.95	84	80	265	59	137	2.0
	3	.31	2.17	757.88	85	80	246	60	140	2.0
8.0	4	.33	2.31	759.79	88	81	242	62	140	2.0
	5	.33	2.31	761.71	88	81	256	62	146	2.0
8.5	6	.30	2.10	763.545	89	82	270	63	139	2.0
	7	.32	2.24	765.46	89	82	263	61	138	2.5
8.5	8	.35	2.45	767.44	90	83	261	62	138	3.0
	9	.36	2.52	769.46	90	83	258	62	139	3.0
8.5	10	.36	2.52	771.47	91	84	256	64	139	3.0
	11	.27	1.89	773.265	90	84	253	63	139	2.5
	12	.15	1.05	774.68	89	84	256	65	139	1.5

Relationship: 7.0
 Box #: 4 Y: 1.001 Delta H@: 2.03
 Start Time: _____ End Time: _____
 Pre Leak Ck: _____ CFM @ _____ "Hg
 Mid Leak Ck: dead CFM @ 2.0 "Hg (Vol: _____)
 Post Leak Ck: dead CFM @ 3.0 "Hg
 Pitot Leak Ck: _____ @ _____ "H2O
 Box Oper: _____ Probe Oper: _____

TRAVERSE DATA SHEET

Page 1 of 2

Sampling time per point: 2.5 min/pt

Plant: okeekanta

Run #: Comp-3

Location: Unit #12

Date: 1 Feb 91

	Trav. No.	Delta P	Delta H	Meter Reading	DGM In	DGM Out	Hot Box	Impg Temp	Stack Temp	Vac
A				729.52						
10.02	1	.29	2.03	736.51	72	71	270	69	139	1.0
9.5	2	.31	2.17	733.38	73	71	259	63	138	1.0
	3	.35	2.45	735.355	76	72	246	66	139	1.0
	4	.37	2.59	737.39	78	73	246	67	139	1.0
6.5	5	.35	2.45	739.29	79	73	267	67	140	1.0
	6	.33	2.31	741.23	80	73	265	66	140	1.0
6.5	7	.31	2.17	743.09	81	75	268	62	138	1.0
	8	.32	2.24	744.96	82	75	267	60	138	1.5
5	9	.32	2.24	746.855	83	76	270	59	138	1.5
	10	.32	2.24	748.745	83	76	265	58	140	2.0
8.5	11	.30	2.10	750.58	84	77	264	59	138	2.0
	12	.30	2.10	752.362	84	77	268	59	140	2.0

Relationship: 7.0
 Box #: 4 Y: 6.001 Delta H@: 2.03
 Start Time: 11:45 End Time: 11:4
 Pre Leak Ck: dead CFM @ 15 "Hg.
 Mid Leak Ck: 0 CFM @ 2 "Hg (Vol: _____)
 Post Leak Ck: 0 CFM @ 3 "Hg
 Pitot Leak Ck: dead @ 6.5 "H2O
 Box Oper: M. W. Kasoff Probe Oper: B. Gibson

APPENDIX IX
EQUIPMENT CALIBRATION SHEETS

POST
METER BOX CALIBRATION SHEET

BOX #: 4
PRES BAR: 30.02

DATE: 2-11-91
VACUUM: 10IN HG

RUN #	VOLUME WET	VOLUME DRY	DELTA H	DELTA H /13.6	PRES BAR (ABS)	TIME (MINS)
1	10.00	10.089	1.95	.143	30.16	13.39
2	10.00	10.353	1.95	.143	30.16	13.73
3	10.00	10.333	1.95	.143	30.16	13.73

RUN #	TEMP WET (°F)	TEMP DRY INLET	TEMP DRY OUT	TEMP DRY (AVG)	Y	DELTA H @
1	65.0	85.7	80.0	82.8	1.020	1.87
2	65.0	87.7	81.7	84.7	.9973	1.96
3	65.0	88.7	82.3	85.5	1.001	1.96
AVERAGE					1.006	1.93

PRE CAL Y = 1.0010 % DIFFERENCE = .50 %
ALLOWABLE = 5.00 %

FORMULAS:

Y=

DELTA H @=

$$\frac{(V w) (P b) (T d)}{(V d) (P b \text{ ABS}) (T w)} \quad \frac{0.0317 (\text{DELTA H})}{(P b) (T d)} \quad * \quad \left[\frac{(T w) (\text{TIME})^2}{(V w)} \right]$$

S. MacKAY

CALIBRATION BY:

METER BOX CALIBRATION SHEET

BOX NUMBER: 4
 PRESS BAR : 30.04

DATE: 10 SEPT 1990
 DUE: 10 MAR 1991

RUN #	VOLUME WET	VOLUME DRY	DELTA H	DELTA H /13.6	PRES BAR (ABS)	TIME (MINS)
1	5	5.037	.50	.0368	30.08	13.80
2	5	5.043	1.00	.0735	30.11	9.55
3	10	10.190	1.50	.1103	30.15	15.34
4	10	10.273	2.00	.1471	30.19	13.46
5	10	10.330	3.00	.2206	30.26	11.69
6	10	10.400	4.00	.2941	30.33	9.64

RUN #	TEMP WET ('F)	TEMP DRY INLET	TEMP DRY OUT	TEMP DRY (AVG)	Y	DELTA H @
1	69.3	82.3	77.3	79.8	1.011	2.09
2	69.7	83.7	78.3	81.0	1.010	2.00
3	70.0	86.7	80.3	83.5	1.005	1.93
4	70.0	89.3	82.7	86.0	.9979	1.97
5	69.3	91.7	83.3	87.5	.9940	2.21
6	69.0	94.7	85.3	90.0	.9900	1.99
AVERAGE					1.001	2.03

MAX % DEVIATION 1.10
 ALLOWABLE % DEV 2.00

FORMULAS:

$$Y = \frac{(V_w)(P_b)(T_d)}{(V_d)(P_b \text{ ABS})(T_w)}$$

$$\text{DELTA H @} = \frac{0.0317 (\text{DELTA H})}{(P_b)(T_d)} * \left[\frac{(T_w)(\text{TIME})^2}{(V_w)} \right]$$

CALIBRATION BY:

From Computer Disc
 SCOTT LAWTON
 13-Feb-90

THERMOCOUPLE CALIBRATION SHEET

SET #: METER BOX #4 - IN

DATE: 9/11/85

STANDARD ('F)	THERMOCOUPLE ('F)	% DIFFERENCE
32	27	1.02
63	57	1.15
204	201	.45
	MAXIMUM	1.15
	ALLOWABLE	1.50

SET #: METER BOX #4 - OUT

DATE: 9/11/85

STANDARD ('F)	THERMOCOUPLE ('F)	% DIFFERENCE
32	27	1.02
63	57	1.15
204	202	.30
	MAXIMUM	1.15
	ALLOWABLE	1.50

C. LODI

CALIBRATION BY: _____

CARL POE CO., INC.

99 REINERMAN ST. • HOUSTON, TEXAS 77007 • 713-861-3816

February 19, 1990

Eastmount Engineering
420 Main
Walpole, MA 02081

Dear Sirs:


This is to certify that your AL-19 American Wet Test Meter, serial no. P-468, has been calibrated with an American five foot bell prover, serial no. 2260. It is traceable to the Bureau of Standards, reference no. 106870, PI-TAPE.

Test Results are as follows:

<u>FLOW RATE</u>	<u>% OF ERROR</u>
60 CFH	+0.3%
30 CFH	0.0%
15 CFH	0.0%

Sincerely,

CARL POE CO., INC.



Carl W. Poe
CWP/mp

THERMOCOUPLE CALIBRATION SHEET

SET #: 8'-1

DATE: 10-25-85

REFERENCE MERCURY/GLASS

STANDARD ('F)	THERMOCOUPLE ('F)	ABSOLUTE OF % DEVIATION
74	72	.37
210	205	.75
400	409	1.05
	MAXIMUM DEVIATION	1.05
	ALLOWABLE	1.50

SET #: 8.5'-1

DATE: 11-15-85

STANDARD ('F)	THERMOCOUPLE ('F)	ABSOLUTE OF % DEVIATION
66	63	.57
170	170	0
211.5	215	.52
	MAXIMUM DEVIATION	.57
	ALLOWABLE	1.50

CALIBRATION BY:

G. ZWILLING

NOZZLE CALIBRATION SHEET

PROJECT NAME: OKEE/ANTA

PROJECT NUMBER: 90 102

POINT# NOZZLE# 1/4-1 NOZZLE # 1/4-2 NOZZLE# _____ NOZZLE # _____

1 .305 .256 _____ _____

2 .305 .258 _____ _____

3 .305 .267 _____ _____

AVG. .305 .257 _____ _____

SEAN MacFARLANE
CALIBRATED BY:

3 DEC 90
DATE:

NOZZLE CALIBRATION SHEET

PROJECT NAME: OKEELENTA

PROJECT NUMBER: 90-102

POINT#	NOZZLE# <u>5/16-3</u>	NOZZLE # <u>9/16-14</u>	NOZZLE# <u>1/4-3</u>	NOZZLE # <u>1/4-1</u>
1	<u>.316</u>	<u>.313</u>	<u>.251</u>	<u>.250</u>
2	<u>.314</u>	<u>.312</u>	<u>.249</u>	<u>.251</u>
3	<u>.315</u>	<u>.311</u>	<u>.250</u>	<u>.251</u>
AVG.	<u>.315</u>	<u>.312</u>	<u>.250</u>	<u>.251</u>

SEAN MCKAY
CALIBRATED BY:

3 DEC 90
DATE: